



**UTAH RADIOACTIVE MATERIAL LICENSE (RML UT2300249)**  
**UPDATED SITE-SPECIFIC PERFORMANCE ASSESSMENT**  
**SUPPLEMENTAL RESPONSE TO ROUND 1 INTERROGATORIES**

**February 6, 2015**

**For**  
**Utah Division of Radiation Control**  
195 North 1950 West  
Salt Lake City, UT 84114-4850

**EnergySolutions, LLC**  
423 West 300 South, Suite 200  
Salt Lake City, UT 84101

**TABLE OF CONTENTS**

<b>Section</b>		<b>Page</b>
<b>1.0</b>	<b>INTRODUCTION</b>	<b>1-1</b>
<b>2.0</b>	<b>NATIONAL ENGINEERED COVER STUDY</b>	<b>2-1</b>
<b>3.0</b>	<b>CLIVE'S SITE-SPECIFIC EXAMPLES OF CLAY BARRIER PROTECTION</b>	<b>3-1</b>
3.1	11e.(2) Embankment Clay Barrier	3-3
3.2	LARW Embankment Clay Barrier	3-8
3.3	Mixed Waste Test Pad Clay Barrier	3-8
3.4	Cover Test Cell Clay Barrier	3-11
<b>4.0</b>	<b>SUMMARY AND CONCLUSIONS</b>	<b>4-1</b>
<b>5.0</b>	<b>REFERENCES</b>	<b>5-1</b>
	<b>APPENDIX A - In-Field Density and Permeability Tests</b>	<b>A-1</b>

## 1. INTRODUCTION

EnergySolutions operates a low-level radioactive waste (LLRW) disposal facility west of the Cedar Mountains in Clive, Utah. Clive is located along Interstate-80, approximately 3 miles south of the highway, in Tooele County. The facility is approximately 50 miles east of Wendover, Utah and approximately 75 highway miles west of Salt Lake City, Utah. The facility sits at an elevation of 4,275 feet (ft) above mean sea level (amsl).

On February 14, 2011, EnergySolutions requested concurrence from the Utah Division of Radiation Control (Division) that previous licensing activities be allowed for the receipt and disposal of processed ion-exchange resin waste on a large-scale at the Clive facility (Shrum, 2011a and Shrum, 2011b). The Division reviewed EnergySolutions' analysis supporting this request and determined that EnergySolutions could receive processed ion-exchange resin waste up to 40,000 cubic feet per year. However, in order to receive processed ion-exchange resin waste at volumes greater than 40,000 cubic feet per year, the Division required EnergySolutions to conduct new performance assessment analyses that include

*“prediction of nuclide concentration and peak dose (at the time peak dose would occur) using updated dose conversion factors, and a suggested model time frame of 10,000 years, as well as any need to revisit/update the waste source term, receptor and exposure pathways”* (Lundberg, 2011).

While the ultimate quantity of processed ion-exchange resin waste that may eventually be disposed is unknown, EnergySolutions recognizes that UAC R313-25-9(1)(c) supports the Division's requirement for an updated site-specific Performance Assessment in the event that the total disposal volume of processed ion-exchange resin waste *“will result in greater than 10 percent of the total site source term over the operational life of the facility”* [UAC R313-25-9(1)(c)].

Additionally, in response to the challenges EnergySolutions experienced in constructing and monitoring its rock armor Cover Test Cell, the Division further directed that EnergySolutions design and assess the performance of an evapotranspirative cover technology (or mulch) using the more robust HYDRUS model (in place of the EPA-HELP model) (DRC, 2012).

In compliance with these requirements and in conjunction with EnergySolutions' application to renew Radioactive Material License UT2300249 (EnergySolutions, 2015; Appendix P), EnergySolutions submitted to the Division on October 8, 2012 an updated site-specific Performance Assessment, which includes:

- Analysis of additional subsurface fate and transport of LLRW contaminants leached from the Embankment via contact with precipitation that has infiltrated through new evapotranspirative cover designs as required in DRC (2012); and transported to a well at the point of compliance 90 feet from the outside edge of the LLRW material in the Class A West (CAW) Embankment;

- Modeling of expected groundwater well concentrations and comparison to groundwater protection levels (GWPLs) for the Permit-required Time of Compliance of 500 years following embankment closure, projected peak groundwater well concentrations for each radionuclide for a Performance Period of 10,000 years following embankment closure, and projected peak doses to the general public for a Performance Period of 10,000 years following embankment closure, as required in Lundberg (2011) and Lundberg (2014a);
- Modeling of expected exposures and resulting doses to credible hypothetical inadvertent industrial intruders within a Time of Compliance of 10,000 years following embankment closure (as required to mirror those modeled in the depleted uranium Performance Assessment per Lundberg, [2014b]);
- Evaluation of additional radionuclides that were not included in prior Class A Performance Assessments conducted in support of EnergySolutions' Clive-based licenses (see Table A-1 of EnergySolutions, 2015; Appendix P), as required by Lundberg (2011); and
- Justification for renewal of EnergySolutions' Radioactive Material License UT2300249, as required by Lundberg (2011).

On June 7, 2013, EnergySolutions received from the Division a Round 1 Request for Information regarding the updated site-specific Performance Assessment. Responses to the Round 1 Interrogatories and a revised Report were submitted to the Division December 30, 2013 (EnergySolutions, 2013b). Following review of EnergySolutions' responses to the Round 1 Interrogatories, the Division requested additional information via a Round 2 set of Interrogatories (dated July 2, 2014). Instead of employing the traditional list format historically used by the Division and EnergySolutions, the Round 2 interrogatories were placed contextually throughout the revised Report (previously submitted to the Division in conjunction with EnergySolutions' responses to the Round 1 interrogatories).

Following receipt of the Round 2 Interrogatories, EnergySolutions and Division staff met on July 17, 2014 and November 13, 2014 to agree upon an acceptable format for responses. As a result of these meetings, it was decided that responses to the Division's Round 2 Interrogatories would be contextually addressed within the Report and expanded Round 1 Interrogatory responses. EnergySolutions submitted revision 2 of the updated site-specific Performance Assessment as a comprehensive compilation of applicable legacy activities and expanded responses to Round 1 Interrogatories (EnergySolutions, 2015; Appendix P).

A major fraction of the Division's Round 1 and round 2 Interrogatories referenced implications a findings from a 2010 U.S. Nuclear Regulatory Commission (NRC) authorized study of changes in the post-construction hydrogeologic properties of the final covers at test facilities and operating waste containment facilities. While addressed therein, EnergySolutions has included herein site-specific examples of their ability to protect clay barriers from the impacts of freeze-thaw cycles.

## 2. NATIONAL ENGINEERED COVER STUDY


The CAW Embankment cover is designed and modeled to limit the amount of precipitation ultimately entering the disposed waste region, leaching within the waste mass, and the potential flux of contaminants to groundwater. As a result, the updated site-specific Performance Assessment demonstrates that the CAW cover is an important component in the Embankment's ability to satisfy the required performance objectives (EnergySolutions, 2015; Appendix P).

In recognition of the overall importance of cover designs in the ultimate performance of disposal embankments, NRC authorized a study in 2010 of the post-construction (up to approximately 9 years) hydrogeologic properties of the final covers at test facilities and operating waste containment facilities, as presented in Figure 2-1 (Benson et al., 2011). The Study included field tests, sample collection, laboratory tests, and data analyses from sites operating in a wide range of meteorological and hydrogeologic conditions. While selecting similar arid-permeable geohydraulic/meteorologic-modeled sites similar to Clive, Benson et al. (2011) statistical analysis and in-service characteristic distributions also included humid-permeable and humid-impermeable sites (dissimilar to Clive).

In the Study, test sections from various in-service covers were exhumed to evaluate how the engineering properties of the cover materials had changed during their service life. Field tests were conducted and samples were collected and tested in the laboratory. The Study's objectives included:

- characterization of changes in the engineering properties of the cover materials directly relevant to assessing hydrologic effectiveness,
- identification of conditions that induce changes in the engineering properties of cover materials and ultimately affect percolation into waste,
- identification of soil types and design and construction approaches that result in covers that are less prone to temporal change and therefore have more predictable performance, and
- recommendation of approaches to verify the hydrologic performance of final covers.

A diverse group of field sites were selected in the Study to represent a broad range of climatological conditions, as well as types of soil and vegetation. The average annual precipitation of the Study sites ranged from 119 mm/year (Apple Valley, CA) to 1,263 mm/year (Albany, GA). Appreciable snowfall was observed at 6 sites (Helena and Polson, MT; Omaha, NE; Cedar Rapids, IA; Monticello, UT; and Underwood, ND). Similarly, the Study included a broad variety of cover designs for a wide range of waste types, including municipal solid waste, hazardous waste, low-level radioactive waste, and mixed waste.



**Figure 2-1. Locations of NRC's cover study sites, (Benson et al., 2011; pg. 2-2)**

Of the 27 in-service covers evaluated, 15 were store-and-release covers (equivalent to CAW's evapotranspirative cover). Nine of the store-and-release covers were monolithic in design (i.e., a thick layer of finer textured soil overlain by topsoil) and six employed a simple two-layer fine over-coarse design, constructed to enhance the storage capacity of the overlying finer-textured layer. Additionally, the store-and-release covers were vegetated with a mixture of annual and perennial grass mixtures. Similarly, only 4 of the sites Benson et al (2011) studied are in arid-permeable geohydraulic/meteorologic-modeled sites similar to Clive. The wide differences in meteorologic and geohydraulic conditions of Benson et al. (2011) are representative in the wide cover performance distributions measured therein.

Prior to field testing, a minimum of 300 mm of surface soil was removed so that the tests were conducted directly on the storage layer or the barrier layer (as opposed to any present surface layer). Hydraulic conductivities were assumed to represent conditions at saturation (although, not a representative condition found in any of Clive's in-service covers). In-situ field hydraulic conductivity tests were conducted using sealed double-ring infiltrometers and borehole permeameters. As illustrated in Figures 2-2 and 2-3, these tests assumed an infinite volume of infiltration precipitation available in the storage or barrier layers.

The hydraulic conductivities of the various cover soil layers were found to be consistent with the sequence and method in which the layers were placed and exposed while in service. For example, clay barrier layers are generally placed with low hydraulic conductivities, whereas storage layers are placed to promote root development and storage capacity. As such, in-service storage layers were observed as having hydraulic conductivities with a geometric mean =  $1.7 \times 10^{-6}$  m/s. By comparison, in field hydraulic conductivities of clay barriers were observed as having a geometric mean value of  $6 \times 10^{-7}$  m/s.

When measured from the infiltration of water through the entire cover system (i.e, storage and release over clay barrier layers) overall cover in-service hydraulic conductivities were found to be within a range of  $7.5 \times 10^{-8}$  m/s and  $6.0 \times 10^{-6}$  m/s. The geometric mean of overall in-service hydraulic conductivities was  $4.4 \times 10^{-7}$  m/s, generally on order of magnitude higher than the as-built hydraulic conductivities (regardless of their initial design/as-built condition), with the largest increases observed in hydraulic conductivities for clay barriers that have been exposed to freeze-thaw cycling.

The Study defines a "freeze-thaw cycle" as a period of at least 24 hours during which the soil temperature of the layer of interest falls below 0°C, followed by a 24 hour period with temperatures greater than 0°C. As a result of the freeze-thaw cycling, structure is introduced into the soil layers that act as preferential flow paths, transforming a monolithic barrier layer with very low hydraulic conductivity into a structured and permeable soil layer. Analysis of site temperature data suggests that storage and barrier layers from all Study sites underwent a sufficient number of freeze-thaw cycles to develop the structure required to induce a maximum change in hydraulic conductivity. However, no such increases were observed in layers covered with soils of adequate depth to insulate them from below freezing atmospheric temperatures. This is of particular significance when evaluating the Study's applicability to Clive's site-specific clay barrier performance experience, in that at least one freeze-thaw cycle was observed at each of the Study sites. Most prominent changes for Study site in-service hydraulic conductivities from freeze-thaw cycles were observed within the first 1 to 3 years following construction. Negligible changes were observed from cycles occurring 5 years after initial construction.



**Figure 2-2. Borehole permeability test, (Benson et al., 2011; pg. 3-3)**



**Figure 2-3. Infiltrometer test, (Benson et al., 2011; pg. 3-4)**

The Study demonstrates that when exposed to freeze-thaw cycles, model representation of saturated hydraulic conductivities and associated van Genuchten alpha and n parameters should be increased from their initial design/as-built condition. Similarly, performance assessments should recognize that constructed covers are in a state of disequilibrium with the surrounding environment.

To account for such, a program of in-field direct monitoring should be incorporated to monitor the migration of a constructed cover from its design/as-built condition to a state of equilibrium with the surrounding environment. For example, Benson et al. (2011) generally recommends the installation of lysimeters beneath embankments for direct monitoring of the percolation (and by extension, bulk in-service hydraulic conductivity). Additionally, such migration of cover material properties should be accounted for in performance assessment, with alteration occurring until an equilibrium condition exists with the surrounding environment.

It also should be noted that the national studies documented by Benson et al. (2011) generally include covers constructed with lower percentages of clays. Because of this, Benson et al. recommends,

*“If available, a site-specific saturated hydraulic conductivity that reflects in-service condition should be used for performance predictions [instead of the wide distribution from regional sites examined herein].”* Benson et al. (2011, pg. 6-38)

While informative to the updated site-specific Performance Assessment (EnergySolutions, 2015; Appendix P), several significant differences exist between Benson et al. (2011) Study sites and EnergySolutions’ various Clive embankments (supporting Benson et al.’s recommendation for the use of site-specific hydraulic conductivities).

- 1) Clay barriers with several thicknesses of soil frost protection have been exposed to repeated winter conditions without any observed increase in in-service density or permeability.
- 2) Temperatures at the upper clay barrier surface have never been measured below 0°C at its Clive Cover Test Cell (EnergySolutions, 2014a).
- 3) While recognized as not equivalent to the evapotranspirative cover design proposed for CAW, water from infiltration through a completed cover has not been detected within lysimeters constructed beneath EnergySolutions’ rock armored disposal embankments (Mixed Waste, LARW, 11e.(2), and Cover Test Cell).

### 3. CLIVE'S SITE-SPECIFIC EXAMPLES OF CLAY BARRIER PROTECTION

Because of the range of site locations studied therein, Benson et al. (2011) provides a national input parameter database, which represents a variety of expected geohydrologic conditions, climates, behaviors, and wastes. In their general guidance for site decommissioning, NRC expresses caution in the interpretation of results produced from the use of generalized national data,

*“These data sources are available to provide estimates of parameter values in the absence of site-specific information. The large national databases can also be used to characterize parameter uncertainty. This is particularly appropriate when there are insufficient site-specific data on which to base parameter uncertainty estimates.” [emphasis added]; (NRC, 1999; pg. ix).*


NRC expresses further caution against the treatment of generic and national parameter distributions as though they are site-specific specifics,

*“It is clear that reduction in uncertainties occur as more site specific, direct measurements are made. Frequently, however, the site-specific data are unavailable and there must be reliance on estimates from generic, regional or local data sources that act as surrogate for site specific information. There is some caution that must be exercised in applying the local, regional, or generic data bases to site-specific cases.” [emphasis added]; (NRC, 1999; pg. 25)*

Finally, NRC provides the following clarification, using an example parameter “pdf”, as to its preference for selection of site-specific characteristics over the use of national data ranges,

*“In the absence of site-specific information, the effective value of a parameter at a site could conceivably be any reasonable value. Consider Figure [3-1]. With no site-specific information to use, the distribution based on the observed national data defines the range and relative likelihood of values the parameter can reasonably be expected to assume at the site. That is, the value of 0.18 is most likely, but a value of 0.10, while unlikely, cannot be dismissed since it has been observed [nationally]. It is thus appropriate to use the national distribution to represent the probability distribution of the effective (average) parameter value at the site, again, assuming that there is no site-specific information. As discussed previously, this will tend to overestimate the uncertainty of the parameter value both because the variability of the national data is likely to be greater than the variability at the site (see Figure [3-1]) and because the variability of the national data [instead of that from site-specific observations] is being used to represent the uncertainty of the parameter.” [emphasis added]; (NRC, 1999; pg. 27).*

Therefore, in accordance with the guidance of NRC (1999) site-specific observations should be preferentially selected over Benson et al.’s national ranges reported by Benson et al. (2011). By doing so, uncertainty is reduced and the risk of overestimation of variability is minimized.



**Figure 3-1. NRC’s Example: Expected Relationship Between the Variability of a Parameter on a National Scale and on a Site-Specific Basis” (NRC, 1999; pg. 27)**

The general cover design requirements for the licensing of near surface land low-level radioactive waste (LLRW), low activity radioactive waste (LARW), and 11e.(2) by-product disposal embankments are set forth in the UAC R313-24, UAC R313-25 and 10 CFR 40, as administered by the Division. Covers are designed to minimize, to the extent practicable, water infiltration into the waste. Location and layout of EnergySolutions' various Clive embankments (Mixed Waste, 11e.(2), LARW, and CAW) are shown on Figure 3-2.

The embankments are all constructed above a 2-foot thick clay barrier liner, with design/as-built permeability no greater than  $1 \times 10^{-6}$  cm/sec. Following waste placement above the 2-foot thick clay barrier liner, an engineered cover system is built. The Mixed Waste, 11e.(2), LARW, and CAW cover systems begin with clay barrier layers with design/as-built permeabilities of less than  $1 \times 10^{-8}$  m/sec for lower clay barriers and  $5 \times 10^{-10}$  m/sec for upper clay barriers. For the LARW and CAW Embankments, the lower radon barrier layers ( $1 \times 10^{-8}$  m/sec permeability) are at least 1.0 foot thick. For the 11e.(2) Embankment top slope, the lower radon barrier layer ( $1 \times 10^{-8}$  m/sec permeability) is at least 3.0 feet thick. For the 11e.(2) Embankment side slope, the lower radon barrier layer ( $1 \times 10^{-8}$  m/sec permeability) is at least 2.5 feet thick. By comparison, the LARW, CAW, and 11e.(2) Embankment upper clay barrier layers ( $5 \times 10^{-10}$  m/sec permeability) are at least 1.0 foot thick.

Embankment construction activities during the past twenty years of operation of clay barrier layers in Clive's embankments liners and covers has provided EnergySolutions with extensive experience and data demonstrating an ability to sufficiently protect these layers from freeze/thaw damage during winter/non-construction periods. This experience is reflected in the Division-approved spring start-up procedures, quality control, and quality assurance requirements of Work Element – Clay Liner Placement and Work Element – Radon Barrier Placement of the Low-Level Radioactive Waste and 11e.(2) Construction Quality Assurance / Quality Control Manual (CQA/QC Manual).

### **3.1 11e.(2) Embankment Clay Barrier**

The capacity of the 11e.(2) Embankment is 5,048,965 cubic yards (yd<sup>3</sup>) and occupies approximately 92 acres of EnergySolutions' Clive facility. EnergySolutions' 11e.(2) design is a near-surface landfill embankment, constructed using materials native to the site or found in close proximity to the site. Engineered features of the Embankment are designed based upon State of Utah regulations, NRC guidance, EPA guidance, and EnergySolutions' past experience at this location.

Since its initial licensing in 1999, 1,607,295 yd<sup>3</sup> of waste has been placed in the 11e.(2) Embankment from the eastern edge of its licensed footprint towards the west (EnergySolutions, 2014b). Waste material is placed on the liner and compacted in place to a waste column height of approximately 45 feet at the embankment shoulder (above grade). At the embankment's highest point, the waste column will be approximately 54 feet thick. When the Embankment is filled to the maximum height, a three and one-half foot thick clay barrier is placed on the side slopes and a four-foot thick layer of clay is placed on top and compacted. A twelve-inch filter zone of small diameter rock then provides a drainage layer above the clay barrier. An erosion barrier of specification-sized rock then covers the surface of the embankment.




Figure 3-2. EnergySolutions' Clive Facility Embankment Layout and Orientation

Unlike the CAW Embankment, significant amounts of clay barrier liner were initially constructed, following the initial licensing of the 11e.(2) Embankment in the year 2000. Similarly, final cover has intermittently been constructed as 11e.(2) waste placement has reached its design height. In cases where it is recognized that waste placement will not take place above constructed clay barrier liner for a period of more than 30 days or when atmospheric temperatures drop below 0°C, at least 9 inches of loose clay or 6 inches of compacted clay is required to be placed as frost protection. Prior to subsequent waste placement, EnergySolutions is required to excavate below the placed frost protection and re-test the underlying clay barrier liner for its design/as-built density and permeability. Areas compromised for placement testing are repaired by applying the same methodology applied during its initial construction.

As is illustrated in Figure 3-3, a significant portion of 11e.(2) clay barrier liner was originally constructed in 2000. In compliance with requirements of the Division-approved CQA/QC Manual, areas of the frost-protected clay barrier liner constructed in 2000 were tested prior to placement of 10,054 yd<sup>3</sup> of 11e.(2) byproduct waste in 2013 and 15,207 yd<sup>3</sup> in 2014 (see Appendix A for in-field tests). Contrary to the observations of unprotected clays by Benson et al. (2011), EnergySolutions' tests indicated that permeabilities of frost-protected clay barrier layers actually exhibited reductions from their design/as-built limits of  $1 \times 10^{-8}$  m/sec to  $8.9 \times 10^{-10}$  m/sec and  $4.0 \times 10^{-11}$  m/sec – with improvements in proctor densities (see Table 3-1). Of significance in determination of the unrepresentativeness of Benson et al. (2011) findings to EnergySolutions' clay observations at Clive, the improvements in the 11e.(2) Embankment clay barriers were seen after more than a decade of freeze/thaw cycles (where Benson et al. [2011] observed the most predominant increases in clay barrier permeabilities within the first few years following construction).

During the 11 freeze-thaw cycles in which the frost-protected 11e.(2) clay barrier liner was exposed to the atmosphere, EnergySolutions' Clive Meteorological Station reports average atmospheric temperatures of -2.4°C in January and -2.7 °C in December (MSI, 2014). MSI (2014) further reports a record minimum temperature of -31.5°C experienced on January 14, 2013, with the period of January through December 2013 seen as the coolest year during the 11 freeze-thaw cycles since the clay barrier liner's construction. Similarly, MSI (2014) further reports the second coldest period since the clay barrier liner's construction was observed during January 2007 (with the coldest temperature of -25.5 °C being observed on January 14, 2007). Notably, while Benson et al. (2011) report that unprotected clay barriers exhibit the greatest freeze-thaw driven changes during the first three years following construction, EnergySolutions' 11e.(2) frost-protected clay barrier liner exhibited improved characteristics.




Figure 3-3. 11e.(2) Embankment Frost-Protected Clay Barrier Test Locations

**Table 3-1**

**11e.(2) Embankment Frost-Protected Clay Barrier Spring Startup Tests**

<b>11e.(2) LIFT ID</b>	<b>FROST PROTECTION</b>	<b>DATE BUILT</b>	<b>DESIGN PERMEABILITY (m/sec)</b>	<b>DATE OF SPRING TESTING</b>	<b>IN-SERVICE PERMEABILITY (m/sec)</b>	<b>WINTER PERMEABILITY DECREASE (%)</b>	<b>WINTER DENSITY INCREASE (%)</b>
ECL000811 EC121004SS	0.75 feet of uncompacted clay	August 2000	$1.1 \times 10^{-9}$	April 2012	$8.9 \times 10^{-10}$	1,236	102
ECR12020314 EC130503SS	1 foot of uncompacted clay	August 2000	$1.5 \times 10^{-9}$	April 2013	$4.0 \times 10^{-11}$	3,750	108

### **3.2 LARW Embankment Clay Barrier**

The LARW Embankment received low-activity radioactive waste from 1988 until May, 2004, when it was filled to its design capacity. The completed LARW disposal cell is 1,115 feet by 1,670 feet, covering approximately 43 acres. Beginning in 1988, waste was placed above a 2-foot clay barrier layer of compacted clayey soils (with design/as-built permeability limited to no more than  $1 \times 10^{-8}$  m/sec). Above the two foot thick layer clay barrier layer and waste, the LARW Embankment was covered in three sections: the 1994 side slope cover, the 2004 side slope cover, and the uniform top slope cover. The 2004 slope is the same as the 1994 side slope cover, with the addition of a sacrificial soil layer (freeze protection) and a Type-B Filter (24 inches thick above the clay barrier layers). Changes in the side slope criteria were driven by the Groundwater Quality Discharge Permit No. UGW450005 (October 28, 1994) and later in July 2004. By comparison, the top slope and 2004 side slope consist of 42 inches of various materials above the clay barrier layers.

As is illustrated in Figure 3-4, several sections of LARW clay barrier liner were left frost-protected during winter months, prior to subsequent spring start-up confirmative testing and continued waste placement (see Appendix A for in-field tests). Contrary to the observations of unprotected clays by Benson et al. (2011), EnergySolutions' LARW Embankment tests presented in Table 3-2 demonstrate that permeabilities of frost-protected in-service clay barrier layers actually exhibited significant reductions in permeabilities from their design/as-built limits of  $1 \times 10^{-8}$  m/sec.

Notably, while Benson et al. (2011) report that unprotected clay barriers exhibit the greatest freeze-thaw driven changes during the first three years following construction, EnergySolutions' LARW Embankment frost-protected clay barrier liner reflects the same trend of improved characteristics as observed with the 11e.(2) Embankment.

### **3.3 Mixed Waste Test Pad Clay Barrier**

In compliance with applicable hazardous waste management requirements found in UAC R315, EnergySolutions' Mixed Waste Embankment is built over a composite liner of three feet of compacted clay barrier (with permeability less than or equal to  $1.0 \times 10^{-9}$  m/sec), intermixed with several layers of high density polyethylene (HDPE) liner. However, prior to construction within the Mixed Waste Embankment footprint, EnergySolutions is required to demonstrate constructability application of the design, procedures, and equipment on a clay barrier test pad of approximately 60 foot by 75 foot. Construction of clays in the liner test pad must be placed and compacted in at least three lifts with loose material thicknesses not exceeding twelve inches. The clay liner test pad is required to demonstrate an ability to achieve a design/as-built permeability of no more than  $1.0 \times 10^{-9}$  m/sec.




Figure 3-4. LARW Embankment Frost-Protected Clay Barrier Test Locations

**Table 3-2**

**LARW Embankment Frost-Protected Clay Barrier Spring Startup Tests**

<b>LARW LIFT ID</b>	<b>FROST PROTECTION</b>	<b>DATE BUILT</b>	<b>DESIGN PERMEABILITY (m/sec)</b>	<b>DATE OF SPRING TESTING</b>	<b>IN-SERVICE PERMEABILITY (m/sec)</b>	<b>WINTER PERMEABILITY DECREASE (%)</b>	<b>WINTER DENSITY INCREASE (%)</b>
LRBC9010501	1 foot of uncompacted clay	October 2004	$1 \times 10^{-8}$	April 2005	$1.3 \times 10^{-10}$	7,692	111
LRJ7011026	1 foot of uncompacted clay	October 2001	$1 \times 10^{-8}$	April 2002	$1.7 \times 10^{-9} - 7.7 \times 10^{-10}$	1,000 - 10,000	98 - 105
LRP1011012	1 foot of uncompacted clay	October 2001	$1 \times 10^{-8}$	April 2002	$7.7 \times 10^{-10} - 3.1 \times 10^{-11}$	1,299 - 32,258	113 - 118
LRF10041011	1.5 feet of uncompacted clay	October 2004	$1 \times 10^{-8}$	April 2005	$4.4 \times 10^{-9}$	227	102
LRP1010725	1 foot of uncompacted clay	June 2004	$1 \times 10^{-8}$	April 2005	$1.2 \times 10^{-9}$	833	118

Similarly, prior to construction of the Mixed Waste cover's initial two foot thick clay barrier, EnergySolutions is required to demonstrate its constructability via a clay cover barrier test pad also of approximately 60 foot by 75 foot. Construction of clays in the cover barrier test pad must be placed and compacted in at least two lifts with loose material thicknesses not exceeding twelve inches. The clay cover barrier test pad is required to demonstrate an ability to achieve a design/as-built permeability of no more than  $5.0 \times 10^{-10}$  m/sec.

Out of concern over the impact of freeze-thaw cycles on clay barrier layers left exposed to freezing atmospheric temperatures (without placement of protection), the Division of Solid and Hazardous Waste required EnergySolutions to construct a clay barrier layer test pad with a design/as-built permeability not exceeding  $1.0 \times 10^{-9}$  m/sec in 2007. This test pad was then left exposed to atmospheric temperatures (beneath a single layer of HDPE) between October 2007 and April 2008. Spring start-up analysis observed improvements in density of 110% and permeability of 2,000% (i.e.,  $5.0 \times 10^{-11}$  m/sec), respectively.

Notably, while Benson et al. (2011) report that unprotected clay barriers exhibit the greatest freeze-thaw driven changes during the first three years following construction, EnergySolutions' Mixed Waste clay barrier test pad left exposed without soil frost protection exhibited no freeze/thaw degradation in density or permeability.

### **3.4 Cover Test Cell Clay Barrier**

In order to demonstrate a rock armor design's ability to comply with the legacy Class A Embankment's ability to satisfy the required performance objectives, EnergySolutions constructed a Cover Test Cell in 2004 mirroring the Class A Embankment design. Since its construction and in satisfaction of Condition 28 of Radioactive Material License #UT 2300249, each year EnergySolutions has submitted an annual Cover Test Cell Report that presents, analyzes and interprets temperature and water balance data collected over the prior year. Most recently, EnergySolutions provided the Division with a Report of Cover Test Cell clay barrier temperature measurements and cover system water balance information for the time period from January 1, 2005 through December 31, 2013 (EnergySolutions, 2014a).

While clearly not of similar layer composition above the clay barriers as the CAW's evapotranspirative cover, review of the temperature data obtained at the surface of the upper clay barrier layer (Test Cell constructed with a two-foot thick clay barrier as the initial layer) demonstrates that the clay radon barrier is adequately protected from freezing temperatures (even though long ranges of atmospheric sub-freezing temperatures were observed in January 2013). In fact, analysis of the temperatures at the midpoint of the upper clay barrier indicates that this location has never experienced freezing conditions, since its initial construction (even with a historical atmospheric low temperatures measured during January 2013 and January 2007). Similarly, THERM monitoring locations provide supplemental measurements of potential freeze/thaw depths from the midpoint of the sacrificial soil layer down to the interface between the  $1 \times 10^{-8}$  m/sec and  $5 \times 10^{-10}$  m/sec clay barriers. Analysis of THERM data further suggests that the interface between the two clay barriers is adequately protected from freeze/thaw impacts.

#### 4. SUMMARY AND CONCLUSIONS

Benson et al. (2011) examined field tests, sample collection, laboratory tests, and data analyses from a nationwide selection of sites operating in various meteorological and hydrogeologic conditions. While including four similar arid-permeable geohydraulic/meteorologic-modeled sites similar to Clive, Benson et al. (2011) statistical analysis and in-service characteristic distributions also statistically represent humid-permeable and humid-impermeable sites (dramatically dissimilar to Clive). Furthermore, of the 27 in-service covers evaluated by Benson et al. (2011), 15 are equivalent in design and function to EnergySolutions' proposed CAW's evapotranspirative cover.

NRC expresses caution in the interpretation of results produced from the use of generalized national data such as those of Benson et al. (2011),

*“These data sources are available to provide estimates of parameter values in the absence of site-specific information. The large national databases can also be used to characterize parameter uncertainty. This is particularly appropriate when there are insufficient site-specific data on which to base parameter uncertainty estimates.” [emphasis added]; (NRC, 1999; pg. ix).*

NRC expresses further caution against the treatment of generic and national parameter distributions as though they are site-specific specifics,

*“It is clear that reduction in uncertainties occur as more site specific, direct measurements are made. Frequently, however, the site-specific data are unavailable and there must be reliance on estimates from generic, regional or local data sources that act as surrogate for site specific information. There is some caution that must be exercised in applying the local, regional, or generic data bases to site-specific cases.” [emphasis added]; (NRC, 1999; pg. 25)*

Substantiating and in accordance with NRC's guidance, it is significant to note that site-specific data obtained from EnergySolutions' use of compacted clays for embankment liners and cover barrier layers do not mirror the impact of freeze/thaw on hydraulic conductivity predicted in Benson et al. (2011). Therefore, Clive's site-specific observations should be preferentially-weighted over Benson et al.'s national ranges in the Division's approval of the demonstration of compliant-performance of the CAW's evapotranspirative cover in the updated site-specific Performance Assessment (EnergySolutions, 2015). By doing so, uncertainty is reduced and the risk of overestimation of variability is minimized. As such, EnergySolutions' Class A West evapotranspirative cover and Embankment will not exhibit degradation in long-term performance due to freeze/thaw impacts in the low permeability clay barrier layers.

## 5. REFERENCES

Benson, C.H., Albright, W.H., Fratta, D.O., Tinjum, J.M., Kucukkirca, E., Lee, S.H., Scalia, J., Schlicht, P.D., and Wang, X. 2011, NUREG/CR-7028, “Engineered Covers for Waste Containment: Changes in Engineering Properties and Implications for Long-Term Performance Assessment, Volume 1”, Office of Nuclear Regulatory Research, NRC, December 2011.

DRC. “Review and Audit of EnergySolutions’ Cover Test Cell (CTC) Corrective Action Plan and Related Documents.” From Rusty Lundberg (DRC) to Sean McCandless (EnergySolutions), 31 January 2012.

EnergySolutions. “Radioactive Material License renewal application”, EnergySolutions, 2015.

EnergySolutions. “Cover Test Cell Annual Report – 2013” (CD14-0021), February 11, 2014a.

EnergySolutions, “Ground Water Quality Discharge Permit Condition I.H.6 – 2014 Annual As-Built Reports,” December 18, 2014b.

EnergySolutions. “Groundwater Quality Discharge Permit”, EnergySolutions, 2013a.

Lundberg, R. “Policy Regarding the Application of Existing Performance Assessment Rules (R313-25-8 (sic), *Technical Analyses*, Utah Administrative Code) and U.S. Nuclear Regulatory Commission (NRC) Direction (SRM-SECY-2013-075) and Applicable Federal Guidance for Performance Assessments (NUREG-1573)” Memorandum from Rusty Lundberg (Utah Division of Radiation Control) to Division Staff, 25 February 2014a.

Lundberg, R., Personal Communication with Vern Rogers, April 9, 2014b.

MSI. “January 2011 Through December 2011 and January 1993 through December 2013 Summary Report of Meteorological Data Collected at EnergySolutions’ Clive, Utah Facility”, Project No. 011110111, Meteorological Solutions February 2014.

NRC. “Information on Hydrologic Conceptual Models, Parameters, Uncertainty Analysis, and Data Sources for Dose Assessments at Decommissioning Sites.” (NUREG/CR-6656). Division of Risk Analysis and Applications, Office of Nuclear Regulatory Research, U.S. Nuclear Regulatory Commission, November 1999.

Shrum, D. “Radioactive Material License #UT2300249: Justification for the Disposal of Blended Low Level Radioactive Waste at the Clive Containerized Waste Facility.”(CD11-0034) Letter from Dan Shrum (EnergySolutions) to Rusty Lundberg (Utah Radiation Control Board), 14 February 2011a.

Shrum, D. “Radioactive Material License #UT2300249; Justification for Disposal of SempraSafe Processed Waste at the Clive Containerized Waste Facility.”(CD11-0212) Letter from Dan Shrum (EnergySolutions) to Rusty Lundberg (Utah Radiation Control Board), 28 July 2011b.


**APPENDIX A**

**In-Field Density and Permeability Tests**



### EMBANKMENT CONSTRUCTION LIFT APPROVAL FORM

PROJECT:        CAN        MW   X   11e.(2)        CLASS A OTHER         
 WORK ELEMENT:    FOUNDATION   X   CLAY LINER        RADON BARRIER OTHER         
 NW CORNER:    N 12050.72 E 11717.21        DATE:    10/4/2012       



P 1	N 11980.61 E 11720.27
EW:	22 X 0.212 = 5
NS:	296 X 0.235 = 70
P 2	N 11512.36 E 11722.26
EW:	22 X 0.896 = 20
NS:	296 X 0.818 = 242
P 3	N 11178.74 E 11703.99
EW:	22 X 0.508 = 11
NS:	296 X 0.946 = 280
P 4	N 11058.96 E 11694.66
EW:	22 X 0.205 = 5
NS:	296 X 0.353 = 104
P 5	N 10655.86 E 11692.46
EW:	22 X 0.651 = 14
NS:	296 X 0.713 = 211
Page 2 attached: <input checked="" type="checkbox"/> Y <input type="checkbox"/> N	

IDENTIFY LOTS ABOVE

LIFT ID:    EC121004SS        UNC. THICKNESS:    9.0"        Constructed Per Test Pad #:    N/A         
 Lift Bonding Inspections (change in grade of at least 1" - two per linear foot): By:    N/A        Date:    N/A        Time:    N/A         
 Grade Pole Inspections (at least a 70 foot grid & all control points): By:    N/A        Date:    N/A        Time:    N/A         
 Dry Clod Size Inspection (Less than or equal to 1"): By:    N/A        Date:    N/A        Time:    N/A         
 Equipment Used for Compaction & # of Passes:        N/A         
 # of Deflocculant Bags:    N/A        Size of Mixing Area:        N/A        On-Cell / Off-Cell # Passes with Tiller:    N/A       

KEYING IN NOTES: N E S W        N/A        DENSITY TESTS ID # (S):        1 - 6         
 PERMEABILITY TESTS LOT # (S):        3        SANDCONE TEST LOT # (S):        N/A       

COMMENTS:    This lift approval is for spring start-up of 38999 ft<sup>2</sup> along the Eastern side of 11e.(2) embankment lift areas S-11, R-12, L-12, H-12, and D-12. This testing satisfies the requirement that "spring start-up testing shall be conducted on" these lift areas "prior to and in the same construction season as initial waste placement for each area."  
   On 10/08/12 @ 8:00 a.m., the liner temperature approximately 1" beneath the surface was found to be 41° F.  
   High compaction was observed on test 1 Lot 1.

LIFT APPROVED BY:    *Jeremy Hodges*        DATE:    10/8/2012        TIME:    9:21         
   *[Signature]*    10-23-12           *[Signature]*    11-5-12         
 QC OFFICER APPROVAL        DATE        QA APPROVAL        DATE



**RANDOM NUMBER CONTINUATION SHEET**

Date: 10/04/12

Lift ID: EC121004SS

NW Corner N 12050.72 E 11717.21

<p><i>P</i><sub>6</sub> <u>N 10541.77 E 11694.29</u></p> <p>EW: <u>22</u> X <u>0.884</u> = <u>19</u></p> <p>NS: <u>295</u> X <u>0.099</u> = <u>29</u></p>	<p><i>P</i><sub>14</sub> _____</p> <p>EW: _____ X _____ = _____</p> <p>NS: _____ X _____ = _____</p>	<p><i>P</i><sub>22</sub> _____</p> <p>EW: _____ X _____ = _____</p> <p>NS: _____ X _____ = _____</p>
<p><i>P</i><sub>7</sub> _____</p> <p>EW: _____ X _____ = _____</p> <p>NS: _____ X _____ = _____</p>	<p><i>P</i><sub>15</sub> _____</p> <p>EW: _____ X _____ = _____</p> <p>NS: _____ X _____ = _____</p>	<p><i>P</i><sub>23</sub> _____</p> <p>EW: _____ X _____ = _____</p> <p>NS: _____ X _____ = _____</p>
<p><i>P</i><sub>8</sub> _____</p> <p>EW: _____ X _____ = _____</p> <p>NS: _____ X _____ = _____</p>	<p><i>P</i><sub>16</sub> _____</p> <p>EW: _____ X _____ = _____</p> <p>NS: _____ X _____ = _____</p>	<p><i>P</i><sub>24</sub> _____</p> <p>EW: _____ X _____ = _____</p> <p>NS: _____ X _____ = _____</p>
<p><i>P</i><sub>9</sub> _____</p> <p>EW: _____ X _____ = _____</p> <p>NS: _____ X _____ = _____</p>	<p><i>P</i><sub>17</sub> _____</p> <p>EW: _____ X _____ = _____</p> <p>NS: _____ X _____ = _____</p>	<p><i>P</i><sub>25</sub> _____</p> <p>EW: _____ X _____ = _____</p> <p>NS: _____ X _____ = _____</p>
<p><i>P</i><sub>10</sub> _____</p> <p>EW: _____ X _____ = _____</p> <p>NS: _____ X _____ = _____</p>	<p><i>P</i><sub>18</sub> _____</p> <p>EW: _____ X _____ = _____</p> <p>NS: _____ X _____ = _____</p>	<p><i>P</i><sub>26</sub> _____</p> <p>EW: _____ X _____ = _____</p> <p>NS: _____ X _____ = _____</p>
<p><i>P</i><sub>11</sub> _____</p> <p>EW: _____ X _____ = _____</p> <p>NS: _____ X _____ = _____</p>	<p><i>P</i><sub>19</sub> _____</p> <p>EW: _____ X _____ = _____</p> <p>NS: _____ X _____ = _____</p>	<p><i>P</i><sub>27</sub> _____</p> <p>EW: _____ X _____ = _____</p> <p>NS: _____ X _____ = _____</p>
<p><i>P</i><sub>12</sub> _____</p> <p>EW: _____ X _____ = _____</p> <p>NS: _____ X _____ = _____</p>	<p><i>P</i><sub>20</sub> _____</p> <p>EW: _____ X _____ = _____</p> <p>NS: _____ X _____ = _____</p>	<p><i>P</i><sub>27</sub> _____</p> <p>EW: _____ X _____ = _____</p> <p>NS: _____ X _____ = _____</p>
<p><i>P</i><sub>13</sub> _____</p> <p>EW: _____ X _____ = _____</p> <p>NS: _____ X _____ = _____</p>	<p><i>P</i><sub>21</sub> _____</p> <p>EW: _____ X _____ = _____</p> <p>NS: _____ X _____ = _____</p>	<p><i>P</i><sub>29</sub> _____</p> <p>EW: _____ X _____ = _____</p> <p>NS: _____ X _____ = _____</p>

**COMMENTS:**

---



---



---



---



---





**FIELD DENSITY TEST**

PROJECT:     CAN     MW    X    11e.(2)     CLASS A     OTHER      
 LIFT IDENTIFICATION:     EC121004SS     DATE:     10/4/2012  
 TEST ID NUMBER(S):     2 LOT 2      
 TEST LOCATION:     N 11512.36 E 11722.26     TEST METHOD:     D1556    X    D6938

**ASTM D6938 (DENSITY DETERMINATION)**  
 Make/Model    Troxler 3430    Gauge Serial #    19481  
 Last Calibration Date:    9/17/12     
 Daily Standard Counts:    Off-Cell Standard     
 Density    1986    Moisture    636     
*Method A (Direct Transmission)*  
 Depth Setting    8 (inches)    Count Time    1 (minutes)  
 Moisture Count    196    Density Count    1307  
 Wet Density ( $\rho_m$ )    120.1 (lbs/ft<sup>3</sup>)    Dry Density    105.0 (lbs/ft<sup>3</sup>)  
 Moisture Density    15.2 (lbs/ft<sup>3</sup>)    Moisture Fraction    14.5 (%)

**MOISTURE DETERMINATION**  
 ASTM D2216 @ 110° C  
 Container ID     FU21      

Mass of container & wet specimen ( $M_{cmx}$ )	468.1	g
Mass of container & dry specimen ( $M_{cds}$ )	405.3	g
Mass of water ( $M_w$ ) $M_w = M_{cmx} - M_{cds}$	62.8	g
Mass of container ( $M_c$ )	108.6	g
Mass of dry specimen ( $M_d$ ) $M_d = M_{cds} - M_c$	296.7	g
Moisture content ( $w$ ) $w = (M_w / M_d) \times 100$	21.2	%

Dry Density ( $\rho_d = (100 \times \rho_m) / (100 + w)$ )  
 $\rho_d = (100 \times 120.1) / (100 + 21.2) = 99.1$  lbs/ft<sup>3</sup>  
*Note: Wet Density from ASTM D 1556 ( $\rho_m$ ) takes precedence over ASTM D 6938 ( $\rho_m$ )*  
 Percent Compaction =  $\rho_d / \gamma_{dmax} \times 100$   
 $99.1 / 100.0 \times 100 = 99.1$  %

Comments:

**ASTM D1556 (DENSITY DETERMINATION)**  
 Testing Apparatus     Calibrated Vol. (lbs/ft<sup>3</sup>)      
 Bulk Density of sand ( $\rho_s$ )     g/cm<sup>3</sup>     lbs/ft<sup>3</sup>  
 Mass of Sand to Fill Cone & Plate ( $M_2$ )     g  
 Mass of bottle & cone before filling cone, plate & hole     g  
 Mass of bottle & cone after filling cone, plate & hole     g  
 Mass of sand to fill cone, plate, & hole ( $M_1$ )     g  
 Mass of sand to fill hole     g  
 Mass of wet soil & container     g  
 Mass of container     g  
 Mass of wet soil ( $M_3$ )     g  
 Test Hole Volume  
 $V = (M_1 - M_2) / \rho_s$      cm<sup>3</sup>  
 Dry Mass of soil  
 $M_d = 100 M_3 / (w + 100)$      g  
 Wet Density  
 $\rho_m = (M_3 / V) \times 62.43$      lbs/ft<sup>3</sup>  
 Dry Density  
 $\rho_d = M_d / V$      g/cm<sup>3</sup>  
 Dry Unit Weight  
 $\gamma_d = \rho_d \times 62.43$      lbs/ft<sup>3</sup>

Soil Description:     Reddish brown clay      
 Proctor ID:     S5020221-1      
 Standard Proctor (ASTM D698)  
 Maximum Dry Density ( $\gamma_{dmax}$ )    100.0 (lbs/ft<sup>3</sup>)  
 Optimum Moisture ( $w_{opt}$ )    23.5 (%)  
 Required Moisture:    N/A % to    N/A %  
 Required Percent Compaction:    95.0 (%)

TEST RESULTS:  
 Pass     Date:    10/5/12     
 Failed Moisture      
 Failed Compaction     Time:    822     
 By:    Jeremy Hodges    /       (signature)  
 (print)    (signature)

      10-23-12     
 QC OFFICER APPROVAL    DATE   

      11-5-12     
 QA APPROVAL    DATE











**FIELD PERMEABILITY TEST**

PROJECT: CAW MW X 11e.(2) OTHER \_\_\_\_\_  
 Test Location: N. 11178.74 E. 11703.99 Elevation/Lift EC121004SS Lot No. 3

TESTING DATA: TESTED BY: Jeremy Hodges  
 Soil Saturation Start: Date: 10/5/12 Time: 10:00 Max. Dry Density 97.0 pcf  
 Soil Saturation Finish: Date: 10/5/12 Time: 14:00 Opt. Moisture 25.0 %  
 Depth of Wet Front Measurements: 1) 0.8 2) 2.2 3) 1.3 Density test # 3  
 Average Depth of Wet Front (L) 1.4 cm Dry Density 98.0 pcf  
 Radius of Measuring Tube (Rt) 0.32 cm Moisture content 24.2 %  
 Radius of Permeameter Ring (Rr) 22.0 cm Compaction 101.0 %  
 Height of Water, (Ht) 186.8 cm  
 Soil/Water temp, in ring, after test 21 °C

$\frac{dH}{dT} = \frac{\text{Change in Head (cm)}}{\text{Time (minutes)}} = \frac{N/A}{8} \text{ cm/min}$   
 $R = \underline{0.976}$  (From Figure 1)

$(\frac{dH}{dT}) = \underline{1.7301}$   
 Based on linear regression

$K_s = \left[ \frac{(2) (\frac{dH}{dT}) (L)}{(60) ((Ht) + (0.5)(L))} \right] \left[ \frac{(Rt)^2}{(Rr)^2} \right] X (R)$


$K_s = \left[ \frac{(2) (1.7301) (1.4)}{(60) ((186.8) + (0.5)(1.4))} \right] \left[ \frac{(0.32)^2}{(22.0)^2} \right] X \underline{0.976}$

$K_s = \underline{8.9E-08}$  cm/sec Required Permeability: x  $\leq 1X10^{-6}$   $\leq 5X10^{-8}$   $\leq 1X10^{-7}$

Soil/Water Temp (°C)	Corr. Factor (R)
0	1.783
1	1.723
2	1.664
3	1.611
4	1.560
5	1.511
6	1.465
7	1.421
8	1.379
9	1.339
10	1.301
11	1.265
12	1.230
13	1.197
14	1.165
15	1.135
16	1.106
17	1.077
18	1.051
19	1.025
20	1.000
21	<b>0.976</b>
22	0.953
23	0.931
24	0.910
25	0.889
26	0.869
27	0.850
28	0.832
29	0.814
30	0.797
31	0.780
32	0.764
33	0.749
34	0.733
35	0.719
36	0.705
37	0.692
38	0.678
39	0.665
40	0.653

Timed Water Drop Reading

min.	min.
0:00	<u>40.0</u>
0:20	<u>39.2</u>
0:40	<u>37.9</u>
1:00	<u>36.9</u>
1:20	<u>36.2</u>
1:40	<u>35.1</u>
2:00	<u>34.3</u>
2:20	<u>33.6</u>
2:40	<u>32.8</u>
3:00	<u>32.3</u>
3:20	<u>31.6</u>
3:40	<u>30.9</u>
4:00	<u>30.4</u>



Required Permeability:

$\leq 1.0E-06$

Actual Permeability:

8.9E-08

Test Results:  Pass  Fail

By Jeremy Hodges Date 10/05/12

QC OFFICER APPROVAL

DATE


QA APPROVAL

DATE

01/15-12 Figure 1  
 11-5-12

# EMBANKMENT CONSTRUCTION LIFT APPROVAL FORM

PROJECT: \_\_\_\_\_ CAN \_\_\_\_\_ MW X 11e.(2) \_\_\_\_\_ CLASS A OTHER \_\_\_\_\_  
 WORK ELEMENT: \_\_\_\_\_ FOUNDATION X CLAY LINER \_\_\_\_\_ RADON BARRIER OTHER \_\_\_\_\_  
 NW CORNER: N 12050.72 E 11717.21 DATE: 5/3/2013



IDENTIFY LOTS ABOVE

LIFT ID: EC130503SS UNC. THICKNESS: 9.0" Constructed Per Test Pad #: N/A  
 Lift Bonding Inspections (change in grade of at least 1" - two per linear foot): By: N/A Date: N/A Time: N/A  
 Grade Pole Inspections (at least a 70 foot grid & all control points): By: N/A Date: N/A Time: N/A  
 Dry Clod Size Inspection (Less than or equal to 1"): By: N/A Date: N/A Time: N/A  
 Equipment Used for Compaction & # of Passes: N/A  
 # of Deflocculant Bags: N/A Size of Mixing Area: N/A On-Cell / Off-Cell # Passes with Tiller: N/A

KEYING IN NOTES: N E S W N/A DENSITY TESTS ID # (S): 1 - 6  
 PERMEABILITY TESTS LOT # (S): 2 SANDCONE TEST LOT # (S): N/A

COMMENTS: This lift approval is for spring start-up of 38999 ft² along the Eastern side of 11e.(2) embankment lift areas S-11, R-12, L-12, H-12, and D-12. This testing satisfies the requirement that "spring start-up testing shall be conducted on" these lift areas "prior to and in the same construction season as initial waste placement for each area."

LIFT APPROVED BY: [Signature]  
 QC OFFICER APPROVAL: [Signature] DATE: 5-07-13

DATE: 5/3/2013 TIME: 15:41  
 QA APPROVAL: [Signature] DATE: 1/30/15

## RANDOM NUMBER CONTINUATION SHEET

Date: 05/03/13

Lift ID: EC130503SS

NW Corner N 12050.72 E 11717.21

$P_6$ <u>N 10541.77 E 11694.29</u> EW: <u>22</u> X <u>0.884</u> = <u>19</u> NS: <u>295</u> X <u>0.099</u> = <u>29</u>	$P_{14}$ _____ EW: _____ X _____ = _____ NS: _____ X _____ = _____	$P_{22}$ _____ EW: _____ X _____ = _____ NS: _____ X _____ = _____
$P_7$ _____ EW: _____ X _____ = _____ NS: _____ X _____ = _____	$P_{15}$ _____ EW: _____ X _____ = _____ NS: _____ X _____ = _____	$P_{23}$ _____ EW: _____ X _____ = _____ NS: _____ X _____ = _____
$P_8$ _____ EW: _____ X _____ = _____ NS: _____ X _____ = _____	$P_{16}$ _____ EW: _____ X _____ = _____ NS: _____ X _____ = _____	$P_{24}$ _____ EW: _____ X _____ = _____ NS: _____ X _____ = _____
$P_9$ _____ EW: _____ X _____ = _____ NS: _____ X _____ = _____	$P_{17}$ _____ EW: _____ X _____ = _____ NS: _____ X _____ = _____	$P_{25}$ _____ EW: _____ X _____ = _____ NS: _____ X _____ = _____
$P_{10}$ _____ EW: _____ X _____ = _____ NS: _____ X _____ = _____	$P_{18}$ _____ EW: _____ X _____ = _____ NS: _____ X _____ = _____	$P_{26}$ _____ EW: _____ X _____ = _____ NS: _____ X _____ = _____
$P_{11}$ _____ EW: _____ X _____ = _____ NS: _____ X _____ = _____	$P_{19}$ _____ EW: _____ X _____ = _____ NS: _____ X _____ = _____	$P_{27}$ _____ EW: _____ X _____ = _____ NS: _____ X _____ = _____
$P_{12}$ _____ EW: _____ X _____ = _____ NS: _____ X _____ = _____	$P_{20}$ _____ EW: _____ X _____ = _____ NS: _____ X _____ = _____	$P_{27}$ _____ EW: _____ X _____ = _____ NS: _____ X _____ = _____
$P_{13}$ _____ EW: _____ X _____ = _____ NS: _____ X _____ = _____	$P_{21}$ _____ EW: _____ X _____ = _____ NS: _____ X _____ = _____	$P_{29}$ _____ EW: _____ X _____ = _____ NS: _____ X _____ = _____

**COMMENTS:**

---

---

---

---

---

---

**FIELD DENSITY TEST**

PROJECT:     CAN     MW   X   11e.(2)     CLASS A     OTHER      
 LIFT IDENTIFICATION:     EC130503SS     DATE:     5/3/2013      
 TEST ID NUMBER(S):     **I LOT 1**      
 TEST LOCATION:     N 11980.61 E 11720.27     TEST METHOD:     D1556   X   D6938    

**ASTM D6938 (DENSITY DETERMINATION)**  
 Make/Model   Troloxer 3430   Gauge Serial #   31021    
 Last Calibration Date:   9/17/12    
 Daily Standard Counts: *Off-Cell Standard*  
 Density   2472   Moisture   683    
*Method A (Direct Transmission)*  
 Depth Setting   8   (inches) Count Time   1   (minutes)  
 Moisture Count   153   Density Count   1426    
 Wet Density ( $\rho_m$ )   127.0   (lbs/ft<sup>3</sup>) Dry Density   116.4   (lbs/ft<sup>3</sup>)  
 Moisture Density   10.6   (lbs/ft<sup>3</sup>) Moisture Fraction   9.1   (%)

**ASTM D1556 (DENSITY DETERMINATION)**  
 Testing Apparatus     Calibrated Vol. (lbs/ft<sup>3</sup>)      
 Bulk Density of sand ( $\rho_1$ )     g/cm<sup>3</sup>     lbs/ft<sup>3</sup>  
 Mass of Sand to Fill Cone & Plate ( $M_2$ )     g  
 Mass of bottle & cone **before** filling     g  
     cone, plate & hole     g  
 Mass of bottle & cone **after** filling     g  
     cone, plate & hole     g  
 Mass of sand to fill cone, plate, & hole ( $M_1$ )     g  
 Mass of sand to fill hole     g  
 Mass of wet soil & container     g  
 Mass of container     g  
 Mass of wet soil ( $M_3$ )     g  
 Test Hole Volume     cm<sup>3</sup>  
 $V = (M_1 - M_2) / \rho_1$   
 Dry Mass of soil     g  
 $M_d = 100 M_3 / (w + 100)$   
 Wet Density     lbs/ft<sup>3</sup>  
 $\rho_m = (M_3 / V) \times 62.43$   
 Dry Density     g/cm<sup>3</sup>  
 $\rho_d = M_d / V$   
 Dry Unit Weight     lbs/ft<sup>3</sup>  
 $\gamma_d = \rho_d \times 62.43$

**MOISTURE DETERMINATION**  
 ASTM D4643  
 Container ID     **TLT**    

Mass of container & wet specimen ( $M_{cms}$ )	<u>  364.0  </u>	g
Mass of container & dry specimen ( $M_{cds}$ )	<u>  338.3  </u>	g
Mass of water ( $M_w$ ) $M_w = M_{cms} - M_{cds}$	<u>  25.7  </u>	g
Mass of container ( $M_c$ )	<u>  230.1  </u>	g
Mass of dry specimen ( $M_s$ ) $M_s = M_{cds} - M_c$	<u>  108.2  </u>	g
Moisture content ( $w$ ) $w = (M_w / M_s) \times 100$	<u>  23.8  </u>	%

Soil Description:     **Reddish brown clay**      
 Proctor ID:     **S5020221-1**      
 Standard Proctor (ASTM D698)  
 Maximum Dry Density ( $\gamma_d \max$ )   100.0   (lbs/ft<sup>3</sup>)  
 Optimum Moisture ( $w_{opt}$ )   23.5   (%)  
 Required Moisture:   N/A   % to   N/A   %  
 Required Percent Compaction:   95.0   (%)

Dry Density ( $\rho_d$ ) =  $(100 \times \rho_m) / (100 + w)$   
 $\rho_d = (100 \times 127.0) / (100 + 23.8) = 102.6$  lbs/ft<sup>3</sup>  
*Note: Wet Density from ASTM D 1556 ( $\rho_m$ ) takes precedence over ASTM D 6938 ( $\rho_w$ )*  
 Percent Compaction =  $\rho_d / \gamma_d \max \times 100$   
 $102.6 / 100.0 \times 100 = 102.6$  %

Comments:  
**Microwave oven power setting on HIGH. Initial time setting of 3 minutes and subsequent incremental drying periods of 1 minute until a change of 0.1 % or less of the initial wet mass of the soil.**

TEST RESULTS:  
  X   Pass Date:   5/3/13    
    Failed Moisture  
    Failed Compaction Time:   1004    
 By:   Brennon Dick        
     (print) (signature)

      5-07-13    
 QC OFFICER APPROVAL DATE QA APPROVAL       5-7-13    
 DATE

**FIELD DENSITY TEST**

PROJECT:      CAN      MW   X   11e.(2)      CLASS A      OTHER       
 LIFT IDENTIFICATION:      EC130503SS      DATE:      5/3/2013  
 TEST ID NUMBER(S):      2 LOT 2       
 TEST LOCATION:      N 11512.36 E 11722.26      TEST METHOD:      D1556   X   D6938

**ASTM D6938 (DENSITY DETERMINATION)**  
 Make/Model   Troxler 3430   Gauge Serial #   31021    
 Last Calibration Date:   9/17/12    
 Daily Standard Counts:   Off-Cell Standard    
 Density   2472   Moisture   683    
*Method A (Direct Transmission)*  
 Depth Setting   8   (inches) Count Time   1   (minutes)  
 Moisture Count   206   Density Count   1386    
 Wet Density ( $\rho_m$ )   127.9   (lbs/ft<sup>3</sup>) Dry Density   113.2   (lbs/ft<sup>3</sup>)  
 Moisture Density   14.7   (lbs/ft<sup>3</sup>) Moisture Fraction   13.0   (%)

**MOISTURE DETERMINATION**  
 ASTM D4643  
 Container ID      **WAWA**  

Mass of container & wet specimen ( $M_{cms}$ )	<u>  343.4  </u> g
Mass of container & dry specimen ( $M_{cds}$ )	<u>  324.5  </u> g
Mass of water ( $M_w$ ) $M_w = M_{cms} - M_{cds}$	<u>  18.9  </u> g
Mass of container ( $M_c$ )	<u>  232.2  </u> g
Mass of dry specimen ( $M_s$ ) $M_s = M_{cds} - M_c$	<u>  92.3  </u> g
Moisture content ( $w$ ) $w = (M_w / M_s) \times 100$	<u>  20.5  </u> %

Dry Density ( $\rho_d$ ) =  $(100 \times \rho_m) / (100 + w)$   
 $\rho_d = (100 \times 127.9) / (100 + 20.5) = 106.2$  lbs/ft<sup>3</sup>  
Note: Wet Density from ASTM D 1556 ( $\rho_m$ ) takes precedence over ASTM D 6938 ( $\rho_w$ )  
 Percent Compaction =  $\rho_d / \gamma_d \text{max} \times 100$   
 $106.2 / 100.0 \times 100 = 106.2$  %

Comments:  
**Microwave oven power setting on HIGH. Initial time setting of 3 minutes and subsequent incremental drying periods of 1 minute until a change of 0.1 % or less of the initial wet mass of the soil.**

**ASTM D1556 (DENSITY DETERMINATION)**  
 Testing Apparatus      Calibrated Vol. (lbs/ft<sup>3</sup>)       
 Bulk Density of sand ( $\rho_1$ )      g/cm<sup>3</sup>      lbs/ft<sup>3</sup>  
 Mass of Sand to Fill Cone & Plate ( $M_2$ )      g  

Mass of bottle & cone <b>before</b> filling cone, plate & hole	<u>    </u> g
Mass of bottle & cone <b>after</b> filling cone, plate & hole	<u>    </u> g
Mass of sand to fill cone, plate, & hole ( $M_1$ )	<u>    </u> g
Mass of sand to fill hole	<u>    </u> g
Mass of wet soil & container	<u>    </u> g
Mass of container	<u>    </u> g
Mass of wet soil ( $M_3$ )	<u>    </u> g

 Test Hole Volume  
 $V = (M_1 - M_2) / \rho_1$       cm<sup>3</sup>  
 Dry Mass of soil  
 $M_4 = 100 M_3 / (w + 100)$       g  
 Wet Density  
 $\rho_m = (M_3 / V) \times 62.43$       lbs/ft<sup>3</sup>  
 Dry Density  
 $\rho_d = M_4 / V$       g/cm<sup>3</sup>  
 Dry Unit Weight  
 $\gamma_d = \rho_d \times 62.43$       lbs/ft<sup>3</sup>

Soil Description:      **Reddish brown clay**  
 Proctor ID:      **S5020221-1**  
 Standard Proctor (ASTM D698)  
 Maximum Dry Density ( $\gamma_d \text{max}$ )   100.0   (lbs/ft<sup>3</sup>)  
 Optimum Moisture ( $w_{opt}$ )   23.5   (%)  
 Required Moisture:   N/A   % to   N/A   %  
 Required Percent Compaction:   95.0   (%)

TEST RESULTS:  
  X   Pass Date:   5/3/13    
     Failed Moisture  
     Failed Compaction Time:   1003    
 By:   Brennon Dick         
(print) (signature)

       5-07-13    
 QC OFFICER APPROVAL DATE QA APPROVAL DATE  
       5-7-13



**FIELD DENSITY TEST**

PROJECT:      CAN      MW   X   11e.(2)      CLASS A      OTHER       
 LIFT IDENTIFICATION:      EC130503SS      DATE:      5/3/2013       
 TEST ID NUMBER(S):      4 LOT 4       
 TEST LOCATION:      N 11058.96 E 11694.66      TEST METHOD:      D1556   X   D6938     

**ASTM D6938 (DENSITY DETERMINATION)**  
 Make/Model   Troxler 3430   Gauge Serial #   31021    
 Last Calibration Date:   9/17/12    
 Daily Standard Counts: *Off-Cell Standard*  
 Density   2472   Moisture   683    
*Method A (Direct Transmission)*  
 Depth Setting   8   (inches) Count Time   1   (minutes)  
 Moisture Count   181   Density Count   1947    
 Wet Density ( $\rho_m$ )   115.0   (lbs/ft<sup>3</sup>) Dry Density   102.2   (lbs/ft<sup>3</sup>)  
 Moisture Density   12.8   (lbs/ft<sup>3</sup>) Moisture Fraction   12.5   (%)

**ASTM D1556 (DENSITY DETERMINATION)**  
 Testing Apparatus      Calibrated Vol. (lbs/ft<sup>3</sup>)       
 Bulk Density of sand ( $\rho_1$ )      g/cm<sup>3</sup>      lbs/ft<sup>3</sup>  
 Mass of Sand to Fill Cone & Plate ( $M_2$ )      g  
 Mass of bottle & cone **before** filling      g  
     cone, plate & hole      g  
 Mass of bottle & cone **after** filling      g  
     cone, plate & hole      g  
 Mass of sand to fill cone,      g  
     plate, & hole ( $M_1$ )      g  
 Mass of sand to fill hole      g  
 Mass of wet soil & container      g  
          g  
          g  
 Mass of container      g  
 Mass of wet soil ( $M_3$ )      g  
 Test Hole Volume      cm<sup>3</sup>  
 $V = (M_1 - M_2) / \rho_1$   
 Dry Mass of soil      g  
 $M_4 = 100 M_3 / (w + 100)$   
 Wet Density      lbs/ft<sup>3</sup>  
 $\rho_m = (M_3 / V) \times 62.43$   
 Dry Density      g/cm<sup>3</sup>  
 $\rho_d = M_4 / V$   
 Dry Unit Weight      lbs/ft<sup>3</sup>  
 $\gamma_d = \rho_d \times 62.43$

**MOISTURE DETERMINATION**  
 ASTM D4643  
 Container ID      AZ     

Mass of container & wet specimen ( $M_{cms}$ )	<u>  417.1  </u>	g
Mass of container & dry specimen ( $M_{cds}$ )	<u>  386.4  </u>	g
Mass of water ( $M_w$ ) $M_w = M_{cms} - M_{cds}$	<u>  30.7  </u>	g
Mass of container ( $M_c$ )	<u>  228.2  </u>	g
Mass of dry specimen ( $M_s$ ) $M_s = M_{cds} - M_c$	<u>  158.2  </u>	g
Moisture content ( $w$ ) $w = (M_w / M_s) \times 100$	<u>  19.4  </u>	%

Soil Description:      **Brownish mixed clay**       
 Proctor ID:      E001024-1       
 Standard Proctor (ASTM D698)  
 Maximum Dry Density ( $\gamma_{dmax}$ )   101.0   (lbs/ft<sup>3</sup>)  
 Optimum Moisture ( $w_{opt}$ )   21.5   (%)  
 Required Moisture:   N/A   % to   N/A   %  
 Required Percent Compaction:   95.0   (%)

Dry Density ( $\rho_d$ ) =  $(100 \times \rho_m) / (100 + w)$   
 $\rho_d = (100 \times 115.0) / (100 + 19.4) = 96.3$  lbs/ft<sup>3</sup>  
*Note: Wet Density from ASTM D 1556 ( $\rho_m$ ) takes precedence over ASTM D 6938 ( $\rho_w$ )*  
 Percent Compaction =  $\rho_d / \gamma_{dmax} \times 100$   
 $96.3 / 101.0 \times 100 = 95.4$  %

Comments:  
**Microwave oven power setting on HIGH. Initial time setting of 3 minutes and subsequent incremental drying periods of 1 minute until a change of 0.1 % or less of the initial wet mass of the soil.**

TEST RESULTS:  
  X   Pass Date:   5/3/13    
     Failed Moisture  
     Failed Compaction Time:   1001    
 By:   Brennon Dick         
     (print)      (signature)

QC OFFICER APPROVAL      DATE   5-07-13    
 QA APPROVAL      DATE   5-7-13

**FIELD DENSITY TEST**

PROJECT:      CAN      MW   X   11e.(2)      CLASS A      OTHER       
 LIFT IDENTIFICATION:      EC130503SS      DATE:      5/3/2013       
 TEST ID NUMBER(S):      5 LOT 5       
 TEST LOCATION:      N 10655.86 E 11692.46      TEST METHOD:      D1556   X   D6938     

**ASTM D6938 (DENSITY DETERMINATION)**  
 Make/Model Troxler 3430 Gauge Serial # 31021  
 Last Calibration Date: 9/17/12  
 Daily Standard Counts: Off-Cell Standard  
 Density 2472 Moisture 683  
*Method A (Direct Transmission)*  
 Depth Setting 8 (inches) Count Time 1 (minutes)  
 Moisture Count 188 Density Count 1618  
 Wet Density ( $\rho_w$ ) 122.0 (lbs/ft<sup>3</sup>) Dry Density 108.7 (lbs/ft<sup>3</sup>)  
 Moisture Density 13.3 (lbs/ft<sup>3</sup>) Moisture Fraction 12.2 (%)

**ASTM D1556 (DENSITY DETERMINATION)**  
 Testing Apparatus      Calibrated Vol. (lbs/ft<sup>3</sup>)       
 Bulk Density of sand ( $\rho_1$ )      g/cm<sup>3</sup>      lbs/ft<sup>3</sup>  
 Mass of Sand to Fill Cone & Plate ( $M_2$ )      g  
 Mass of bottle & cone **before** filling cone, plate & hole      g  
 Mass of bottle & cone **after** filling cone, plate & hole      g  
 Mass of sand to fill cone, plate, & hole ( $M_1$ )      g  
 Mass of sand to fill hole      g  
 Mass of wet soil & container      g  
 Mass of container      g  
 Mass of wet soil ( $M_3$ )      g  
 Test Hole Volume  $V = (M_1 - M_2) / \rho_1$       cm<sup>3</sup>  
 Dry Mass of soil  $M_4 = 100 M_3 / (w + 100)$       g  
 Wet Density  $\rho_w = (M_3 / V) \times 62.43$       lbs/ft<sup>3</sup>  
 Dry Density  $\rho_d = M_4 / V$       g/cm<sup>3</sup>  
 Dry Unit Weight  $\gamma_d = \rho_d \times 62.43$       lbs/ft<sup>3</sup>

**MOISTURE DETERMINATION**  
 ASTM D4643  
 Container ID JFK  

Mass of container & wet specimen ( $M_{cms}$ )	<u>414.2</u>	g
Mass of container & dry specimen ( $M_{c ds}$ )	<u>383.0</u>	g
Mass of water ( $M_w$ ) $M_w = M_{cms} - M_{c ds}$	<u>31.2</u>	g
Mass of container ( $M_c$ )	<u>227.2</u>	g
Mass of dry specimen ( $M_s$ ) $M_s = M_{c ds} - M_c$	<u>155.8</u>	g
Moisture content ( $w$ ) $w = (M_w / M_s) \times 100$	<u>20.0</u>	%

Soil Description: Lean Clay  
 Proctor ID: S5010925-2  
 Standard Proctor (ASTM D698)  
 Maximum Dry Density ( $\gamma_{d max}$ ) 103.2 (lbs/ft<sup>3</sup>)  
 Optimum Moisture ( $w_{opt}$ ) 20.1 (%)  
 Required Moisture: N/A % to N/A %  
 Required Percent Compaction: 95.0 (%)

Dry Density ( $\rho_d = (100 \times \rho_w) / (100 + w)$ )  
 $\rho_d = (100 \times 122.0) / (100 + 20.0) = 101.6$  lbs/ft<sup>3</sup>  
*Note: Wet Density from ASTM D 1556 ( $\rho_w$ ) takes precedence over ASTM D 6938 ( $\rho_w$ )*  
 Percent Compaction =  $\rho_d / \gamma_{d max} \times 100$   
 $101.6 / 103.2 \times 100 = 98.5$  %

Comments:  
**Microwave oven power setting on HIGH. Initial time setting of 3 minutes and subsequent incremental drying periods of 1 minute until a change of 0.1 % or less of the initial wet mass of the soil.**

TEST RESULTS:  
  X   Pass Date: 5/3/13  
     Failed Moisture  
     Failed Compaction Time: 1015  
 By: Brennon Dick (print) [Signature] (signature)

[Signature] 5-7-13  
 QC OFFICER APPROVAL DATE

[Signature] 5-7-13  
 QA APPROVAL DATE

PROJECT:     CAN     MW   X   11e.(2)     CLASS A     OTHER      
 LIFT IDENTIFICATION:     EC130503SS     DATE:     5/3/2013      
 TEST ID NUMBER(S):     6 LOT 6      
 TEST LOCATION:     N 10541.77 E 11694.29     TEST METHOD:     D1556   X   D6938    

**ASTM D6938 (DENSITY DETERMINATION)**  
 Make/Model   Troloxer 3430   Gauge Serial #   31021    
 Last Calibration Date:   9/17/12    
 Daily Standard Counts:   Off-Cell Standard    
 Density   2472   Moisture   683    
*Method A (Direct Transmission)*  
 Depth Setting   8   (inches) Count Time   1   (minutes)  
 Moisture Count   212   Density Count   1673    
 Wet Density ( $\rho_m$ )   120.7   (lbs/ft<sup>3</sup>) Dry Density   105.5   (lbs/ft<sup>3</sup>)  
 Moisture Density   15.2   (lbs/ft<sup>3</sup>) Moisture Fraction   14.4   (%)

**ASTM D1556 (DENSITY DETERMINATION)**  
 Testing Apparatus     Calibrated Vol. (lbs/ft<sup>3</sup>)      
 Bulk Density of sand ( $\rho_1$ )     g/cm<sup>3</sup>     lbs/ft<sup>3</sup>  
 Mass of Sand to Fill Cone & Plate ( $M_2$ )     g  
 Mass of bottle & cone **before** filling cone, plate & hole     g  
 Mass of bottle & cone **after** filling cone, plate & hole     g  
 Mass of sand to fill cone, plate, & hole ( $M_1$ )     g  
 Mass of sand to fill hole     g  
 Mass of wet soil & container     g  
 Mass of container     g  
 Mass of wet soil ( $M_3$ )     g  
 Test Hole Volume  $V = (M_1 - M_2) / \rho_1$      cm<sup>3</sup>  
 Dry Mass of soil  $M_4 = 100 M_3 / (w + 100)$      g  
 Wet Density  $\rho_m = (M_3 / V) \times 62.43$      lbs/ft<sup>3</sup>  
 Dry Density  $\rho_d = M_4 / V$      g/cm<sup>3</sup>  
 Dry Unit Weight  $\gamma_d = \rho_d \times 62.43$      lbs/ft<sup>3</sup>

**MOISTURE DETERMINATION**  
 ASTM D4643  
 Container ID     **LALA**    

Mass of container & wet specimen ( $M_{cms}$ )	<u>  350.5  </u>	g
Mass of container & dry specimen ( $M_{c ds}$ )	<u>  328.7  </u>	g
Mass of water ( $M_w$ ) $M_w = M_{cms} - M_{c ds}$	<u>  21.8  </u>	g
Mass of container ( $M_c$ )	<u>  227.3  </u>	g
Mass of dry specimen ( $M_s$ ) $M_s = M_{c ds} - M_c$	<u>  101.4  </u>	g
Moisture content ( $w$ ) $w = (M_w / M_s) \times 100$	<u>  21.5  </u>	%

Soil Description:     **Lean Clay**      
 Proctor ID:     **S5010925-2**      
 Standard Proctor (ASTM D698)  
 Maximum Dry Density ( $\gamma_d max$ )   103.2   (lbs/ft<sup>3</sup>)  
 Optimum Moisture ( $w_{opt}$ )   20.1   (%)  
 Required Moisture:   N/A   % to   N/A   %  
 Required Percent Compaction:   95.0   (%)

Dry Density ( $\rho_d$ ) =  $(100 \times \rho_m) / (100 + w)$   
 $\rho_d = (100 \times 120.7) / (100 + 21.5) = 99.3$  lbs/ft<sup>3</sup>  
*Note: Wet Density from ASTM D 1556 ( $\rho_m$ ) takes precedence over ASTM D 6938 ( $\rho_w$ )*  
 Percent Compaction =  $\rho_d / \gamma_d max \times 100$   
 $99.3 / 103.2 \times 100 = 96.3$  %

Comments:  
**Microwave oven power setting on HIGH. Initial time setting of 3 minutes and subsequent incremental drying periods of 1 minute until a change of 0.1 % or less of the initial wet mass of the soil.**

TEST RESULTS:  
  X   Pass Date:   5/3/13    
    Failed Moisture  
    Failed Compaction Time:   1020    
 By:   Brennon Dick        
 (print) (signature)

QC OFFICER APPROVAL     DATE   5-07-13    
 QA APPROVAL     DATE   5-7-13

**FIELD PERMEABILITY TEST**

PROJECT: CAW MW X 11e.(2) OTHER \_\_\_\_\_  
 Test Location: N 11512.36 E 11722.26 Elevation/Lift EC130503SS Lot No. 2

TESTING DATA: TESTED BY: Brennon Dick  
 Soil Saturation Start: Date: 5/3/13 Time: 0945 Max. Dry Density 100.0 pcf  
 Soil Saturation Finish: Date: 5/3/13 Time: 1410 Opt. Moisture 23.5 %  
 Depth of Wet Front Measurements: 1) 0.2 2) 0.2 3) 1.3 Density test # 2  
 Average Depth of Wet Front (L) 0.6 cm Dry Density 106.2 pcf  
 Radius of Measuring Tube (Rt) 0.32 cm Moisture content 20.5 %  
 Radius of Permeameter Ring (Rr) 22.0 cm Compaction 106.2 %  
 Height of Water, (Ht) 181.6 cm  
 Soil/Water temp, in ring, after test 24 °C

$\frac{dH}{dT} = \frac{\text{Change in Head (cm)}}{\text{Time (minutes)}} = \frac{\text{N/A}}{8} \text{ cm/min}$   
 R = 0.910 (From Figure 1)

$(\frac{dH}{dT}) = \underline{0.1883}$   
 Based on linear regression

$K_s = \left[ \frac{(2) (\frac{dH}{dT}) (L)}{(60) ((Ht)+(0.5)(L))} \right] \left[ \frac{(Rt)^2}{(Rr)^2} \right] X (R)$


$K_s = \left[ \frac{(2)(\frac{0.1883}{(60)((181.6) + (0.5)(0.6))}) (0.6)}{\left( \frac{0.32}{22.0} \right)^2} \right] X \underline{0.910}$

$K_s = \underline{4.0E-09} \text{ cm/sec}$  Required Permeability: X  $\leq 1X10^{-6}$   $\leq 5X10^{-8}$   $\leq 1X10^{-7}$

Soil/Water Temp (°C)	Corr. Factor (R)
0	1.783
1	1.723
2	1.664
3	1.611
4	1.560
5	1.511
6	1.465
7	1.421
8	1.379
9	1.339
10	1.301
11	1.265
12	1.230
13	1.197
14	1.165
15	1.135
16	1.106
17	1.077
18	1.051
19	1.025
20	1.000
21	0.976
22	0.953
23	0.931
24	<b>0.910</b>
25	0.889
26	0.869
27	0.850
28	0.832
29	0.814
30	0.797
31	0.780
32	0.764
33	0.749
34	0.733
35	0.719
36	0.705
37	0.692
38	0.678
39	0.665
40	0.653

Timed Water Drop Reading

min.	min.
0:00	<u>41.2</u>
0:20	<u>41.1</u>
0:40	<u>41.1</u>
1:00	<u>41.0</u>
1:20	<u>41.0</u>
1:40	<u>41.0</u>
2:00	<u>40.9</u>
2:20	<u>40.9</u>
2:40	<u>40.9</u>
3:00	<u>40.9</u>
3:20	<u>40.8</u>
3:40	<u>40.9</u>
4:00	<u>41.0</u>



Required Permeability:

$\leq 1.0E-06$

Actual Permeability:

4.0E-09

Test Results:  Pass  Fail

By [Signature] Date 5-03-13

QC OFFICER APPROVAL

5-07-13  
DATE

QA APPROVAL

5-7-13  
DATE

Figure 1

(EW12)

ENVIROCORE OF UTAH, INC.  
LIFT APPROVAL FORM  
(EC-1904)

ORIGINAL  
(DATE: 06/27/98)  
REVISION: 03 RCN: 02

PROJECT: LARW MW X 11e. (2) OTHER (specify) clay liner 5<sup>th</sup> Lift

NW CORNER

DATE: 8-11-00

1120 N 1190 E 1393 E 810 N	1 N 1089 E 1243	P1 EW: <u>X</u> = <u>    </u> NS: <u>X</u> = <u>    </u>
	2 N 1008 E 1360	P2 EW: <u>X</u> = <u>    </u> NS: <u>X</u> = <u>    </u>
	3 N 942 E 1332	P3 EW: <u>X</u> = <u>    </u> NS: <u>X</u> = <u>    </u>
	4 N 844 E 1272	P4 EW: <u>X</u> = <u>    </u> NS: <u>X</u> = <u>    </u>
	5 N 825 E 1357	P5 EW: <u>X</u> = <u>    </u> NS: <u>X</u> = <u>    </u>

IDENTIFY LOTS ABOVE

LIFT ID: ECL000811 NW CORNER: 1120 N 1190 E INTERFACE RANDOM #: N/R

WASTE GENERATOR ID NUMBER(S): N/R

THICKNESS: UNC: Ave = 5.0" COMP: N/R ELEV: N/R

DEBRIS CALCULATIONS: N/R

KEYING IN NOTES: N 3 S W Satisfactory DENSITY TESTS ID #(S): 33, 34, 35, 36, 37

COMMENTS: The material compacted procedures were approved in test pad 98 TP-2

LIFT APPROVED BY: Glen Chan DATE: 8-11-00 TIME: 1100

Ray Leach 8-15-2000 D. Jones 4 8-15-00  
 QC OFFICER APPROVAL DATE QA OFFICER APPROVAL DATE

# ENVIROCARE OF UTAH, INC. ORIGINAL

## FIELD DENSITY TEST

(EC-1905, rev. 4)

PROJECT: \_\_\_\_\_ LARW: \_\_\_\_\_ MW: X lie. (2): \_\_\_\_\_ OTHER (specify): \_\_\_\_\_

LIFT IDENTIFICATION: ECL000811 DATE: 8-11-00

WASTE OR (TEST) ID NUMBER(S): 33 lot 1

TEST LOCATION: 1089 N 1243 E TEST METHOD: \_\_\_\_\_ D1556 X D2922

**D2922 DENSITY DETERMINATION  
(NUCLEAR DENSITY GAUGE)**

GAUGE ID NO. 25128

On-Cell Standard:	Off-Cell Standard:
Density _____	Density _____
Counts _____	Counts <u>2544</u>
Moisture _____	Moisture _____
Counts _____	Counts <u>730</u>
Depth Setting _____	Count Time _____
(inches) <u>6</u>	(minutes) <u>1</u>
Moisture _____	Density _____
Counts <u>222</u>	Counts <u>2274</u>
Wet _____	Dry _____
Density _____	Density _____
(PCF) <u>124.0</u>	(PCF) <u>107.6</u>
Moisture _____	Moisture _____
Density _____	Fraction _____
(PCF) <u>16.5</u>	(%) <u>15.3</u>

**D1556 DENSITY DETERMINATION  
(SAND CONE)**

Bulk Density of sand (PCF) 8/1400  
 Mass of Sand to Fill Cone & Plate (g) \_\_\_\_\_

Mass of bottle & cone before filling cone, plate, & hole (g) \_\_\_\_\_  
 Mass of bottle & cone, after filling cone, plate, & hole (g) \_\_\_\_\_  
 Mass of sand to fill cone, plate, & hole (g) \_\_\_\_\_  
 Mass of sand to fill cone & plate (g) \_\_\_\_\_  
 Mass of sand to fill hole (g) \_\_\_\_\_  
 Mass of wet soil & container (g) \_\_\_\_\_

Mass of container (g) \_\_\_\_\_  
 Mass of wet soil (g) \_\_\_\_\_


Wet Bulk density Mass of wet Density of sand (PCF) x soil (g) (PCF) Mass of sand filling hole  
 Wet \_\_\_\_\_  
 Density (PCF) \_\_\_\_\_

**MOISTURE DETERMINATION**

Container ID <u>EE</u>	
Mass of wet soil & container (g)	<u>229.6</u>
Mass of dry soil & container (g)	<u>209.5</u>
Mass of water (g)	<u>20.1</u>
Mass of dry soil & container (g)	<u>209.5</u>
Mass of container (g)	<u>129.6</u>
Mass of dry soil (g)	<u>79.9</u>
Moisture content (%)	<u>25.2</u>

**SOIL DATA: PROCTOR # E000721-3**

Proctor Dry Density (PCF) 97.0  
 Proctor Optimum Moisture (%) 25.0  
 Required Moisture (%): 25.0 to 39.0  
 Required Compaction (%): 95.0

TEST RESULTS:  
 Pass  
 Failed Moisture  
 Failed Compaction  
 BY: Ryan Harris TIME: 10:30

Dry Density =  $\frac{\text{Wet Density (PCF)} \times 100.0}{\text{Moisture content (\%)} + 100.0}$   
 Dry Density =  $\frac{124.0 \times 100.0}{25.2 + 100.0} = 99.0$  pcf

Percent Compaction =  $\frac{\text{Dry Density} \times 100.0}{\text{Proctor Density}}$   
 Percent Compaction =  $\frac{99.0 \times 100.0}{97.0} = 102.1$  %

Ryan Harris 8-15-2000  
 QC OFFICER APPROVAL DATE

Ryan Harris 8-15-00  
 QA OFFICER APPROVAL DATE

ENVIROCARE OF UTAH, INC.

ORIGINAL

FIELD DENSITY TEST

(EC-1905, rev. 4)

PROJECT: \_\_\_\_\_ LARW: \_\_\_\_\_ MW: X Lie. (2): \_\_\_\_\_ OTHER (specify): \_\_\_\_\_

LIFT IDENTIFICATION: ECL000811 DATE: 8-11-00

WASTE OR (TEST) ID NUMBER(S): 34 lot 2

TEST LOCATION: 100B N 1360 E TEST METHOD: \_\_\_\_\_ D1556 X D2922

D2922 DENSITY DETERMINATION  
(NUCLEAR DENSITY GAUGE)

GAUGE ID NO. 2512B

On-Cell Standard: Density Counts Moisture Counts Depth Setting (inches) <u>6</u> Moisture Counts <u>235</u> Wet Density (PCF) <u>123.4</u> Moisture Density (PCF) <u>17.5</u>	Off-Cell Standard: Density Counts <u>2544</u> Moisture Counts <u>730</u> Count Time (minutes) <u>1</u> Density Counts <u>2305</u> Dry Density (PCF) <u>105.9</u> Moisture Fraction (%) <u>16.6</u>
---	--

D1556 DENSITY DETERMINATION  
(SAND CONE)

Bulk Density of sand  
(PCF) G.C. 8/14/00  
Mass of Sand to Fill  
Cone & Plate (g) \_\_\_\_\_

Mass of bottle & cone  
before filling cone,  
plate, & hole (g) \_\_\_\_\_  
Mass of bottle & cone,  
after filling cone,  
plate, & hole (g) \_\_\_\_\_  
Mass of sand to fill  
cone, plate, & hole (g) \_\_\_\_\_  
Mass of sand to fill  
cone & plate (g) \_\_\_\_\_  
Mass of sand to fill  
hole (g) \_\_\_\_\_  
Mass of wet soil &  
container (g) \_\_\_\_\_  
Mass of container (g) \_\_\_\_\_  
Mass of wet soil (g) \_\_\_\_\_

Wet Bulk density Mass of wet  
Density of sand (PCF) x soil (g)  
(PCF) Mass of sand filling hole

Wet \_\_\_\_\_  
Density (PCF) \_\_\_\_\_

MOISTURE DETERMINATION

Container ID <u>ASD</u>	
Mass of wet soil & container (g)	<u>233.3</u>
Mass of dry soil & container (g)	<u>213.0</u>
Mass of water (g)	<u>20.3</u>
Mass of dry soil & container (g)	<u>213.0</u>
Mass of container (g)	<u>133.3</u>
Mass of dry soil (g)	<u>79.7</u>
Moisture content (%)	<u>25.5</u>

SOIL DATA: PROCTOR # E000721-3

Proctor Dry Density (PCF) 97.0  
Proctor Optimum Moisture (%) 25.0  
Required Moisture (%): 25.0 to 30.0  
Required Compaction (%): 95.0

TEST RESULTS:  
 Pass  
 Failed Moisture  
 Failed Compaction  
BY: Ryan Harris TIME: 1030

Dry Density =  $\frac{\text{Wet Density (PCF)} \times 100.0}{\text{Moisture content (\%)} + 100.0}$   
Dry Density =  $\frac{123.4 \times 100.0}{25.5 + 100.0} = 98.3$  pcf

Percent Compaction =  $\frac{\text{Dry Density} \times 100.0}{\text{Proctor Density}}$   
Percent Compaction =  $\frac{98.3 \times 100.0}{97.0} = 101.4$  %

Rex D. Reed 8-15-2000  
QC OFFICER APPROVAL DATE

D. Harris 8-15-00  
QA OFFICER APPROVAL DATE

# ENVIROCARE OF UTAH, INC.

# ORIGINAL

## FIELD DENSITY TEST

(EC-1905, rev. 4)

PROJECT: \_\_\_\_\_ LARW: \_\_\_\_\_ MW: X lie.(2): \_\_\_\_\_ OTHER (specify): \_\_\_\_\_

LIFT IDENTIFICATION: ECL000B11 DATE: 8-11-00

WASTE OR (TEST) ID NUMBER(S): 35 1 of 3

TEST LOCATION: 942 N 1332 E TEST METHOD: \_\_\_\_\_ D1556 + D2922

**D2922 DENSITY DETERMINATION  
(NUCLEAR DENSITY GAUGE)  
GAUGE ID NO. 25128**

On-Cell Standard:	Off-Cell Standard:
Density Counts _____	Density Counts <u>2544</u>
Moisture Counts _____	Moisture Counts <u>730</u>
Depth Setting <u>6</u> (inches)	Count Time <u>1</u> (minutes)
Moisture Counts <u>231</u>	Density Counts <u>2401</u>
Wet Density (PCF) <u>121.7</u>	Dry Density (PCF) <u>104.5</u>
Moisture Density (PCF) <u>17.2</u>	Moisture Fraction (%) <u>16.5</u>

**D1556 DENSITY DETERMINATION  
(SAND CONE)**

Bulk Density of sand (PCF) g.c. 81/100

Mass of Sand to Fill Cone & Plate (g) \_\_\_\_\_

Mass of bottle & cone before filling cone, plate, & hole (g) \_\_\_\_\_

Mass of bottle & cone after filling cone, plate, & hole (g) \_\_\_\_\_

Mass of sand to fill cone, plate, & hole (g) \_\_\_\_\_

Mass of sand to fill cone & plate (g) \_\_\_\_\_

Mass of sand to fill hole (g) \_\_\_\_\_

Mass of wet soil & container (g) \_\_\_\_\_

Mass of container (g) \_\_\_\_\_

Mass of wet soil (g) \_\_\_\_\_

Wet Density (PCF) \_\_\_\_\_

Bulk density of sand (PCF) \_\_\_\_\_

Mass of wet soil (g) \_\_\_\_\_

Mass of sand filling hole \_\_\_\_\_

Wet Density (PCF) \_\_\_\_\_

**MOISTURE DETERMINATION**

Container ID <u>R</u>	
Mass of wet soil & container (g)	<u>230.1</u>
Mass of dry soil & container (g)	<u>209.1</u>
Mass of water (g)	<u>21.0</u>
Mass of dry soil & container (g)	<u>209.1</u>
Mass of container (g)	<u>130.1</u>
Mass of dry soil (g)	<u>79.0</u>
Moisture content (%)	<u>26.6</u>

**SOIL DATA: PROCTOR # E00071-3**

Proctor Dry Density (PCF) 97.0

Proctor Optimum Moisture (%) 25.0

Required Moisture (%): 25.0 to 30.0

Required Compaction (%): 95.0

Dry Density =  $\frac{\text{Wet Density (PCF)}}{\text{Moisture content (\%)} + 100.0} \times 100.0$

Dry Density =  $\frac{121.7}{26.6 + 100.0} \times 100.0 = 96.1$  pcf

Percent Compaction =  $\frac{\text{Dry Density} \times 100.0}{\text{Proctor Density}}$

Percent Compaction =  $\frac{96.1 \times 100.0}{97.0} = 99.1$  %

**TEST RESULTS:**

Pass

Failed Moisture

Failed Compaction

BY: Ryan Harris TIME: 1030

QC OFFICER APPROVAL: Ryan Harris DATE: 8-15-2000

QA OFFICER APPROVAL: \_\_\_\_\_ DATE: 8-15-00

ENVIROCARE OF UTAH, INC.

ORIGINAL

FIELD DENSITY TEST

(EC-1905, rev. 4)

PROJECT: LAEW: MW: A lie. (2): OTHER (specify):

LIFT IDENTIFICATION: ECL000811 DATE: 8-11-00

WASTE OR (TEST) ID NUMBER(S): 36 lot 4

TEST LOCATION: 844 N. 1272 E TEST METHOD: D1556 + D2922

D2922 DENSITY DETERMINATION  
(NUCLEAR DENSITY GAUGE)  
GUAGE ID NO. 25128

On-Cell Standard:	Off-Cell Standard:
Density	Density
Counts	Counts <u>2544</u>
Moisture	Moisture
Counts	Counts <u>720</u>
Depth Setting	Count Time
(inches) <u>6</u>	(minutes) <u>1</u>
Moisture	Density
Counts <u>219</u>	Counts <u>2489</u>
Wet	Dry
Density	Density
(PCF) <u>120.3</u>	(PCF) <u>104.0</u>
Moisture	Moisture
Density	Fraction
(PCF) <u>16.2</u>	(%) <u>15.6</u>

D1556 DENSITY DETERMINATION  
(SAND CONE)

Bulk Density of sand (PCF) G-c 8/11/00  
Mass of Sand to Fill Cone & Plate (g)

Mass of bottle & cone before filling cone, plate, & hole (g)  
Mass of bottle & cone, after filling cone, plate, & hole (g)  
Mass of sand to fill cone, plate, & hole (g)  
Mass of sand to fill cone & plate (g)  
Mass of sand to fill hole (g)  
Mass of wet soil & container (g)

Mass of container (g)  
Mass of wet soil (g)

Wet Bulk density Mass of wet  
Density of sand (PCF) x soil (g)  
(PCF) Mass of sand filling hole

Wet  
Density (PCF)


MOISTURE DETERMINATION

Container ID <u>AFG</u>	
Mass of wet soil & container (g)	<u>233.4</u>
Mass of dry soil & container (g)	<u>213.3</u>
Mass of water (g)	<u>20.1</u>
Mass of dry soil & container (g)	<u>213.3</u>
Mass of container (g)	<u>133.4</u>
Mass of dry soil (g)	<u>79.9</u>
Moisture content (%)	<u>25.2</u>

SOIL DATA: PROCTOR # E000721-3

Proctor Dry Density (PCF) 97.0  
Proctor Optimum Moisture (%) 25.0  
Required Moisture (%): 25.0 to 30.0  
Required Compaction (%): 95.0

TEST RESULTS:

Pass  
 Failed Moisture  
 Failed Compaction

BY: Ryan Harris TIME: 10:30

Dry Density =  $\frac{\text{Wet Density (PCF)} \times 100.0}{\text{Moisture content (\%)} + 100.0}$

Dry Density =  $\frac{120.3 \times 100.0}{25.2 + 100.0} = 96.1$  pcf

Percent Compaction =  $\frac{\text{Dry Density} \times 100.0}{\text{Proctor Density}}$

Percent Compaction =  $\frac{96.1 \times 100.0}{97.0} = 99.1$  %

QC OFFICER APPROVAL: Ryan Harris DATE: 8-15-2000

QA OFFICER APPROVAL: D. [Signature] DATE: 8-15-00

# ENVIROCARE OF UTAH, INC.

**ORIGINAL**

## FIELD DENSITY TEST

(EC-1905, rev. 4)

PROJECT: \_\_\_\_\_ LARV: \_\_\_\_\_ MW: 4 lie.(2): \_\_\_\_\_ OTHER (specify): \_\_\_\_\_

LIFT IDENTIFICATION: ECL000811 DATE: 8-11-00

WASTE OR TEST ID NUMBER(S): 37 lot 5

TEST LOCATION: 025 N 1357 E TEST METHOD: \_\_\_\_\_ D1556 + D2922

**D2922 DENSITY DETERMINATION  
(NUCLEAR DENSITY GAUGE)  
GAUGE ID NO. 2512B**

On-Cell Standard:	Off-Cell Standard:
Density _____	Density _____
Counts _____	Counts <u>2544</u>
Moisture _____	Moisture _____
Counts _____	Counts <u>730</u>
Depth Setting _____	Count Time _____
(inches) <u>6</u>	(minutes) <u>1</u>
Moisture _____	Density _____
Counts <u>226</u>	Counts <u>2427</u>
Wet _____	Dry _____
Density _____	Density _____
(PCF) <u>121.3</u>	(PCF) <u>104.5</u>
Moisture _____	Moisture _____
Density _____	Fraction _____
(PCF) <u>16.8</u>	(%) <u>16.1</u>

**D1556 DENSITY DETERMINATION  
(SAND CONE)**

Bulk Density of sand (PCF) G.C 8/11/00

Mass of Sand to Fill Cone & Plate (g) \_\_\_\_\_

Mass of bottle & cone before filling cone, plate, & hole (g) \_\_\_\_\_

Mass of bottle & cone, after filling cone, plate, & hole (g) \_\_\_\_\_

Mass of sand to fill cone, plate, & hole (g) \_\_\_\_\_

Mass of sand to fill cone & plate (g) \_\_\_\_\_

Mass of sand to fill hole (g) \_\_\_\_\_

Mass of wet soil & container (g) \_\_\_\_\_

Mass of container (g) \_\_\_\_\_

Mass of wet soil (g) \_\_\_\_\_

Wet Bulk density of wet soil (g) \_\_\_\_\_

Density (PCF) =  $\frac{\text{Mass of wet soil (g)}}{\text{Mass of sand filling hole (g)}} \times \text{Bulk density of sand (PCF)}$

Wet Density (PCF) \_\_\_\_\_

**MOISTURE DETERMINATION**

Container ID <u>AH</u>	
Mass of wet soil & container (g)	<u>230.6</u>
Mass of dry soil & container (g)	<u>210.5</u>
Mass of water (g)	<u>20.1</u>
Mass of dry soil & container (g)	<u>210.5</u>
Mass of container (g)	<u>130.6</u>
Mass of dry soil (g)	<u>79.9</u>
Moisture content (%)	<u>25.2</u>

**SOIL DATA: PROCTOR # F000721-3**

Proctor Dry Density (PCF) 97.0

Proctor Optimum Moisture (%) 25.0

Required Moisture (%): 25.0 to 30.0

Required Compaction (%): 95.0

**TEST RESULTS:**

Pass

Failed Moisture

Failed Compaction

BY: Evan Harris TIME: 1030

Dry Density =  $\frac{\text{Wet Density (PCF)} \times 100.0}{\text{Moisture content (\%)} + 100.0}$

Dry Density =  $\frac{121.3 \times 100.0}{25.2 + 100.0} = 96.9$  pcf

Percent Compaction =  $\frac{\text{Dry Density} \times 100.0}{\text{Proctor Density}}$

Percent Compaction =  $\frac{96.9 \times 100.0}{97.0} = 99.9$  %

Rex L Seal  
QC OFFICER APPROVAL

8-15-2000  
DATE

[Signature]  
QA OFFICER APPROVAL

8-15-00  
DATE

**ENVIRO CARE OF UTAH, INC.**  
**FIELD PERMEABILITY TEST**  
 (EC-1906 rev 1)

**ORIGINAL**

REVISION: 05/03/00

PROJECT: \_\_\_\_\_ LARW: \_\_\_\_\_ MW: X 11e(2): \_\_\_\_\_ OTHER (specify) \_\_\_\_\_  
 Test Location: 100BN 1360 E Elevation/Lift 5th Lot No. 2

TESTING DATA: TESTED BY: Ryan Harriss  
 Soil Saturation Start: Date: 8-10-00 Time: 1500 Max. Dry Density 92.0 pcf  
 Soil Saturation Finish: Date: 8-11-00 Time: 0800 Opt. Moisture 25.0 %  
 Depth of Wet Front (L) 4.3 cm  
 Radius of Measuring Tube (Rt) .16 cm Density test # 34  
 Radius of Permeameter Ring (Rr) 13.02 cm Dry Density 98.3 pcf  
 Height of Water, (Ht) 140.0 cm Moisture content 25.5 %  
 Soil/Water temp, in ring, after test N/R °C N/R 11e(2) Compaction 101.4 %

$dH = \text{Change in Head (cm)} = 5.9 \text{ cm} \times 0.01667 = 0.12294125 \text{ cm/sec}$   
 $dT = \text{Time (minutes)} = 8 \text{ min}$   
 $R = 1.000 \text{ (From Figure 1) } * (R = 1.000 \text{ for } 11e(2))$


$$K_s = \left[ \frac{(2) (dH/dT) (L)}{(Ht) + (0.5) (L)} \right] \left[ \frac{(Rt)^2}{(Rr)^2} \right] \times (R)$$

$$K_s = \left[ \frac{(2)(0.12294125)(4.3)}{(140.0) + (0.5)(4.3)} \right] \left[ \frac{(.16)^2}{(13.02)^2} \right] \times 1.000$$

$K_s = 1.1 \times 10^{-7} \text{ cm/sec}$

Timed Water Drop Reading

min.	min.	min.
0.00	20.8	4.20 17.8
0.20	20.6	4.40 17.4
0.40	20.4	5.00 17.1
1.00	20.1	5.20 16.8
1.20	19.8	5.40 16.5
1.40	19.6	6.00 16.3
2.00	19.4	6.20 16.0
2.20	19.2	6.40 15.8
2.40	19.0	7.00 15.5
3.00	18.8	7.20 15.3
3.20	18.6	7.40 15.1
3.40	18.4	8.00 14.9
4.00	18.1	



Soil/Water Temp (°C)	Corr. Factor (R)
0	1.783
1	1.723
2	1.664
3	1.611
4	1.560
5	1.511
6	1.465
7	1.421
8	1.379
9	1.339
10	1.301
11	1.265
12	1.230
13	1.197
14	1.165
15	1.135
16	1.106
17	1.077
18	1.051
19	1.025
20	1.000
21	0.976
22	0.953
23	0.931
24	0.910
25	0.889
26	0.869
27	0.850
28	0.832
29	0.814
30	0.797
31	0.780
32	0.764
33	0.749
34	0.733
35	0.719
36	0.705
37	0.692
38	0.678
39	0.665
40	0.653

Figure 1

Required Permeability  $1.1 \times 10^{-7} - 5 \times 10^{-7} \text{ cm/sec}$  Test Results Pass Fail By Glencha Date 8-11-00

Reed Leach  
 QC APPROVAL

8-15-2000  
 DATE

D. [Signature]  
 QA APPROVAL

8-15-00  
 DATE

**EC-1905 Calculation Check**

Lift ID: ECR12020314 Clay Liner R12 1711N; 1189E

Date: 3/14/02 4th Lift

Lift / Lot Number	Proctor Dry Dens	Proctor Opti.Moist	Mass of Soil+Cont	Dry Mass soil+cont	Water Mass	Cont Mass	Mass of dry soil	Moist Cont	Wet Dens	Dry Dens	% Comp	Moist. Diff. Act. - Opti.	Proctor ID Number	Liner/RB OK?
4th/1	100.0	23.5	382.7	326.0	56.7	133.2	192.8	29.4	118.3	91.4	91.4	5.9	S5020221-1	Yes
4th/1A (Retest)	100.0	23.5	328.2	308.2	20.0	228.2	80.0	25.0	118.1	94.5	94.5	1.5	S5020221-1	Yes
4th/1 B (Retest)	100.0	23.5	326.5	307.2	19.3	226.5	80.7	23.9	119.6	96.5	96.5	0.4	S5020221-1	Yes
4th/2	100.0	23.5	459.6	411.4	48.2	228.2	183.2	26.3	119.4	94.5	94.5	2.8	S5020221-1	Yes
4th/2A (Retest)	100.0	23.5	327.6	306.4	21.2	227.6	78.8	26.9	118.6	93.5	93.5	3.4	S5020221-1	Yes
4th/2B (Retest)	100.0	23.5	326.5	306.5	20.0	226.5	80.0	25.0	121.7	97.4	97.4	1.5	S5020221-1	Yes
4th/3	100.0	23.5	464.7	412.6	52.1	226.8	185.8	28.0	118.1	92.3	92.3	4.5	S5020221-1	Yes
4th/3A (Retest)	100.0	23.5	231.9	211.5	20.4	131.9	79.6	25.6	119.7	95.3	95.3	2.1	S5020221-1	Yes
4th/4	100.0	23.5	463.6	413.7	49.9	236.6	177.1	28.2	115.9	90.4	90.4	4.7	S5020221-1	Yes
4th/4A (Retest)	100.0	23.5	327.4	305.9	21.5	227.4	78.5	27.4	120.7	94.7	94.7	3.9	S5020221-1	Yes
4th/4B (Retest)	100.0	23.5	229.5	210.3	19.2	129.5	80.8	23.8	119.7	96.7	96.7	0.3	S5020221-1	Yes
4th/5	100.0	23.5	431.5	388.9	42.6	227.8	161.1	26.4	118.5	93.8	93.8	2.9	S5020221-1	Yes
4th/5A (Retest)	100.0	23.5	336.6	315.9	20.7	236.6	79.3	26.1	120.7	95.7	95.7	2.6	S5020221-1	Yes
4th/6	100.0	23.5	475.2	421.6	53.6	232.3	189.3	28.3	119.6	93.2	93.2	4.8	S5020221-1	Yes
4th/6A (Retest)	100.0	23.5	327.4	308.1	19.3	227.4	80.7	23.9	121.9	98.4	98.4	0.4	S5020221-1	Yes
4th/7	100.0	23.5	453.8	410.6	43.2	227.6	183.0	23.6	119.7	96.8	96.8	0.1	S5020221-1	Yes
4th/8	100.0	23.5	459.3	412.1	47.2	227.0	185.1	25.5	121.0	96.4	96.4	2.0	S5020221-1	Yes
4th/9	100.0	23.5	465.9	422.7	43.2	227.5	195.2	22.1	121.9	99.8	99.8	-1.4	S5020221-1	Yes
4th/9A (Retest)	100.0	23.5	328.1	309.0	19.1	228.0	81.0	23.6	123.1	99.6	99.6	0.1	S5020221-1	Yes
4th/10	100.0	23.5	432.8	394.3	38.5	232.5	161.8	23.8	119.6	96.6	96.6	0.3	S5020221-1	Yes
4th/11	100.0	23.5	477.4	432.3	45.1	227.8	204.5	22.1	123.0	100.7	100.7	-1.4	S5020221-1	Yes
4th/11A (Retest)	100.0	23.5	327.6	307.3	20.3	227.6	79.7	25.5	121.7	97.0	97.0	2.0	S5020221-1	Yes
4th/12	100.0	23.5	337.8	298.2	39.6	130.6	167.6	23.6	122.9	99.4	99.4	0.1	S5020221-1	Yes
4th/13	100.0	23.5	451.5	409.5	42.0	232.6	176.9	23.7	118.2	95.6	95.6	0.2	S5020221-1	Yes
4th/14	100.0	23.5	370.6	324.7	45.9	129.5	195.2	23.5	122.1	98.9	98.9	0.0	S5020221-1	Yes
4th/15	100.0	23.5	467.9	422.7	45.2	226.6	196.1	23.0	122.8	99.8	99.8	-0.5	S5020221-1	Yes
4th/15A (Retest)	100.0	23.5	332.0	312.5	19.5	232.0	80.5	24.2	120.6	97.1	97.1	0.7	S5020221-1	Yes
4th/16	100.0	23.5	445.8	402.7	43.1	231.3	171.4	25.1	122.9	98.2	98.2	1.6	S5020221-1	Yes
4th/17	100.0	23.0	443.3	407.7	35.6	227.8	179.9	19.8	120.7	100.8	100.8	-3.2	S5020221-2	Yes
4th/17A (Retest)	100.0	23.0	326.8	307.7	19.1	226.8	80.9	23.6	118.5	95.9	95.9	0.6	S5020221-2	Yes
4th/18	100.0	23.0	455.3	405.3	50.0	227.8	177.5	28.2	127.4	99.4	99.4	5.2	S5020221-2	Yes
4th/18A (Retest)	100.0	23.0	229.6	209.1	20.5	129.6	79.5	25.8	121.0	96.2	96.2	2.8	S5020221-2	Yes

**Permeability Testing Lot 8**

Depth of Wet Front	3.4	cm
Radius of Tube	0.16	cm
Radius of Ring	13.02	cm
Height of Water	157.1	cm
Soil/Water Temp	N/R	°C
R (from Table)	1	
Change in Head	11	cm
Time	8	min
<b>K<sub>s</sub></b>	<b>1.5E-07</b>	<b>cm/sec</b>

**Sand Cone Lot # 18**

Density of sand	92.4	pcf
Mass of sand to fill cone & plate	1710.7	g
Mass of sand & bottle before filling hole	6118.7	g
Mass of sand & bottle after filling hole & cone	3150.8	g
Mass of sand to fill hole & cone	2967.9	g
Mass of sand to fill hole	1257.2	g
Mass of soil & container	1745.5	g
Mass of container	12.3	g
Mass of wet soil	1733.2	g
<b>Wet density of soil</b>	<b>127.4</b>	<b>pcf</b>
Wet density per nuclear density gauge	123.1	pcf
Wet density correlation $\geq .95$ and $\leq 1.05$	0.97	

# E1 VIROCARE OF UTA, INC.

**LIFT APPROVAL FORM**  
(EC-1904, rev. 5)

ORIGINAL

PROJECT:      LARW      MW  11e.(2)      CLASS A      OTHER Clay liner - R12

NW CORNER

DATE: 3/14/02

PAGE 1 of 2

<p style="font-size: 1.5em; transform: rotate(-30deg); opacity: 0.5;">N/A NB 3/8/02 See page 2 of 2</p>	P <sub>1</sub>	EW: <u>    </u> X <u>    </u> = <u>    </u>	NS: <u>    </u> X <u>    </u> = <u>    </u>
	P <sub>2</sub>	EW: <u>    </u> X <u>    </u> = <u>    </u>	NS: <u>    </u> X <u>    </u> = <u>    </u>
	P <sub>3</sub>	EW: <u>    </u> X <u>    </u> = <u>    </u>	NS: <u>    </u> X <u>    </u> = <u>    </u>
	P <sub>4</sub>	EW: <u>    </u> X <u>    </u> = <u>    </u>	NS: <u>    </u> X <u>    </u> = <u>    </u>
	P <sub>5</sub>	EW: <u>    </u> X <u>    </u> = <u>    </u>	NS: <u>    </u> X <u>    </u> = <u>    </u>
	Page 2 attached: <input checked="" type="checkbox"/> N		

IDENTIFY LOTS ABOVE

LIFT ID: ECR12020314 NW CORNER: N 1711 E 1189 INTERFACE RANDOM #: N/R

WASTE GENERATOR ID NUMBER(S): N/R

THICKNESS: UNC: 9.0" COM: N/R ELEV: N/R Debris Insp. By: N/R Date: N/R Time: N/R

DEBRIS CALCULATIONS: N/R

KEYING IN NOTES: NESW Satisfactory DENSITY TESTS ID # (S): 47-104, 49A, 50A, 51B, 52A, 55A, 57A, 61A, 62A, 64A

COMMENTS: This lift of clay liner was placed and compacted in accordance with ETP 98-1. Lots 1, 2, 3, 4, 5, 6, 9, 11, 15, 17, 18 failed on 3/14/02. Lots were retested on 3/19/02 after contractor worked failing lots. Lots 1, 2 and 4 failed retest on 3/19/02. Lots were retested on 3/20/02 after contractor worked failing lots. All lots meet specifications

LIFT APPROVED BY: [Signature] DATE: 3/21/02 TIME: 1651

[Signature] 3/21/02 D. Jones 4 3-25-02

QC OFFICER APPROVAL

DATE

QA OFFICER APPROVAL

DATE

RJA 3.21-02


ENVIROCARE OF UTAH, INC

RANDOM NUMBER TEST ID FORM

(Continuation Sheet)

ORIGINAL

DATE: 3/4/02 PAGE: 2 of 2  
 LIFT ID: ECR12 020314 LIFT NW CORNER: N1711, E1189  
*4th lift*



LOT	nw N	nw E	NS Side	EW Side	Rand N	Rand E	Test dN	Test dE	Test N	Test E
P 1	1,711	1,189	66	102	0.600	0.555	40	57	1,671	1,246
P 2	1,711	1,291	66	100	0.407	0.136	27	14	1,684	1,305
P 3	1,645	1,189	66	102	0.778	0.299	51	31	1,594	1,220
P 4	1,645	1,291	66	100	0.582	0.636	38	64	1,607	1,355
P 5	1,579	1,189	66	102	0.455	0.990	30	101	1,549	1,290
P 6	1,579	1,291	66	100	0.592	0.603	39	60	1,540	1,351
P 7	1,513	1,189	66	102	0.812	0.395	54	40	1,459	1,229
P 8	1,513	1,291	66	100	0.200	0.562	13	56	1,500	1,347
P 9	1,447	1,189	66	102	0.837	0.864	55	88	1,392	1,277
P 10	1,447	1,291	66	100	0.418	0.286	28	29	1,419	1,320
P 11	1,381	1,189	66	102	0.776	0.968	51	99	1,330	1,288
P 12	1,381	1,291	66	100	0.591	0.558	39	56	1,342	1,347
P 13	1,315	1,189	66	102	0.837	0.397	55	40	1,260	1,229
P 14	1,315	1,291	66	100	0.717	0.193	47	19	1,268	1,310
P 15	1,249	1,189	66	102	0.144	0.092	9	9	1,240	1,198
P 16	1,249	1,291	66	100	0.032	0.297	2	30	1,247	1,321
P 17	1,183	1,189	64	102	0.938	0.642	60	65	1,123	1,254
P 18	1,183	1,291	64	100	0.834	0.786	53	79	1,130	1,370

COMMENTS: \_\_\_\_\_  
 \_\_\_\_\_  
 \_\_\_\_\_

# ENVIROCARE OF UTAH INC.

## FIELD DENSITY TEST

(EC-1905, rev. 5)

ORIGINAL

PROJECT: LARW MW 11e. (2) CLASS A OTHER         

LIFT IDENTIFICATION: ACR12020314 DATE: 3-14-02

WASTE OR TEST ID NUMBER(S): 47 lot 1

TEST LOCATION: N1671 E1246 TEST METHOD: D1556  X D2922

**D2922 DENSITY DETERMINATION**  
(NUCLEAR DENSITY GAUGE)  
GAUGE ID NO. 19481

On-Cell Standard:	Off-Cell Standard:
Density	Density
Counts <u>        </u>	Counts <u>2501</u>
Moisture	Moisture
Counts <u>        </u>	Counts <u>050</u>
Depth Setting	Count Time
(inches) <u>8</u>	(minutes) <u>1</u>
Moisture	Density
Counts <u>230</u>	Counts <u>1438</u>
Wet	Dry
Density	Density
(PCF) <u>118.3</u>	(PCF) <u>98.0</u>
Moisture	Moisture
Density	Fraction
(PCF) <u>20.3</u>	(%) <u>20.7</u>

**D1556 DENSITY DETERMINATION**  
(SAND CONE)

Bulk Density of sand (PCF) \_\_\_\_\_

Mass of Sand to Fill Cone & Plate (g) \_\_\_\_\_

Mass of bottle & cone before filling cone, plate, & hole (g) \_\_\_\_\_

Mass of bottle & cone, after filling cone, plate, & hole (g) \_\_\_\_\_

Mass of sand to fill cone, plate, & hole (g) \_\_\_\_\_

Mass of sand to fill cone & plate (g) \_\_\_\_\_

Mass of sand to fill hole (g) \_\_\_\_\_

Mass of wet soil & container (g) \_\_\_\_\_

Mass of container (g) \_\_\_\_\_

Mass of wet soil (g) \_\_\_\_\_


Wet Bulk density Mass of wet  
Density = of sand (PCF) X soil (g)  
(PCF) Mass of sand filling hole

Wet = \_\_\_\_\_  
Density (PCF)

**MOISTURE DETERMINATION**

Container ID B25

Mass of wet soil & container (g)	382.7
Mass of dry soil & container (g)	326.0
Mass of water (g)	56.7
Mass of dry soil & container (g)	326.0
Mass of container (g)	133.2
Mass of dry soil (g)	192.8
Moisture content (%)	29.4

Dry Density =  $\frac{\text{Wet Density (PCF)} \times 100.0}{\text{Moisture content (\%)} + 100.0}$

Dry Density =  $\frac{118.3 \times 100.0}{29.4 + 100.0} = 91.4$  pcf

Percent Compaction =  $\frac{\text{Dry Density} \times 100.0}{\text{Proctor Density}}$

Percent Compaction =  $\frac{91.4 \times 100.0}{100.0} = 91.4$  %

**SOIL DATA:** PROCTOR # S502022L1

Proctor Dry Density (PCF) 100.0

Proctor Optimum Moisture (%) 23.5

Required Moisture (%): 23.5 to 28.5

Required Compaction (%): 95.0%

**TEST RESULTS:**

Pass

Failed Moisture

Failed Compaction

BY: 502/10n TIME: 1300

QC OFFICER APPROVAL \_\_\_\_\_ DATE 3/21/02

QA OFFICER APPROVAL D Young 4 DATE 3-25-02

RR 3-21-02

# E.I. TROCARE OF UTAH INC.

## FIELD DENSITY TEST

(EC-1905, rev 5)

ORIGINAL

PROJECT: LARW MW 4 11e. (2) CLASS A OTHER    

LIFT IDENTIFICATION: ELR12020314 DATE: 3/19/02

WASTE OR ~~TEST~~ ID NUMBER(S): 47A lot 1

TEST LOCATION: M1471 E 1244 TEST METHOD:     D1556 X D2922

**D2922 DENSITY DETERMINATION  
(NUCLEAR DENSITY GAUGE)**  
GAUGE ID NO. 19481

On-Cell Standard: Density Counts Moisture Counts Depth Setting (inches) <u>8</u> Moisture Counts <u>202</u> Wet Density (PCF) <u>118.1</u> Moisture Density (PCF) <u>18.4</u>	Off-Cell Standard: Density Counts <u>2504</u> Moisture Counts <u>420</u> Count Time (minutes) <u>1</u> Density Counts <u>1453</u> Dry Density (PCF) <u>99.5</u> Moisture Fraction (%) <u>18.7</u>
---	---

**D1556 DENSITY DETERMINATION  
(SAND CONE)**

Bulk Density of sand (PCF) \_\_\_\_\_  
Mass of Sand to Fill Cone & Plate (g) \_\_\_\_\_

Mass of bottle & cone before filling cone, plate, & hole (g) \_\_\_\_\_  
Mass of bottle & cone, after filling cone, plate, & hole (g) \_\_\_\_\_  
Mass of sand to fill cone, plate, & hole (g) \_\_\_\_\_  
Mass of sand to fill cone & plate (g) \_\_\_\_\_  
Mass of sand to fill hole (g) \_\_\_\_\_  
Mass of wet soil & container (g) \_\_\_\_\_  
Mass of container (g) \_\_\_\_\_  
Mass of wet soil (g) \_\_\_\_\_

Wet Bulk density Mass of wet  
Density of sand (PCF) X soil (g)  
(PCF) Mass of sand filling hole  
Wet \_\_\_\_\_  
Density (PCF) \_\_\_\_\_

**MOISTURE DETERMINATION**

Container ID <u>15</u>	
Mass of wet soil & container (g)	328.2
Mass of dry soil & container (g)	308.2
Mass of water (g)	20.0
Mass of dry soil & container (g)	308.2
Mass of container (g)	228.2
Mass of dry soil (g)	80.0
Moisture content (%)	25.0%

SOIL DATA: PROCTOR # 55020226-1  
Proctor  
Dry Density (PCF) 100.0  
Proctor  
Optimum Moisture (%) 23.5  
Required  
Moisture (%): 23.5 to 28.5  
Required  
Compaction (%): 95.0%

Dry Density =  $\frac{\text{Wet Density (PCF)} \times 100.0}{\text{Moisture content (\%)} + 100.0}$   
Dry Density =  $\frac{118.1 \times 100.0}{25.0\% + 100.0} = 94.5$  pcf

Percent Compaction =  $\frac{\text{Dry Density} \times 100.0}{\text{Proctor Density}}$   
Percent Compaction =  $\frac{94.5 \times 100.0}{100.0} = 94.5\%$

TEST RESULTS:  
\_\_\_\_ Pass  
\_\_\_\_ Failed Moisture  
X Failed Compaction  
BY: MD TIME: 1400

QC OFFICER APPROVAL

DATE

QA OFFICER APPROVAL

DATE

*MD* 3-21-02

3/21/02

[Signature]

3-25-02

# E1 TROCARE OF UTAH, INC.

## FIELD DENSITY TEST

(EC-1905, rev. 5)

ORIGINAL

PROJECT: LARW MW 2 11a.(2) CLASS A OTHER     

LIFT IDENTIFICATION: ECR12020314 DATE: 3/21/02

WASTE OR TEST ID NUMBER(S): 4713 Lat 1

TEST LOCATION: M11091 E1244 TEST METHOD: D1556 4 D2922

**D2922 DENSITY DETERMINATION**  
(NUCLEAR DENSITY GAUGE)  
GAUGE ID NO. 19481

On-Cell Standard:	Off-Cell Standard:
Density	Density
Counts <u>    </u>	Counts <u>2505</u>
Moisture	Moisture
Counts <u>    </u>	Counts <u>1048</u>
Depth Setting	Count Time
(inches) <u>8</u>	(minutes) <u>1</u>
Moisture	Density
Counts <u>205</u>	Counts <u>1400</u>
Wet	Dry
Density	Density
(PCF) <u>119.6</u>	(PCF) <u>101.6</u>
Moisture	Moisture
Density	Fraction
(PCF) <u>18.0</u>	(%) <u>17.2</u>

**D1556 DENSITY DETERMINATION**  
(SAND CONE)

Bulk Density of sand (PCF)     

Mass of Sand to Fill Cone & Plate (g)     

Mass of bottle & cone before filling cone, plate, & hole (g)     

Mass of bottle & cone, after filling cone, plate, & hole (g)     

Mass of sand to fill cone, plate, & hole     

Mass of sand to fill cone & plate (g)     

Mass of sand to fill hole (g)     

Mass of wet soil & container (g)     

Mass of container (g)     

Mass of wet soil (g)     

Wet Bulk density Mass of wet Density of sand (PCF) X soil (g) (PCF)      Mass of sand filling hole

Wet     

Density (PCF)     

**MOISTURE DETERMINATION**

Container ID <u>X1</u>	
Mass of wet soil & container (g)	<u>324.5</u>
Mass of dry soil & container (g)	<u>307.2</u>
Mass of water (g)	<u>19.3</u>
Mass of dry soil & container (g)	<u>307.2</u>
Mass of container (g)	<u>224.5</u>
Mass of dry soil (g)	<u>81.7</u>
Moisture content (%)	<u>23.9</u>

Dry Density =  $\frac{\text{Wet Density (PCF)} \times 100.0}{\text{Moisture content (\%)} + 100.0}$

Dry Density =  $\frac{119.6 \times 100.0}{23.9 + 100.0} = 96.5$  pcf

Percent Compaction =  $\frac{\text{Dry Density} \times 100.0}{\text{Proctor Density}}$

Percent Compaction =  $\frac{96.5 \times 100.0}{100.0} = 96.5$  %

SOIL DATA: PROCTOR # 3502021-1

Proctor Dry Density (PCF) 100.0

Proctor Optimum Moisture (%) 23.5

Required Moisture (%): 23.5 to 28.5

Required Compaction (%): 95.0

TEST RESULTS:

X Pass

     Failed Moisture

     Failed Compaction

BY:      TIME: 1150

QC OFFICER APPROVAL      DATE 3/21/02

QA OFFICER APPROVAL      DATE 3-25-02

RSL 3-21-02

# ENVIROCARE OF UTAH INC.

## FIELD DENSITY TEST

(EC-1905, rev. 5)

ORIGINAL

PROJECT: LARW MM 11s. (2) CLASS A OTHER \_\_\_\_\_

LIFT IDENTIFICATION: EACR12020314 DATE: 3-14-02

WASTE OR TEST ID NUMBER(S): 48 lot 2

TEST LOCATION: N 1684 E 1305 TEST METHOD: D1556  D2922

**D2922 DENSITY DETERMINATION**  
(NUCLEAR DENSITY GAUGE)  
GAUGE ID NO. 19481

On-Cell Standard:	Off-Cell Standard:
Density	Density
Counts <u>          </u>	Counts <u>2501</u>
Moisture	Moisture
Counts <u>          </u>	Counts <u>650</u>
Depth Setting	Count Time
(inches) <u>8</u>	(minutes) <u>1</u>
Moisture	Density
Counts <u>226</u>	Counts <u>1594</u>
Wet	Dry
Density	Density
(PCF) <u>119.4</u>	(PCF) <u>99.4</u>
Moisture	Moisture
Density	Fraction
(PCF) <u>19.9</u>	(%) <u>20.0</u>

**D1556 DENSITY DETERMINATION**  
(SAND CONE)

Bulk Density of sand (PCF) \_\_\_\_\_

Mass of Sand to Fill Cone & Plate (g) \_\_\_\_\_

Mass of bottle & cone before filling cone, plate, & hole (g) \_\_\_\_\_

Mass of bottle & cone, after filling cone, plate, & hole (g) \_\_\_\_\_

Mass of sand to fill cone, plate, & hole (g) \_\_\_\_\_

Mass of sand to fill cone & plate (g) \_\_\_\_\_

Mass of sand to fill hole (g) \_\_\_\_\_

Mass of wet soil & container (g) \_\_\_\_\_

Mass of container (g) \_\_\_\_\_

Mass of wet soil (g) \_\_\_\_\_

Wet	Bulk density	Mass of wet
Density	of sand (PCF)	soil (g)
(PCF)	Mass of sand filling hole	

Wet \_\_\_\_\_

Density (PCF) \_\_\_\_\_

**MOISTURE DETERMINATION**

Container ID E5

Mass of wet soil & container (g)	<u>459.4</u>
Mass of dry soil & container (g)	<u>411.4</u>
Mass of water (g)	<u>48.2</u>
Mass of dry soil & container (g)	<u>411.4</u>
Mass of container (g)	<u>228.2</u>
Mass of dry soil (g)	<u>183.2</u>
Moisture content (%)	<u>26.3</u>

Dry Density =  $\frac{\text{Wet Density (PCF)} \times 100.0}{\text{Moisture content (\%)} + 100.0}$

Dry Density =  $\frac{119.4 \times 100.0}{26.3 + 100.0} = 94.5$  pcf

Percent Compaction =  $\frac{\text{Dry Density} \times 100.0}{\text{Proctor Density}}$

Percent Compaction =  $\frac{94.5 \times 100.0}{100.0} = 94.5$  %

**SOIL DATA:** PROCTOR # S5020221-1

Proctor Dry Density (PCF) 100.0

Proctor Optimum Moisture (%) 23.5

Required Moisture (%): 23.5 to 28.5

Required Compaction (%): 95.0%

**TEST RESULTS:**

Pass \_\_\_\_\_

Failed Moisture \_\_\_\_\_

Failed Compaction

BY: J. D. Ken TIME: 1300

QC OFFICER APPROVAL \_\_\_\_\_ DATE 3/21/02

QA OFFICER APPROVAL D. Jones 4 DATE 3-25-02

*RR 3-21-02*

# ELECTROCORE OF UTAH, INC.

## FIELD DENSITY TEST (EC-1905, rev. 5)

ORIGINAL

PROJECT:     LARW         MW         11e. (2)     CLASS     A     OTHER     

LIFT IDENTIFICATION:     EUP12020314     DATE:     3/19/02    

WASTE OR ~~TEST~~ ID NUMBER(S):     48A         Dot 2    

TEST LOCATION:     N 11084 E 1305     TEST METHOD:     D1556         K         D2922    

**D2922 DENSITY DETERMINATION  
(NUCLEAR DENSITY GAUGE)**  
GAUGE ID NO.     19481    

On-Cell Standard:	Off-Cell Standard:
Density	Density
Counts <u>    </u>	Counts <u>    2504    </u>
Moisture	Moisture
Counts <u>    </u>	Counts <u>    620    </u>
Depth Setting	Count Time
(inches) <u>    8    </u>	(minutes) <u>    1    </u>
Moisture	Density
Counts <u>    221    </u>	Counts <u>    1428    </u>
Wet	Dry
Density	Density
(PCF) <u>    118.4    </u>	(PCF) <u>    98.1    </u>
Moisture	Moisture
Density	Fraction
(PCF) <u>    20.5    </u>	(%) <u>    20.9    </u>

**D1556 DENSITY DETERMINATION  
(SAND CONE)**

Bulk Density of sand (PCF)	<u>    </u>
Mass of Sand to Fill Cone & Plate (g)	<u>    </u>
Mass of bottle & cone before filling cone, plate, & hole (g)	<u>    </u>
Mass of bottle & cone, after filling cone, plate, & hole (g)	<u>    </u>
Mass of sand to fill cone, plate, & hole (g)	<u>    </u>
Mass of sand to fill cone & plate (g)	<u>    </u>
Mass of sand to fill hole (g)	<u>    </u>
Mass of wet soil & container (g)	<u>    </u>
Mass of container (g)	<u>    </u>
Mass of wet soil (g)	<u>    </u>
Wet Bulk density of sand (PCF)	<u>    </u>
Mass of wet soil (g)	<u>    </u>
Mass of sand filling hole (g)	<u>    </u>
Wet Density (PCF)	<u>    </u>

**MOISTURE DETERMINATION**

Container ID <u>    R2    </u>	
Mass of wet soil & container (g)	<u>    327.4    </u>
Mass of dry soil & container (g)	<u>    300.4    </u>
Mass of water (g)	<u>    27.2    </u>
Mass of dry soil & container (g)	<u>    300.4    </u>
Mass of container (g)	<u>    227.4    </u>
Mass of dry soil (g)	<u>    78.8    </u>
Moisture content (%)	<u>    20.9    </u>

Dry Density =  $\frac{\text{Wet Density (PCF)} \times 100.0}{\text{Moisture content (\%)} + 100.0}$

Dry Density =  $\frac{118.4 \times 100.0}{20.9 + 100.0} = 93.5$  pcf

Percent Compaction =  $\frac{\text{Dry Density} \times 100.0}{\text{Proctor Density}}$

Percent Compaction =  $\frac{93.5}{100.0} \times 100.0 = 93.5\%$

**SOIL DATA:** PROCTOR #     55020221-1    

Proctor Dry Density (PCF)     100.0    

Proctor Optimum Moisture (%)     23.5    

Required Moisture (%):     23.5     to     28.5    

Required Compaction (%):     95.0%    

**TEST RESULTS:**

Pass

Failed Moisture

Failed Compaction

BY:     AD     TIME:     1400    

    [Signature]      
QC OFFICER APPROVAL

    3/21/02      
DATE

    [Signature]      
QA OFFICER APPROVAL

    3-25-02      
DATE

    R02 3-21-02

# E.I. TROCARE OF UTAH, INC.

FIELD DENSITY TEST  
(EC-1905, rev. 5)

ORIGINAL

PROJECT: LARW MW K 11e.(2) CLASS A OTHER \_\_\_\_\_

LIFT IDENTIFICATION: ECR/2020314 DATE: 3/20/02

WASTE OR ~~TEST~~ ID NUMBER(S): 48B lot 2

TEST LOCATION: M 1684 G 1305 TEST METHOD: D1556 K D2922

**D2922 DENSITY DETERMINATION  
(NUCLEAR DENSITY GAUGE)**  
GAUGE ID NO. 19481

On-Cell Standard: Density Counts _____ Moisture Counts _____ Depth Setting (inches) <u>8</u> Moisture Counts <u>202</u> Wet Density (PCF) <u>121.7</u> Moisture Density (PCF) <u>17.7</u>	Off-Cell Standard: Density Counts <u>2505</u> Moisture Counts <u>648</u> Count Time (minutes) <u>1</u> Density Counts <u>1520</u> Dry Density (PCF) <u>163.9</u> Moisture Fraction (%) <u>17.1</u>
---	--

**D1556 DENSITY DETERMINATION  
(SAND CONE)**

Bulk Density of sand (PCF) _____ Mass of Sand to Fill Cone & Plate (g) _____ Mass of bottle & cone before filling cone, plate, & hole (g) _____ Mass of bottle & cone, after filling cone, plate, & hole (g) _____ Mass of sand to fill cone, plate, & hole (g) _____ Mass of sand to fill cone & plate (g) _____ Mass of sand to fill hole (g) _____ Mass of wet soil & container (g) _____ Mass of container (g) _____ Mass of wet soil (g) _____	<table border="1" style="width: 100%; height: 100%;"> <tr><td style="height: 20px;"> </td></tr> </table>										

Wet Bulk density Mass of wet Density of sand (PCF) x soil (g) (PCF) Mass of sand filling hole

Wet Density (PCF) \_\_\_\_\_

**MOISTURE DETERMINATION**

Container ID <u>X1</u>	
Mass of wet soil & container (g)	326.5
Mass of dry soil & container (g)	306.5
Mass of water (g)	20.0
Mass of dry soil & container (g)	306.5
Mass of container (g)	224.5
Mass of dry soil (g)	80.0
Moisture content (%)	25.0%

Dry Density =  $\frac{\text{Wet Density (PCF)} \times 100.0}{\text{Moisture content (\%)} + 100.0}$

Dry Density =  $\frac{121.7 \times 100.0}{25.0 + 100.0} = 97.4$  pcf

Percent Compaction =  $\frac{\text{Dry Density} \times 100.0}{\text{Proctor Density}}$

Percent Compaction =  $\frac{97.4 \times 100.0}{100.0} = 97.4$  %

**SOIL DATA:** PROCTOR # 55020221-1

Proctor Dry Density (PCF) 100.0

Proctor Optimum Moisture (%) 23.5

Required Moisture (%): 23.5 to 28.5

Required Compaction (%): 95.0%

**TEST RESULTS:**

Pass

Failed Moisture

Failed Compaction

BY: MM TIME: 11:50

QC OFFICER APPROVAL \_\_\_\_\_ DATE 3/21/02

QA OFFICER APPROVAL D Young DATE 3-25-02

*Handwritten:* R02 3-21-02

# ENVIROCARÉ OF UTAH INC.

## FIELD DENSITY TEST

(EC-1905, rev. 5)

ORIGINAL

PROJECT: LARW MW 11e. (2) CLASS A OTHER \_\_\_\_\_

LIFT IDENTIFICATION: EALR12020314 DATE: 3-14-02

WASTE OR TEST ID NUMBER(S): 49 lot 3

TEST LOCATION: N 1594 E 1220 TEST METHOD: D1556 X D2922

**D2922 DENSITY DETERMINATION  
(NUCLEAR DENSITY GAUGE)**

GAUGE ID NO. 19481

On-Cell Standard: Density Counts Moisture Counts Depth Setting (inches) Moisture Counts Wet Density (PCF) Moisture Density (PCF)	Off-Cell Standard: Density Counts Moisture Counts Count Time (minutes) Density Counts Dry Density (PCF) Moisture Fraction (%)
<u>233</u> <u>6</u> <u>233</u> <u>118.1</u> <u>20.4</u>	<u>2501</u> <u>1050</u> <u>1</u> <u>1044</u> <u>97.4</u> <u>21.1</u>

**D1556 DENSITY DETERMINATION  
(SAND CONE)**

Bulk Density of sand (PCF) \_\_\_\_\_  
 Mass of Sand to Fill Cone & Plate (g) \_\_\_\_\_  
 Mass of bottle & cone before filling cone, plate, & hole (g) \_\_\_\_\_  
 Mass of bottle & cone, after filling cone, plate, & hole (g) \_\_\_\_\_  
 Mass of sand to fill cone, plate, & hole (g) \_\_\_\_\_  
 Mass of sand to fill cone & plate (g) \_\_\_\_\_  
 Mass of sand to fill hole (g) \_\_\_\_\_  
 Mass of wet soil & container (g) \_\_\_\_\_  
 Mass of container (g) \_\_\_\_\_  
 Mass of wet soil (g) \_\_\_\_\_


Wet Bulk density of sand (PCF) X soil (g) \_\_\_\_\_  
 Density (PCF) Mass of sand filling hole \_\_\_\_\_  
 Wet Density (PCF) \_\_\_\_\_

**MOISTURE DETERMINATION**

Container ID	<u>All</u>
Mass of wet soil & container (g)	<u>409.7</u>
Mass of dry soil & container (g)	<u>412.6</u>
Mass of water (g)	<u>52.1</u>
Mass of dry soil & container (g)	<u>412.6</u>
Mass of container (g)	<u>224.8</u>
Mass of dry soil (g)	<u>185.8</u>
Moisture content (%)	<u>28.0</u>

Dry Density =  $\frac{\text{Wet Density (PCF)} \times 100.0}{\text{Moisture content (\%)} + 100.0}$

Dry Density =  $\frac{118.1 \times 100.0}{28.0 + 100.0} = 92.3$  pcf

Percent Compaction =  $\frac{\text{Dry Density} \times 100.0}{\text{Proctor Density}}$

Percent Compaction =  $\frac{92.3 \times 100.0}{100.0} = 92.3$  %

SOIL DATA: PROCTOR # S5020221-1

Proctor Dry Density (PCF) 100.0

Proctor Optimum Moisture (%) 23.5

Required Moisture (%): 23.5 to 28.5

Required Compaction (%): 95.0%

TEST RESULTS:

Pass

Failed Moisture

Failed Compaction

BY: S. Dalton TIME: 1300

QC OFFICER APPROVAL: \_\_\_\_\_ DATE: 3/21/02 QA OFFICER APPROVAL: \_\_\_\_\_ DATE: 3-25-02

*RD 3-21-02*

# EL TROCARE OF UTAH, INC.

## FIELD DENSITY TEST (EC-1905, rev. 5)

ORIGINAL

PROJECT: LARW MW L 11e. (2) CLASS A OTHER \_\_\_\_\_

LIFT IDENTIFICATION: EUR2020314 DATE: 3/19/02

WASTE OR TEST ID NUMBER(S): 49A Lot 3

TEST LOCATION: M1594 E1220 TEST METHOD: D1556 E D2922

**D2922 DENSITY DETERMINATION  
(NUCLEAR DENSITY GAUGE)  
GAUGE ID NO. 1948**

On-Cell Standard:	Off-Cell Standard:
Density Counts _____	Density Counts <u>2504</u>
Moisture Counts _____	Moisture Counts <u>1020</u>
Depth Setting (inches) <u>8</u>	Count Time (minutes) <u>1</u>
Moisture Counts <u>184</u>	Density Counts <u>1591</u>
Wet Density (PCF) <u>119.7</u>	Dry Density (PCF) <u>102.9</u>
Moisture Density (PCF) <u>16.8</u>	Moisture Fraction (%) <u>14.3</u>

**D1556 DENSITY DETERMINATION  
(SAND CONE)**

Bulk Density of sand (PCF) \_\_\_\_\_  
Mass of Sand to Fill Cone & Plate (g) \_\_\_\_\_

Mass of bottle & cone before filling cone, plate, & hole (g) \_\_\_\_\_  
Mass of bottle & cone, after filling cone, plate, & hole (g) \_\_\_\_\_  
Mass of sand to fill cone, plate, & hole (g) \_\_\_\_\_  
Mass of sand to fill cone & plate (g) \_\_\_\_\_  
Mass of sand to fill hole (g) \_\_\_\_\_  
Mass of wet soil & container (g) \_\_\_\_\_

Mass of container (g) \_\_\_\_\_  
Mass of wet soil (g) \_\_\_\_\_

Wet Bulk density of sand (PCF) \_\_\_\_\_  
Mass of wet soil (g) \_\_\_\_\_  
Wet Density (PCF) \_\_\_\_\_


**MOISTURE DETERMINATION**

Container ID <u>E</u>	
Mass of wet soil & container (g)	231.9
Mass of dry soil & container (g)	211.5
Mass of water (g)	20.4
Mass of dry soil & container (g)	211.5
Mass of container (g)	131.9
Mass of dry soil (g)	79.6
Moisture content (%)	25.4

Dry Density =  $\frac{\text{Wet Density (PCF)} \times 100.0}{\text{Moisture content (\%)} + 100.0}$   
 Dry Density =  $\frac{119.7 \times 100.0}{25.4 + 100.0} = 95.3$  pcf

Percent Compaction =  $\frac{\text{Dry Density} \times 100.0}{\text{Proctor Density}}$   
 Percent Compaction =  $\frac{95.3 \times 100.0}{100.0} = 95.3 \%$

**SOIL DATA:**

PROCTOR # 550202212 1/14/02  
 Proctor Dry Density (PCF) 100.0  
 Proctor Optimum Moisture (%) 23.5  
 Required Moisture (%): 23.5 to 28.5  
 Required Compaction (%): 95.0%

**TEST RESULTS:**

Pass  
 Failed Moisture  
 Failed Compaction  
 BY: AD TIME: 1400

QC OFFICER APPROVAL \_\_\_\_\_

DATE 3/21/02

QA OFFICER APPROVAL \_\_\_\_\_

DATE 3-25-02

*RSD 3-21-02*

ENTROCARÉ OF UTAH INC.

FIELD DENSITY TEST  
(EC-1905, rev. 5)

ORIGINAL

PROJECT: LARW MW 11e. (2) CLASS A OTHER \_\_\_\_\_

LIFT IDENTIFICATION: ACR12020314 DATE: 3-14-02

WASTE OR TEST ID NUMBER(S): 50 lot 4

TEST LOCATION: N 1607 E 1355 TEST METHOD: D1556  D2922

D2922 DENSITY DETERMINATION  
(NUCLEAR DENSITY GAUGE)  
GAUGE ID NO. 19481

On-Cell Standard:	Off-Cell Standard:
Density Counts _____	Density Counts <u>2501</u>
Moisture Counts _____	Moisture Counts <u>650</u>
Depth Setting (inches) <u>8</u>	Count Time (minutes) <u>1</u>
Moisture Counts <u>200</u>	Density Counts <u>1742</u>
Wet Density (PCF) <u>115.9</u>	Dry Density (PCF) <u>98.5</u>
Moisture Density (PCF) <u>17.5</u>	Moisture Fraction (%) <u>17.7</u>

D1556 DENSITY DETERMINATION  
(SAND CONE)

Bulk Density of sand (PCF) \_\_\_\_\_

Mass of Sand to Fill Cone & Plate (g) \_\_\_\_\_

Mass of bottle & cone before filling cone, plate, & hole (g) \_\_\_\_\_

Mass of bottle & cone after filling cone, plate, & hole (g) \_\_\_\_\_

Mass of sand to fill cone, plate, & hole (g) \_\_\_\_\_

Mass of sand to fill cone & plate (g) \_\_\_\_\_

Mass of sand to fill hole (g) \_\_\_\_\_

Mass of wet soil & container (g) \_\_\_\_\_

Mass of container (g) \_\_\_\_\_

Mass of wet soil (g) \_\_\_\_\_

Wet Density (PCF) \_\_\_\_\_

Bulk density of sand (PCF) \_\_\_\_\_

Mass of wet soil (g) \_\_\_\_\_

Mass of sand filling hole \_\_\_\_\_

MOISTURE DETERMINATION

Container ID <u>A8</u>	
Mass of wet soil & container (g)	<u>463.4</u>
Mass of dry soil & container (g)	<u>413.7</u>
Mass of water (g)	<u>49.9</u>
Mass of dry soil & container (g)	<u>413.7</u>
Mass of container (g)	<u>234.4</u>
Mass of dry soil (g)	<u>177.1</u>
Moisture content (%)	<u>28.2</u>

Dry Density =  $\frac{\text{Wet Density (PCF)} \times 100.0}{\text{Moisture content (\%)} + 100.0}$

Dry Density =  $\frac{115.9 \times 100.0}{28.2 + 100.0} = 90.4$  pcf

Percent Compaction =  $\frac{\text{Dry Density} \times 100.0}{\text{Proctor Density}}$

Percent Compaction =  $\frac{90.4}{100.0} \times 100.0 = 90.4\%$

SOIL DATA: PROCTOR # S5020221-1

Proctor Dry Density (PCF) 100.0

Proctor Optimum Moisture (%) 23.5

Required Moisture (%): 23.5 to 28.5

Required Compaction (%): 95.0%

TEST RESULTS:

Pass

Failed Moisture

Failed Compaction

BY: J. DeLeon TIME: 1300

QC OFFICER APPROVAL \_\_\_\_\_ DATE 3/21/02

QA OFFICER APPROVAL D. Jones DATE 3-25-02

RQ 3-21-02

# ELECTROCORE OF UTAH, INC.

## FIELD DENSITY TEST ORIGINAL

(EC-1905, rev. 5)

PROJECT: LARW MW X 11e. (2) CLASS A OTHER \_\_\_\_\_

LIFT IDENTIFICATION: EUR12020214 DATE: 3/19/02

WASTE OR ~~TEST~~ ID NUMBER(S): 50A Lot 4

TEST LOCATION: M1009 E1355 TEST METHOD: \_\_\_\_\_ D1556 X D2922

**D2922 DENSITY DETERMINATION**  
(NUCLEAR DENSITY GAUGE)  
GAUGE ID NO. 19481

On-Cell Standard:	Off-Cell Standard:
Density	Density
Counts	Counts <u>2504</u>
Moisture	Moisture
Counts	Counts <u>470</u>
Depth Setting (inches)	Count Time (minutes)
<u>8</u>	<u>1</u>
Moisture	Density
Counts <u>177</u>	Counts <u>1593</u>
Wet	Dry
Density (PCF) <u>120.7</u>	Density (PCF) <u>104.4</u>
Moisture	Moisture
Density (PCF) <u>116.1</u>	Fraction (%) <u>15.4</u>

**D1556 DENSITY DETERMINATION**  
(SAND CONE)

Bulk Density of sand (PCF) \_\_\_\_\_

Mass of Sand to Fill Cone & Plate (g) \_\_\_\_\_

Mass of bottle & cone before filling cone, plate, & hole (g) \_\_\_\_\_

Mass of bottle & cone, after filling cone, plate, & hole (g) \_\_\_\_\_

Mass of sand to fill cone, plate, & hole (g) \_\_\_\_\_

Mass of sand to fill cone & plate (g) \_\_\_\_\_

Mass of sand to fill hole (g) \_\_\_\_\_

Mass of wet soil & container (g) \_\_\_\_\_

Mass of container (g) \_\_\_\_\_

Mass of wet soil (g) \_\_\_\_\_

Wet Bulk density of sand (PCF) \_\_\_\_\_

Mass of wet soil (g) \_\_\_\_\_

Mass of sand filling hole (g) \_\_\_\_\_

Wet Density (PCF) =  $\frac{\text{Mass of wet soil (g)}}{\text{Mass of sand filling hole (g)}} \times \text{Bulk density of sand (PCF)}$

**MOISTURE DETERMINATION**

Container ID E

Mass of wet soil & container (g)	<u>327.4</u>
Mass of dry soil & container (g)	<u>309.9</u>
Mass of water (g)	<u>21.5</u>
Mass of dry soil & container (g)	<u>305.9</u>
Mass of container (g)	<u>227.4</u>
Mass of dry soil (g)	<u>78.5</u>
Moisture content (%)	<u>27.4</u>

Dry Density =  $\frac{\text{Wet Density (PCF)} \times 100.0}{\text{Moisture content (\%)} + 100.0}$

Dry Density =  $\frac{120.7 \times 100.0}{27.4 + 100.0} = 94.7$  pcf

Percent Compaction =  $\frac{\text{Dry Density} \times 100.0}{\text{Proctor Density}}$

Percent Compaction =  $\frac{94.7 \times 100.0}{100.0} = 94.7\%$

**SOIL DATA:** PROCTOR # 55020221-1

Proctor Dry Density (PCF) 100.0

Proctor Optimum Moisture (%) 23.5

Required Moisture (%): 23.5 to 28.5

Required Compaction (%): 95.0%

**TEST RESULTS:**

Pass \_\_\_\_\_

Failed Moisture X

Failed Compaction X

BY: MD TIME: 1400

QC OFFICER APPROVAL \_\_\_\_\_ DATE 3/21/02

QA OFFICER APPROVAL D. Young 4 DATE 3-25-02

RDJ 3-21-02

# E. MIROCARE OF UTAH, INC.

## FIELD DENSITY TEST ORIGINAL

(EC-1905, rev. 5)

PROJECT: LARW MW 11e.(2) CLASS A OTHER \_\_\_\_\_

LIFT IDENTIFICATION: ECR12020314 DATE: 3/20/02

WASTE OR ~~TEST~~ ID NUMBER(S): 503 Lot 4

TEST LOCATION: 41607 E 1385 TEST METHOD: D1556 X D2922

**D2922 DENSITY DETERMINATION**  
(NUCLEAR DENSITY GAUGE)  
GAUGE ID NO. 19481

On-Cell Standard:	Off-Cell Standard:
Density	Density
Counts	Counts <u>2505</u>
Moisture	Moisture
Counts	Counts <u>448</u>
Depth Setting	Count Time
(inches) <u>8</u>	(minutes) <u>1</u>
Moisture	Density
Counts <u>203</u>	Counts <u>1594</u>
Wet	Dry
Density	Density
(PCF) <u>119.7</u>	(PCF) <u>101.7</u>
Moisture	Moisture
Density	Fraction
(PCF) <u>17.8</u>	(%) <u>17.5</u>

**D1556 DENSITY DETERMINATION**  
(SAND CONE)

Bulk Density of sand (PCF)	_____
Mass of Sand to Fill Cone & Plate (g)	_____
Mass of bottle & cone before filling cone, plate, & hole (g)	_____
Mass of bottle & cone after filling cone, plate, & hole (g)	_____
Mass of sand to fill cone, plate, & hole (g)	_____
Mass of sand to fill cone & plate (g)	_____
Mass of sand to fill hole (g)	_____
Mass of wet soil & container (g)	_____
Mass of container (g)	_____
Mass of wet soil (g)	_____
Wet Bulk density of sand (PCF)	_____
Mass of wet soil (g)	_____
Mass of sand filling hole (g)	_____
Wet Density (PCF)	_____

**MOISTURE DETERMINATION**

Container ID	<u>EE</u>
Mass of wet soil & container (g)	<u>229.5</u>
Mass of dry soil & container (g)	<u>210.3</u>
Mass of water (g)	<u>19.2</u>
Mass of dry soil & container (g)	<u>210.3</u>
Mass of container (g)	<u>129.5</u>
Mass of dry soil (g)	<u>80.8</u>
Moisture content (%)	<u>23.8</u>

Dry Density =  $\frac{\text{Wet Density (PCF)} \times 100.0}{\text{Moisture content (\%)} + 100.0}$

Dry Density =  $\frac{119.7 \times 100.0}{23.8 + 100.0} = 96.7$  pcf

Percent Compaction =  $\frac{\text{Dry Density} \times 100.0}{\text{Proctor Density}}$

Percent Compaction =  $\frac{96.7 \times 100.0}{100.0} = 96.7$  %

SOIL DATA: PROCTOR # 58020221-1

Proctor Dry Density (PCF) 100.0

Proctor Optimum Moisture (%) 23.5

Required Moisture (%): 23.5 to 28.5

Required Compaction (%): 95.0%

TEST RESULTS:

X Pass

Failed Moisture

Failed Compaction

BY: MD TIME: 1100

QC OFFICER APPROVAL \_\_\_\_\_ DATE 3/21/02 QA OFFICER APPROVAL D. Davis DATE 3-25-02

RWJ 3-21-02

# ENVIRONMENTAL CARE OF UTAH INC.

## FIELD DENSITY TEST

(EC-1905, rev. 5)

PROJECT: LARW MW 11e. (2) CLASS A OTHER \_\_\_\_\_  
 LIFT IDENTIFICATION: EACR12020314 DATE: 3-14-02  
 WASTE OR TEST ID NUMBER(S): 51 lot 5  
 TEST LOCATION: N 1549 E 1290 TEST METHOD: D1556  D2922

**D2922 DENSITY DETERMINATION**  
 (NUCLEAR DENSITY GAUGE)  
 GAUGE ID NO. 19481

On-Cell Standard:                      Off-Cell Standard:                       
 Density                      Density                       
 Counts                      Counts 2501  
 Moisture                      Moisture                       
 Counts                      Counts 650  
 Depth Setting                      Count Time                       
 (inches) 8 (minutes) 1  
 Moisture                      Density                       
 Counts 215 Counts 1031  
 Wet                      Dry                       
 Density                      Density                       
 (PCF) 118.5 (PCF) 99.7  
 Moisture                      Moisture                       
 Density                      Fraction                       
 (PCF) 18.9 (%) 19.0

**MOISTURE DETERMINATION**

Container ID E2

Mass of wet soil & container (g)	431.5
Mass of dry soil & container (g)	388.9
Mass of water (g)	42.6
Mass of dry soil & container (g)	388.9
Mass of container (g)	227.8
Mass of dry soil (g)	161.1
Moisture content (%)	26.4

Dry Density =  $\frac{\text{Wet Density (PCF)} \times 100.0}{\text{Moisture content (\%)} + 100.0}$

Dry Density =  $\frac{118.5 \times 100.0}{26.4 + 100.0} = 93.8$  pcf

Percent Compaction =  $\frac{\text{Dry Density} \times 100.0}{\text{Proctor Density}}$

Percent Compaction =  $\frac{93.8 \times 100.0}{100.0} = 93.8\%$

**D1556 DENSITY DETERMINATION**  
 (SAND CONE)

Bulk Density of sand (PCF) \_\_\_\_\_  
 Mass of Sand to Fill Cone & Plate (g) \_\_\_\_\_  
 Mass of bottle & cone before filling cone, plate, & hole (g) \_\_\_\_\_  
 Mass of bottle & cone, after filling cone, plate, & hole (g) \_\_\_\_\_  
 Mass of sand to fill cone, plate, & hole (g) \_\_\_\_\_  
 Mass of sand to fill cone & plate (g) \_\_\_\_\_  
 Mass of sand to fill hole (g) \_\_\_\_\_  
 Mass of wet soil & container (g) \_\_\_\_\_  
 Mass of container (g) \_\_\_\_\_  
 Mass of wet soil (g) \_\_\_\_\_

Wet Bulk density of sand (PCF)                      Mass of wet soil (g)                       
 Density                      X soil (g)                       
 (PCF) Mass of sand filling hole                     

Wet Density (PCF)                     

**SOIL DATA:** PROCTOR # S502022-1

Proctor Dry Density (PCF) 100.0  
 Proctor Optimum Moisture (%) 23.5  
 Required Moisture (%): 23.5 to 28.5  
 Required Compaction (%): 95.0%

**TEST RESULTS:**

Pass  
 Failed Moisture  
 Failed Compaction  
 BY: S. Dalton TIME: 1300

QC OFFICER APPROVAL: \_\_\_\_\_ DATE: 3/21/02 QA OFFICER APPROVAL: O Young 4 DATE: 3-25-02

*Handwritten:* RRF 3-21-02

# E. TIROCARE OF UTAH, INC.

## FIELD DENSITY TEST

(EC-1905, rev. 5)

PROJECT: LARW MW 11e. (2) CLASS A OTHER

LIFT IDENTIFICATION: ECR12020314 DATE: 3/19/02

WASTE OR ~~TEST~~ ID NUMBER(S): 51A lots

TEST LOCATION: M 1549 E 1290 TEST METHOD: D1556 X D2922

**D2922 DENSITY DETERMINATION**  
(NUCLEAR DENSITY GAUGE)  
GAUGE ID NO. 19481

On-Cell Standard:	Off-Cell Standard:
Density	Density
Counts	Counts <u>2504</u>
Moisture	Moisture
Counts	Counts <u>420</u>
Depth Setting	Count Time
(inches) <u>8</u>	(minutes) <u>1</u>
Moisture	Density
Counts <u>212</u>	Counts <u>1549</u>
Wet	Dry
Density	Density
(PCF) <u>120.7</u>	(PCF) <u>101.1</u>
Moisture	Moisture
Density	Fraction
(PCF) <u>19.4</u>	(%) <u>19.4</u>

**D1556 DENSITY DETERMINATION**  
(SAND CONE)

Bulk Density of sand (PCF) \_\_\_\_\_  
Mass of Sand to Fill Cone & Plate (g) \_\_\_\_\_

Mass of bottle & cone before filling cone, plate, & hole (g) \_\_\_\_\_  
Mass of bottle & cone after filling cone, plate, & hole (g) \_\_\_\_\_  
Mass of sand to fill cone, plate, & hole (g) \_\_\_\_\_  
Mass of sand to fill cone & plate (g) \_\_\_\_\_  
Mass of sand to fill hole (g) \_\_\_\_\_  
Mass of wet soil & container (g) \_\_\_\_\_  
Mass of container (g) \_\_\_\_\_  
Mass of wet soil (g) \_\_\_\_\_

Wet Bulk density Mass of wet  
Density = of sand (PCF) X soil (g)  
(PCF) Mass of sand filling hole

Wet = \_\_\_\_\_  
Density (PCF)

**MOISTURE DETERMINATION**

Container ID	<u>AB</u>
Mass of wet soil & container (g)	<u>336.4</u>
Mass of dry soil & container (g)	<u>315.9</u>
Mass of water (g)	<u>20.7</u>
Mass of dry soil & container (g)	<u>315.9</u>
Mass of container (g)	<u>236.4</u>
Mass of dry soil (g)	<u>79.3</u>
Moisture content (%)	<u>26.1</u>

Dry Density =  $\frac{\text{Wet Density (PCF)} \times 100.0}{\text{Moisture content (\%)} + 100.0}$   
 Dry Density =  $\frac{120.7 \times 100.0}{26.1 + 100.0} = 95.7$  pcf

Percent Compaction =  $\frac{\text{Dry Density} \times 100.0}{\text{Proctor Density}}$   
 Percent Compaction =  $\frac{95.7 \times 100.0}{100.0} = 95.7\%$

SOIL DATA: PROCTOR # 95020221-1  
 Proctor Dry Density (PCF) 100.0  
 Proctor Optimum Moisture (%) 23.0  
 Required Moisture (%): 23.0 to 28.0  
 Required Compaction (%): 95.0%

TEST RESULTS:  
 Pass  
 Failed Moisture  
 Failed Compaction  
 BY: MD TIME: 1400

QC OFFICER APPROVAL \_\_\_\_\_ DATE 3/21/02 QA OFFICER APPROVAL 4 DATE 3-25-02

MD 3-21-02

# ENVIROCORE OF UTAH INC.

## FIELD DENSITY TEST

(EC-1905, rev. 5)

ORIGINAL

PROJECT: LARW MW 11e.(2) CLASS A OTHER \_\_\_\_\_

LIFT IDENTIFICATION: EACR12020314 DATE: 3-14-02

WASTE OR TEST ID NUMBER(S): 52 lot 6

TEST LOCATION: N 1540 E 1351 TEST METHOD: \_\_\_\_\_ D1556 X D2922

**D2922 DENSITY DETERMINATION  
(NUCLEAR DENSITY GAUGE)**  
GAUGE ID NO. 19491

On-Cell Standard:	Off-Cell Standard:
Density Counts _____	Density Counts <u>2501</u>
Moisture Counts _____	Moisture Counts <u>650</u>
Depth Setting (inches) <u>8</u>	Count Time (minutes) <u>1</u>
Moisture Counts <u>237</u>	Density Counts <u>1584</u>
Wet Density (PCF) <u>119.4</u>	Dry Density (PCF) <u>98.4</u>
Moisture Density (PCF) <u>21.0</u>	Moisture Fraction (%) <u>21.3</u>

**D1556 DENSITY DETERMINATION  
(SAND CONE)**

Bulk Density of sand (PCF) \_\_\_\_\_

Mass of Sand to Fill Cone & Plate (g) \_\_\_\_\_

Mass of bottle & cone before filling cone, plate, & hole (g) \_\_\_\_\_

Mass of bottle & cone after filling cone, plate, & hole (g) \_\_\_\_\_

Mass of sand to fill cone, plate, & hole (g) \_\_\_\_\_

Mass of sand to fill cone & plate (g) \_\_\_\_\_

Mass of sand to fill hole (g) \_\_\_\_\_

Mass of wet soil & container (g) \_\_\_\_\_

Mass of container (g) \_\_\_\_\_

Mass of wet soil (g) \_\_\_\_\_

Wet Density (PCF) \_\_\_\_\_

Bulk density of sand (PCF) \_\_\_\_\_

Mass of wet soil (g) \_\_\_\_\_

Mass of sand filling hole \_\_\_\_\_

**MOISTURE DETERMINATION**

Container ID <u>C5</u>	
Mass of wet soil & container (g)	<u>475.2</u>
Mass of dry soil & container (g)	<u>421.6</u>
Mass of water (g)	<u>53.6</u>
Mass of dry soil & container (g)	<u>421.6</u>
Mass of container (g)	<u>232.3</u>
Mass of dry soil (g)	<u>189.3</u>
Moisture content (%)	<u>28.3</u>

Dry Density =  $\frac{\text{Wet Density (PCF)} \times 100.0}{\text{Moisture content (\%)} + 100.0}$

Dry Density =  $\frac{119.6 \times 100.0}{28.3 + 100.0} = 93.2$  pcf

Percent Compaction =  $\frac{\text{Dry Density} \times 100.0}{\text{Proctor Density}}$

Percent Compaction =  $\frac{93.2 \times 100.0}{100.0} = 93.2$  %

SOIL DATA: PROCTOR # S5020221-1

Proctor Dry Density (PCF) 100.0

Proctor Optimum Moisture (%) 23.5

Required Moisture (%): 23.5 to 28.5

Required Compaction (%): 95.0%

TEST RESULTS:

Pass

Failed Moisture

Failed Compaction

BY: J. D. Hen TIME: 1300

QC OFFICER APPROVAL \_\_\_\_\_ DATE 3/21/02

QA OFFICER APPROVAL D. [Signature] DATE 3-25-02

ROJ 3-21-02

# ENVIROCARE OF UTAH INC.

## FIELD DENSITY TEST

(EC-1905, rev. 5)

ORIGINAL

PROJECT: LARW MW K 11a. (2) CLASS A OTHER \_\_\_\_\_

LIFT IDENTIFICATION: ECR12020314 DATE 3/22/02

WASTE OR TEST ID NUMBER(S): 52A Dot 4

TEST LOCATION: M1540 E 1351 TEST METHOD: D1556 X D2922

**D2922 DENSITY DETERMINATION  
(NUCLEAR DENSITY GAUGE)**  
GAUGE ID NO. 19481

On-Cell Standard: Density Counts Moisture Counts Depth Setting (inches) <u>8</u> Moisture Counts <u>195</u> Wet Density (PCF) <u>121.9</u> Moisture Density (PCF) <u>17.9</u>	Off-Cell Standard: Density Counts <u>2504</u> Moisture Counts <u>420</u> Count Time (minutes) <u>1</u> Density Counts <u>1506</u> Dry Density (PCF) <u>104.0</u> Moisture Fraction (%) <u>17.2</u>
---	--

**D1556 DENSITY DETERMINATION  
(SAND CONE)**

Bulk Density of sand (PCF) \_\_\_\_\_  
Mass of Sand to Fill Cone & Plate (g) \_\_\_\_\_  
  
Mass of bottle & cone before filling cone, plate, & hole (g) \_\_\_\_\_  
Mass of bottle & cone, after filling cone, plate, & hole (g) 118.107 g  
Mass of sand to fill cone, plate, & hole (g) \_\_\_\_\_  
Mass of sand to fill cone & plate (g) \_\_\_\_\_  
Mass of sand to fill hole (g) \_\_\_\_\_  
Mass of wet soil & container (g) \_\_\_\_\_  
Mass of container (g) \_\_\_\_\_  
Mass of wet soil (g) \_\_\_\_\_


Wet Bulk density of sand (PCF) 118.107 g x soil (g) \_\_\_\_\_  
(PCF) Mass of sand filling hole \_\_\_\_\_  
Wet Density (PCF) \_\_\_\_\_

**MOISTURE DETERMINATION**

Container ID <u>A9</u>	
Mass of wet soil & container (g)	<u>327.4</u>
Mass of dry soil & container (g)	<u>308.1</u>
Mass of water (g)	<u>19.3</u>
Mass of dry soil & container (g)	<u>308.1</u>
Mass of container (g)	<u>227.4</u>
Mass of dry soil (g)	<u>80.7</u>
Moisture content (%)	<u>23.9</u>

Dry Density =  $\frac{\text{Wet Density (PCF)} \times 100.0}{\text{Moisture content (\%)} + 100.0}$

Dry Density =  $\frac{121.9 \times 100.0}{23.9 + 100.0} = 98.4$  pcf

Percent Compaction =  $\frac{\text{Dry Density} \times 100.0}{\text{Proctor Density}}$

Percent Compaction =  $\frac{98.4 \times 100.0}{100.0} = 98.4$  %

SOIL DATA: PROCTOR # 55020221-1  
Proctor Dry Density (PCF) 100.0  
Proctor Optimum Moisture (%) 23.5  
Required Moisture (%): 23.5 to 28.5  
Required Compaction (%): 95.0%

TEST RESULTS:  
X Pass  
\_\_\_\_ Failed Moisture  
\_\_\_\_ Failed Compaction  
BY: MD TIME: 1400

QC OFFICER APPROVAL \_\_\_\_\_ DATE 3/21/02

QA OFFICER APPROVAL D Jones 4 DATE 3-25-02

RDJ 3-21-02

ENVIRONMENTAL CARE OF UTAH INC

FIELD DENSITY TEST

(EC-1905, rev. 5)

ORIGINAL

PROJECT: LARW MW 11e.(2) CLASS A OTHER \_\_\_\_\_

LIFT IDENTIFICATION: EACR 2020314 DATE: 3-14-02

WASTE OR TEST ID NUMBER(S): 53 Lot 7

TEST LOCATION: N 1459 E 1229 TEST METHOD: D1556 X D2922

D2922 DENSITY DETERMINATION  
(NUCLEAR DENSITY GAUGE)

GAUGE ID NO. 19481

On-Cell Standard:	Off-Cell Standard:
Density	Density
Counts	Counts <u>2501</u>
Moisture	Moisture
Counts	Counts <u>1050</u>
Depth Setting	Count Time
(inches) <u>8</u>	(minutes) <u>1</u>
Moisture	Density
Counts <u>192</u>	Counts <u>1588</u>
Wet	Dry
Density	Density
(PCF) <u>119.7</u>	(PCF) <u>103.0</u>
Moisture	Moisture
Density	Fraction
(PCF) <u>14.7</u>	(%) <u>14.2</u>

D1556 DENSITY DETERMINATION  
(SAND CONE)

Bulk Density of sand (PCF) \_\_\_\_\_  
Mass of Sand to Fill Cone & Plate (g) \_\_\_\_\_

Mass of bottle & cone before filling cone, plate, & hole (g) \_\_\_\_\_  
Mass of bottle & cone, after filling cone, plate, & hole (g) \_\_\_\_\_

Mass of sand to fill cone, plate, & hole (g) \_\_\_\_\_  
Mass of sand to fill cone & plate (g) \_\_\_\_\_  
Mass of sand to fill hole (g) \_\_\_\_\_  
Mass of wet soil & container (g) \_\_\_\_\_

Mass of container (g) \_\_\_\_\_

Mass of wet soil (g) \_\_\_\_\_

Wet Bulk density Mass of wet  
Density of sand (PCF) X soil (g)  
(PCF) Mass of sand filling hole

Wet \_\_\_\_\_  
Density (PCF) \_\_\_\_\_

SOIL DATA: PROCTOR # 55020221-1

Proctor Dry Density (PCF) 100.0

Proctor Optimum Moisture(%) 23.5

Required Moisture(%) : 23.5 to 28.5

Required Compaction(%) : 95.0%

TEST RESULTS:

Pass  
 Failed Moisture  
 Failed Compaction  
BY: S. D. [Signature] TIME: 1300

MOISTURE DETERMINATION

Container ID	<u>EQ</u>
Mass of wet soil & container (g)	<u>453.8</u>
Mass of dry soil & container (g)	<u>410.6</u>
Mass of water (g)	<u>43.2</u>
Mass of dry soil & container (g)	<u>410.6</u>
Mass of container (g)	<u>227.4</u>
Mass of dry soil (g)	<u>183.0</u>
Moisture content (%)	<u>23.6</u>

Dry Density =  $\frac{\text{Wet Density (PCF)} \times 100.0}{\text{Moisture content (\%)} + 100.0}$

Dry Density =  $\frac{119.7 \times 100.0}{23.6 + 100.0} = 96.8$  pcf

Percent Compaction =  $\frac{\text{Dry Density} \times 100.0}{\text{Proctor Density}}$

Percent Compaction =  $\frac{96.8 \times 100.0}{100.0} = 96.8$  %

QC OFFICER APPROVAL \_\_\_\_\_ DATE 3/21/02 QA OFFICER APPROVAL [Signature] DATE 3-25-02

ASJ 3-21-02

ENVIROCARE OF UTAH INC.

FIELD DENSITY TEST

(EC-1905, rev. 5)

ORIGINAL

PROJECT: LARW MW 11e.(2) CLASS A OTHER \_\_\_\_\_

LIFT IDENTIFICATION: EACR12020314 DATE: 3-14-02

WASTE OR TEST ID NUMBER(S): 54 lot 8

TEST LOCATION: N 1500 E 1347 TEST METHOD: D1556 X D2922

D2922 DENSITY DETERMINATION (NUCLEAR DENSITY GAUGE)

GAUGE ID NO. 19481

On-Cell Standard:	Off-Cell Standard:
Density	Density
Counts	Counts <u>2501</u>
Moisture	Moisture
Counts	Counts <u>650</u>
Depth Setting	Count Time
(inches) <u>8</u>	(minutes) <u>1</u>
Moisture	Density
Counts <u>230</u>	Counts <u>1531</u>
Wet	Dry
Density	Density
(PCF) <u>121.0</u>	(PCF) <u>100.7</u>
Moisture	Moisture
Density	Fraction
(PCF) <u>20.3</u>	(%) <u>20.2</u>

D1556 DENSITY DETERMINATION (SAND CONE)

Bulk Density of sand (PCF) \_\_\_\_\_

Mass of Sand to Fill Cone & Plate (g) \_\_\_\_\_

Mass of bottle & cone before filling cone, plate, & hole (g) \_\_\_\_\_

Mass of bottle & cone, after filling cone, plate, & hole (g) \_\_\_\_\_

Mass of sand to fill cone, plate, & hole (g) \_\_\_\_\_

Mass of sand to fill cone & plate (g) \_\_\_\_\_

Mass of sand to fill hole (g) \_\_\_\_\_

Mass of wet soil & container (g) \_\_\_\_\_

Mass of container (g) \_\_\_\_\_

Mass of wet soil (g) \_\_\_\_\_

Wet Bulk density of sand (PCF) X soil (g) \_\_\_\_\_

Density (PCF) \_\_\_\_\_

Mass of sand filling hole \_\_\_\_\_

Wet \_\_\_\_\_

Density (PCF) \_\_\_\_\_

MOISTURE DETERMINATION

Container ID	<u>A4</u>
Mass of wet soil & container (g)	<u>459.3</u>
Mass of dry soil & container (g)	<u>412.1</u>
Mass of water (g)	<u>47.2</u>
Mass of dry soil & container (g)	<u>412.1</u>
Mass of container (g)	<u>227.0</u>
Mass of dry soil (g)	<u>185.1</u>
Moisture content (%)	<u>25.5</u>

Dry Density =  $\frac{\text{Wet Density (PCF)} \times 100.0}{\text{Moisture content (\%)} + 100.0}$

Dry Density =  $\frac{121.0 \times 100.0}{25.5 + 100.0} = 96.4$  pcf

Percent Compaction =  $\frac{\text{Dry Density} \times 100.0}{\text{Proctor Density}}$

Percent Compaction =  $\frac{96.4 \times 100.0}{100.0} = 96.4$  %

SOIL DATA: PROCTOR # S5020221-1

Proctor Dry Density (PCF) 100.0

Proctor Optimum Moisture (%) 23.5

Required Moisture (%): 23.5 to 28.5

Required Compaction (%): 95.0%

TEST RESULTS:

Pass

Failed Moisture

Failed Compaction

BY: S. Dalton TIME: 1300

QC OFFICER APPROVAL \_\_\_\_\_ DATE 3/21/02

QA OFFICER APPROVAL \_\_\_\_\_ DATE 3-25-02

Ref 3-21-02

# ENVIRONMENTAL CARE OF UTAH INC.

## FIELD DENSITY TEST

(EC-1905, rev. 5)

ORIGINAL

PROJECT: LARW MW 11e. (2) CLASS A OTHER \_\_\_\_\_

LIFT IDENTIFICATION: ACR12020314 DATE: 3-14-02

WASTE OR TEST ID NUMBER(S): 55 lot 9

TEST LOCATION: N 1392 E 1277 TEST METHOD: D1556  D2922

**D2922 DENSITY DETERMINATION  
(NUCLEAR DENSITY GAUGE)**

GAUGE ID NO. 19481

On-Cell Standard:	Off-Cell Standard:
Density	Density
Counts	Counts <u>2501</u>
Moisture	Moisture
Counts	Counts <u>650</u>
Depth Setting	Count Time
(inches) <u>4</u>	(minutes) <u>?</u>
Moisture	Density
Counts <u>210</u>	Counts <u>1504</u>
Wet	Dry
Density	Density
(PCF) <u>121.9</u>	(PCF) <u>103.4</u>
Moisture	Moisture
Density	Fraction
(PCF) <u>18.4</u>	(%) <u>17.8</u>

**D1556 DENSITY DETERMINATION  
(SAND CONE)**

Bulk Density of sand (PCF) \_\_\_\_\_  
 Mass of Sand to Fill Cone & Plate (g) \_\_\_\_\_

Mass of bottle & cone before filling cone, plate, & hole (g) \_\_\_\_\_  
 Mass of bottle & cone after filling cone, plate, & hole (g) \_\_\_\_\_  
 Mass of sand to fill cone, plate, & hole (g) \_\_\_\_\_  
 Mass of sand to fill cone & plate (g) \_\_\_\_\_  
 Mass of sand to fill hole (g) \_\_\_\_\_  
 Mass of wet soil & container (g) \_\_\_\_\_

Mass of container (g) \_\_\_\_\_  
 Mass of wet soil (g) \_\_\_\_\_

Wet Density (PCF)	Bulk density of sand (PCF)	Mass of wet soil (g)
_____	_____	_____

Wet Density (PCF) =  $\frac{\text{Mass of wet soil (g)} - \text{Mass of container (g)}}{\text{Mass of sand filling hole (g)}}$

**MOISTURE DETERMINATION**

Container ID	<u>A7</u>
Mass of wet soil & container (g)	<u>465.9</u>
Mass of dry soil & container (g)	<u>422.7</u>
Mass of water (g)	<u>43.2</u>
Mass of dry soil & container (g)	<u>422.7</u>
Mass of container (g)	<u>227.5</u>
Mass of dry soil (g)	<u>195.2</u>
Moisture content (%)	<u>22.1</u>

Dry Density =  $\frac{\text{Wet Density (PCF)} \times 100.0}{\text{Moisture content (\%)} + 100.0}$

Dry Density =  $\frac{121.9 \times 100.0}{22.1 + 100.0} = 99.8$  pcf

Percent Compaction =  $\frac{\text{Dry Density} \times 100.0}{\text{Proctor Density}}$

Percent Compaction =  $\frac{99.8 \times 100.0}{100.0} = 99.8\%$

SOIL DATA: PROCTOR # S5020221-1

Proctor Dry Density (PCF) 100.0

Proctor Optimum Moisture (%) 23.5

Required Moisture (%): 23.5 to 28.5

Required Compaction (%): 95.0%

TEST RESULTS:

Pass

Failed Moisture

Failed Compaction

BY: J. Dalton TIME: 1300

QC OFFICER APPROVAL: \_\_\_\_\_ DATE: 3/21/02 QA OFFICER APPROVAL: D Young 4 DATE: 3-25-02

*RD* 3-21-02

ENVIROCARE OF UTA INC.

FIELD DENSITY TEST

(EC-1905, rev. 5)

ORIGINAL

PROJECT: LARW MW X 11a.(2) CLASS A OTHER \_\_\_\_\_

LIFT IDENTIFICATION: ECR12020314 DATE 3-19-02

WASTE OR TEST ID NUMBER(S): 55A 6+9

TEST LOCATION: N 1392 E 1277 TEST METHOD: D1556 X D2922

D2922 DENSITY DETERMINATION  
(NUCLEAR DENSITY GAUGE)

GAUGE ID NO. 17481

On-Cell Standard:	Off-Cell Standard:
Density	Density
Counts	Counts <u>2504</u>
Moisture	Moisture
Counts	Counts <u>620</u>
Depth Setting	Count Time
(inches) <u>8</u>	(minutes) <u>1</u>
Moisture	Density
Counts <u>193</u>	Counts <u>1463</u>
Wet	Dry
Density	Density
(PCF) <u>123.1</u>	(PCF) <u>105.4</u>
Moisture	Moisture
Density	Fraction
(PCF) <u>17.7</u>	(%) <u>16.8</u>

D1556 DENSITY DETERMINATION  
(SAND CONE)

Bulk Density of sand (PCF) \_\_\_\_\_

Mass of Sand to Fill Cone & Plate (g) \_\_\_\_\_

Mass of bottle & cone before filling cone, plate, & hole (g) \_\_\_\_\_

Mass of bottle & cone after filling cone, plate, & hole (g) \_\_\_\_\_

Mass of sand to fill cone, plate, & hole (g) \_\_\_\_\_

Mass of sand to fill cone & plate (g) \_\_\_\_\_

Mass of sand to fill hole (g) \_\_\_\_\_

Mass of wet soil & container (g) \_\_\_\_\_

Mass of container (g) \_\_\_\_\_

Mass of wet soil (g) \_\_\_\_\_

Wet Bulk density Mass of wet  
Density -of sand (PCF) X soil (g)  
(PCF) Mass of sand filling hole

Wet \_\_\_\_\_  
Density (PCF) \_\_\_\_\_

MOISTURE DETERMINATION

Container ID	<u>E4</u>
Mass of wet soil & container (g)	<u>328.1</u>
Mass of dry soil & container (g)	<u>309.0</u>
Mass of water (g)	<u>19.1</u>
Mass of dry soil & container (g)	<u>309.0</u>
Mass of container (g)	<u>228.0</u>
Mass of dry soil (g)	<u>81.0</u>
Moisture content (%)	<u>23.6</u> <sup>pc</sup> <u>23.5</u> <sup>std/102</sup>

Dry =  $\frac{\text{Wet Density (PCF)}}{\text{Moisture content (\%)} + 100.0} \times 100.0$

Density =  $\frac{123.1}{23.6} \times 100.0 = 99.6$  <sup>pc</sup> 99.7 <sup>std/102</sup> pcf

Percent Compaction =  $\frac{\text{Dry Density} \times 100.0}{\text{Proctor Density}}$

Percent Compaction =  $\frac{99.6}{99.7} \times 100.0 = 100.0$  <sup>std/102</sup>

SOIL DATA: PROCTOR # 55020221-1

Proctor Dry Density (PCF) 100.0

Proctor Optimum Moisture (%) 23.5

Required Moisture (%): 23.5 to 28.5

Required Compaction (%): 95.0 <sup>std</sup>

TEST RESULTS:

Pass

Failed Moisture

Failed Compaction

BY: Joe Dalton TIME: 1400

QC OFFICER APPROVAL \_\_\_\_\_ DATE 3/21/02

QA OFFICER APPROVAL \_\_\_\_\_ DATE 3-25-02

RD Reed 3-21-02



# ENVIROCARE OF UTAH INC.

## FIELD DENSITY TEST

(EC-1905, rev. 5)

ORIGINAL

PROJECT: LARW MW 11e.(2) CLASS A OTHER \_\_\_\_\_

LIFT IDENTIFICATION: EACR12020314 DATE: 3-14-02

WASTE OR **TEST** ID NUMBER(S): 57 Lot 11

TEST LOCATION: N 1330 E 1288 TEST METHOD: D1556  D2922

**D2922 DENSITY DETERMINATION  
(NUCLEAR DENSITY GAUGE)**

GAUGE ID NO. 19481

On-Cell Standard: Density Counts _____ Moisture Counts _____ Depth Setting (inches) <u>8</u> Moisture Counts <u>205</u> Wet Density (PCF) <u>123.0</u> Moisture Density (PCF) <u>17.9</u>	Off-Cell Standard: Density Counts <u>2501</u> Moisture Counts <u>650</u> Count Time (minutes) <u>1</u> Density Counts <u>1402</u> Dry Density (PCF) <u>105.1</u> Moisture Fraction (%) <u>17.1</u>
---	--

**MOISTURE DETERMINATION**

Container ID	<u>E8</u>
Mass of wet soil & container (g)	<u>477.4</u>
Mass of dry soil & container (g)	<u>432.3</u>
Mass of water (g)	<u>45.1</u>
Mass of dry soil & container (g)	<u>432.3</u>
Mass of container (g)	<u>227.8</u>
Mass of dry soil (g)	<u>204.5</u>
Moisture content (%)	<u>22.1</u>

Dry Density =  $\frac{\text{Wet Density (PCF)} \times 100.0}{\text{Moisture content (\%)} + 100.0}$

Dry Density =  $\frac{123.0 \times 100.0}{22.1 + 100.0} = 100.7$  pcf

Percent Compaction =  $\frac{\text{Dry Density} \times 100.0}{\text{Proctor Density}}$

Percent Compaction =  $\frac{100.7}{100.0} \times 100.0 = 100.7\%$

**D1556 DENSITY DETERMINATION  
(SAND CONE)**

Bulk Density of sand (PCF) \_\_\_\_\_

Mass of Sand to Fill Cone & Plate (g) \_\_\_\_\_

Mass of bottle & cone before filling cone, plate, & hole (g) \_\_\_\_\_

Mass of bottle & cone, after filling cone, plate, & hole (g) \_\_\_\_\_

Mass of sand to fill cone, plate, & hole (g) \_\_\_\_\_

Mass of sand to fill cone & plate (g) \_\_\_\_\_

Mass of sand to fill hole (g) \_\_\_\_\_

Mass of wet soil & container (g) \_\_\_\_\_

Mass of container (g) \_\_\_\_\_

Mass of wet soil (g) \_\_\_\_\_

Wet Density (PCF) =  $\frac{\text{Bulk density of sand (PCF)} \times \text{Mass of sand filling hole}}{\text{Mass of wet soil (g)}}$

SOIL DATA: PROCTOR # S5020221-1

Proctor Dry Density (PCF) 100.0

Proctor Optimum Moisture (%) 23.5

Required Moisture (%): 23.5 to 28.5

Required Compaction (%): 95.0%

TEST RESULTS:

Pass

Failed Moisture

Failed Compaction

BY: J.D. Kim TIME: 1300

QC OFFICER APPROVAL \_\_\_\_\_ DATE 3/21/02

QA OFFICER APPROVAL D. Young DATE 3-25-02

RJL 3-21-02

ENVIROCORE OF UTAF INC.

FIELD DENSITY TEST

(EC-1905, rev. 5)

ORIGINAL

PROJECT: LARW MW X 11a.(2) CLASS A OTHER

LIFT IDENTIFICATION: ECR12020314 DATE: 3/19/02

WASTE OR ~~TEST~~ ID NUMBER(S): 57A both

TEST LOCATION: N 1330 E 1288 TEST METHOD: D1556 X D2922

**D2922 DENSITY DETERMINATION**  
(NUCLEAR DENSITY GAUGE)  
GAUGE ID NO. 19481

On-Cell Standard:                      Off-Cell Standard:                       
Density                      Density                       
Counts                      Counts 2504  
Moisture                      Moisture                       
Counts                      Counts 1020  
Depth Setting                      Count Time                       
(inches) 8 (minutes) 1  
Moisture                      Density                       
Counts 187 Counts 1515  
Wet                      Dry                       
Density                      Density                       
(PCF) 121.7 (PCF) 104.0  
Moisture                      Moisture                       
Density                      Fraction                       
(PCF) 17.1 (%) 10.4

**D1556 DENSITY DETERMINATION**  
(SAND CONE)

Bulk Density of sand (PCF)                       
Mass of Sand to Fill Cone & Plate (g)                       
Mass of bottle & cone before filling cone, plate, & hole (g)                       
Mass of bottle & cone, after filling cone, plate, & hole (g)                       
Mass of sand to fill cone, plate, & hole (g)                       
Mass of sand to fill cone & plate (g)                       
Mass of sand to fill hole (g)                       
Mass of wet soil & container (g)                       
Mass of container (g)                       
Mass of wet soil (g)                     

Wet Bulk density Mass of wet  
Density = of sand (PCF) X soil (g)  
(PCF) Mass of sand filling hole

Net =                       
Density (PCF)                     

**MOISTURE DETERMINATION**

Container ID AC124

Mass of wet soil & container (g)	<u>327.0</u>
Mass of dry soil & container (g)	<u>307.3</u>
Mass of water (g)	<u>20.3</u>
Mass of dry soil & container (g)	<u>307.3</u>
Mass of container (g)	<u>227.0</u>
Mass of dry soil (g)	<u>79.7</u>
Moisture content (%)	<u>25.5</u>

Dry Density =  $\frac{\text{Wet Density (PCF)} \times 100.0}{\text{Moisture content (\%)} + 100.0}$

Dry Density =  $\frac{121.7 \times 100.0}{25.5 + 100.0} = 97.0$  pcf

Percent Compaction =  $\frac{\text{Dry Density} \times 100.0}{\text{Proctor Density}}$

Percent Compaction =  $\frac{97.0 \times 100.0}{100.0} = 97.0$  %

**SOIL DATA:** PROCTOR # 9502022-1

Proctor Dry Density (PCF) 100.0

Proctor Optimum Moisture (%) 23.5

Required Moisture (%): 23.5 to 28.5

Required Compaction (%): 95%

**TEST RESULTS:**

Pass  
 Failed Moisture  
 Failed Compaction

BY: MD TIME: 1400

QC OFFICER APPROVAL                      DATE 3/21/02

QA OFFICER APPROVAL                      DATE 3-25-02

RD 3-21-02





# ENVIROCARE OF UTAH INC.

FIELD DENSITY TEST  
(EC-1905, rev. 5)

ORIGINAL

PROJECT: LARW MW 11e.(2) CLASS A OTHER J

LIFT IDENTIFICATION: E 3/21/02 ACR12020314 DATE: 3-14-02

WASTE OR TEST ID NUMBER(S): 60 Lot 14

TEST LOCATION: N 1268 E 1310 TEST METHOD: D1556 X D2922

**D2922 DENSITY DETERMINATION  
(NUCLEAR DENSITY GAUGE)**  
GAUGE ID NO. 19481

On-Cell Standard:	Off-Cell Standard:
Density Counts _____	Density Counts <u>2501</u>
Moisture Counts _____	Moisture Counts <u>1050</u>
Depth Setting (inches) <u>8</u>	Count Time (minutes) <u>1</u>
Moisture Counts <u>198</u>	Density Counts <u>1498</u>
Wet Density (PCF) <u>122.1</u>	Dry Density (PCF) <u>104.8</u>
Moisture Density (PCF) <u>17.3</u>	Moisture Fraction (%) <u>14.5</u>

**D1556 DENSITY DETERMINATION  
(SAND CONE)**

Bulk Density of sand (PCF) \_\_\_\_\_

Mass of Sand to Fill Cone & Plate (g) \_\_\_\_\_

Mass of bottle & cone before filling cone, plate, & hole (g) \_\_\_\_\_

Mass of bottle & cone, after filling cone, plate, & hole (g) \_\_\_\_\_

Mass of sand to fill cone, plate, & hole (g) \_\_\_\_\_

Mass of sand to fill cone & plate (g) \_\_\_\_\_

Mass of sand to fill hole (g) \_\_\_\_\_

Mass of wet soil & container (g) \_\_\_\_\_

Mass of container (g) \_\_\_\_\_

Mass of wet soil (g) \_\_\_\_\_

Wet Bulk density of sand (PCF) \_\_\_\_\_

Density of sand (PCF) X soil (g) \_\_\_\_\_

(PCF) Mass of sand filling hole \_\_\_\_\_

Wet Density (PCF) \_\_\_\_\_

**MOISTURE DETERMINATION**

Container ID <u>EE</u>	
Mass of wet soil & container (g)	<u>370.0</u>
Mass of dry soil & container (g)	<u>324.7</u>
Mass of water (g)	<u>45.9</u>
Mass of dry soil & container (g)	<u>324.7</u>
Mass of container (g)	<u>129.5</u>
Mass of dry soil (g)	<u>195.2</u>
Moisture content (%)	<u>23.5</u>

Dry Density =  $\frac{\text{Wet Density (PCF)} \times 100.0}{\text{Moisture content (\%)} + 100.0}$

Density =  $\frac{122.1 \times 100.0}{23.5 + 100.0} = 98.9$  pcf

Percent Compaction =  $\frac{\text{Dry Density} \times 100.0}{\text{Proctor Density}}$

Compaction =  $\frac{98.9 \times 100.0}{100.0} = 98.9$  %

SOIL DATA: PROCTOR # S5020221-1

Proctor Dry Density (PCF) 100.0

Proctor Optimum Moisture (%) 23.5

Required Moisture (%): 23.5 to 28.5

Required Compaction (%): 95.0%

TEST RESULTS:

Pass

Failed Moisture

Failed Compaction

BY: S. De / ten TIME: 1300

[Signature] 3/21/02  
QC OFFICER APPROVAL DATE

[Signature] 4 3-25-02  
QA OFFICER APPROVAL DATE

RDJ 3-21-02

# ENVIROCARE OF UTAH, INC.

## FIELD DENSITY TEST

(EC-1905, rev. 5)

ORIGINAL

PROJECT: LARW MW 11e. (2) CLASS A OTHER \_\_\_\_\_

LIFT IDENTIFICATION: ALR12020314 DATE: 3-14-02

WASTE OR TEST ID NUMBER(S): 61 lot 15

TEST LOCATION: N 1240 E 1198 TEST METHOD: D1556 X D2922

**D2922 DENSITY DETERMINATION**  
(NUCLEAR DENSITY GAUGE)  
GAUGE ID NO. 19481

On-Cell Standard:	Off-Cell Standard:
Density	Density
Counts <u>      </u>	Counts <u>2501</u>
Moisture	Moisture
Counts <u>      </u>	Counts <u>1050</u>
Depth Setting	Count Time
(inches) <u>8</u>	(minutes) <u>1</u>
Moisture	Density
Counts <u>210</u>	Counts <u>1449</u>
Wet	Dry
Density	Density
(PCF) <u>122.8</u>	(PCF) <u>104.4</u>
Moisture	Moisture
Density	Fraction
(PCF) <u>18.8</u>	(%) <u>17.0</u>

**D1556 DENSITY DETERMINATION**  
(SAND CONE)

Bulk Density of sand (PCF) \_\_\_\_\_

Mass of Sand to Fill Cone & Plate (g) \_\_\_\_\_

Mass of bottle & cone before filling cone, plate, & hole (g) \_\_\_\_\_

Mass of bottle & cone, after filling cone, plate, & hole (g) \_\_\_\_\_

Mass of sand to fill cone, plate, & hole (g) \_\_\_\_\_

Mass of sand to fill cone & plate (g) \_\_\_\_\_

Mass of sand to fill hole (g) \_\_\_\_\_

Mass of wet soil & container (g) \_\_\_\_\_

Mass of container (g) \_\_\_\_\_

Mass of wet soil (g) \_\_\_\_\_

Wet Density (PCF)	Bulk density of sand (PCF)	Mass of wet soil (g)
_____	_____	_____
Mass of sand filling hole		
_____	_____	_____

**MOISTURE DETERMINATION**

Container ID	<u>X1</u>
Mass of wet soil & container (g)	<u>467.9</u>
Mass of dry soil & container (g)	<u>422.7</u>
Mass of water (g)	<u>45.2</u>
Mass of dry soil & container (g)	<u>422.7</u>
Mass of container (g)	<u>226.4</u>
Mass of dry soil (g)	<u>196.1</u>
Moisture content (%)	<u>23.0</u>

Dry Density =  $\frac{\text{Wet Density (PCF)} \times 100.0}{\text{Moisture content (\%)} + 100.0}$

Dry Density =  $\frac{122.8 \times 100.0}{23.0 + 100.0} = 99.8$  pcf

Percent Compaction =  $\frac{\text{Dry Density} \times 100.0}{\text{Proctor Density}}$

Percent Compaction =  $\frac{99.8 \times 100.0}{100.0} = 99.8\%$

**SOIL DATA:** PROCTOR # S5020221-1

Proctor Dry Density (PCF) 100.0 100.0 100.0

Proctor Optimum Moisture (%) 23.5

Required Moisture (%): 23.5 to 28.5

Required Compaction (%): 95.0%

**TEST RESULTS:**

Pass

Failed Moisture

Failed Compaction

BY: S. Dalton TIME: 1200

QC OFFICER APPROVAL \_\_\_\_\_ DATE 3/21/02

QA OFFICER APPROVAL D. Young 4 DATE 3-25-02

RJR 3-21-02

ENVIROCARE OF UTAH INC.

FIELD DENSITY TEST

(EC-1905, rev. 5)

ORIGINA

PROJECT: LARW MW 11a.(2) CLASS A OTHER \_\_\_\_\_

LIFT IDENTIFICATION: ECR12020314 DATE 3/19/02

WASTE OR TEST ID NUMBER(S): 101A Dot 15

TEST LOCATION: N1240 E1198 TEST METHOD: D1556 K D2922

**D2922 DENSITY DETERMINATION (NUCLEAR DENSITY GAUGE)**  
 GAUGE ID NO. 19481  
 On-Cell Standard: \_\_\_\_\_  
 Density \_\_\_\_\_  
 Counts \_\_\_\_\_  
 Moisture \_\_\_\_\_  
 Counts \_\_\_\_\_  
 Depth Setting (inches) 8  
 Moisture \_\_\_\_\_  
 Counts 212  
 Wet Density \_\_\_\_\_  
 (PCF) 120.4  
 Moisture Density \_\_\_\_\_  
 (PCF) 19.4

Off-Cell Standard: \_\_\_\_\_  
 Density \_\_\_\_\_  
 Counts 2504  
 Moisture \_\_\_\_\_  
 Counts 620  
 Count Time (minutes) 1  
 Density \_\_\_\_\_  
 Counts 1551  
 Dry Density \_\_\_\_\_  
 (PCF) 101.0  
 Moisture Fraction \_\_\_\_\_  
 (%) 19.4

**D1556 DENSITY DETERMINATION (SAND CONE)**  
 Bulk Density of sand (PCF) \_\_\_\_\_  
 Mass of Sand to Fill Cone & Plate (g) \_\_\_\_\_  
 Mass of bottle & cone before filling cone, plate, & hole (g) \_\_\_\_\_  
 Mass of bottle & cone, after filling cone, plate, & hole (g) \_\_\_\_\_  
 Mass of sand to fill cone, plate, & hole (g) \_\_\_\_\_  
 Mass of sand to fill cone & plate (g) \_\_\_\_\_  
 Mass of sand to fill hole (g) \_\_\_\_\_  
 Mass of wet soil & container (g) \_\_\_\_\_  
 Mass of container (g) \_\_\_\_\_  
 Mass of wet soil (g) \_\_\_\_\_  
 Wet Bulk density of sand (PCF) \_\_\_\_\_  
 Density (PCF) \_\_\_\_\_  
 Mass of wet soil (g) \_\_\_\_\_  
 Mass of sand filling hole \_\_\_\_\_

**MOISTURE DETERMINATION**  
 Container ID A13  
 Mass of wet soil & container (g) 332.0  
 Mass of dry soil & container (g) 312.5  
 Mass of water (g) 19.5  
 Mass of dry soil & container (g) 312.5  
 Mass of container (g) 232.0  
 Mass of dry soil (g) 80.5  
 Moisture content (%) 24.2

Dry Density =  $\frac{\text{Wet Density (PCF)} \times 100.0}{\text{Moisture content (\%)} + 100.0}$   
 Dry Density =  $\frac{120.4 \times 100.0}{24.2 + 100.0} = 97.1$  pcf

Percent Compaction =  $\frac{\text{Dry Density} \times 100.0}{\text{Proctor Density}}$   
 Percent Compaction =  $\frac{97.1 \times 100.0}{100.0} = 97.1\%$

**SOIL DATA:** PROCTOR # 5502022-1  
 Proctor Dry Density (PCF) 100.0  
 Proctor Optimum Moisture (%) 23.5  
 Required Moisture (%): 23.5 to 28.5  
 Required Compaction (%): 95.0%

**TEST RESULTS:**  
 Pass  
 Failed Moisture  
 Failed Compaction  
 BY: MM TIME: 1400

QC OFFICER APPROVAL \_\_\_\_\_ DATE 3/21/02

QA OFFICER APPROVAL O Young 4 DATE 3-28-02

RF 3-21-02

**ENVIROCARE OF UTAH INC.**  
**FIELD DENSITY TEST**  
 (EC-1905, rev. 5)

**ORIGINAL**

PROJECT: LARW MW 11e.(2) CLASS A OTHER \_\_\_\_\_

LIFT IDENTIFICATION: E 3/20/02 ACR12020514 DATE: 3-14-02

WASTE OR TEST ID NUMBER(S): 62 lot 16

TEST LOCATION: N 1247 E 1321 TEST METHOD: \_\_\_\_\_ D1556 X D2922

**D2922 DENSITY DETERMINATION**  
 (NUCLEAR DENSITY GAUGE)  
 GAUGE ID NO. 19481

On-Cell Standard: \_\_\_\_\_ Off-Cell Standard: \_\_\_\_\_  
 Density \_\_\_\_\_ Density \_\_\_\_\_  
 Counts \_\_\_\_\_ Counts 2501  
 Moisture \_\_\_\_\_ Moisture \_\_\_\_\_  
 Counts \_\_\_\_\_ Counts 650  
 Depth Setting \_\_\_\_\_ Count Time \_\_\_\_\_  
 (inches) 0 (minutes) 1  
 Moisture \_\_\_\_\_ Density \_\_\_\_\_  
 Counts 218 Counts 1403  
 Wet \_\_\_\_\_ Dry \_\_\_\_\_  
 Density \_\_\_\_\_ Density \_\_\_\_\_  
 (PCF) 122.9 (PCF) 103.8  
 Moisture \_\_\_\_\_ Moisture \_\_\_\_\_  
 Density \_\_\_\_\_ Fraction \_\_\_\_\_  
 (PCF) 19.2 (%) 18.5

**D1556 DENSITY DETERMINATION**  
 (SAND CONE)

Bulk Density of sand (PCF) \_\_\_\_\_  
 Mass of Sand to Fill Cone & Plate (g) \_\_\_\_\_  
 Mass of bottle & cone before filling cone, plate, & hole (g) \_\_\_\_\_  
 Mass of bottle & cone, after filling cone, plate, & hole (g) \_\_\_\_\_  
 Mass of sand to fill cone, plate, & hole (g) \_\_\_\_\_  
 Mass of sand to fill cone & plate (g) \_\_\_\_\_  
 Mass of sand to fill hole (g) \_\_\_\_\_  
 Mass of wet soil & container (g) \_\_\_\_\_  
 Mass of container (g) \_\_\_\_\_  
 Mass of wet soil (g) \_\_\_\_\_


Wet Bulk density Mass of wet Density = of sand (PCF) X soil (g) (PCF) Mass of sand filling hole  
 Wet = \_\_\_\_\_  
 Density (PCF) \_\_\_\_\_

**MOISTURE DETERMINATION**

Container ID B15

Mass of wet soil & container (g)	<u>445.8</u>
Mass of dry soil & container (g)	<u>402.7</u>
Mass of water (g)	<u>43.1</u>
Mass of dry soil & container (g)	<u>402.7</u>
Mass of container (g)	<u>231.3</u>
Mass of dry soil (g)	<u>171.4</u>
Moisture content (%)	<u>25.1</u>

**SOIL DATA:** PROCTOR # S5020221-1

Proctor Dry Density (PCF) 100.0  
 Proctor Optimum Moisture (%) 23.5  
 Required Moisture (%): 23.5 to 28.5  
 Required Compaction (%): 96.0%

Dry Density =  $\frac{\text{Wet Density (PCF)}}{\text{Moisture content (\%)} + 100.0} \times 100.0$

Dry Density =  $\frac{122.9}{25.1 + 100.0} \times 100.0 = 98.2$  pcf

Percent Compaction =  $\frac{\text{Dry Density} \times 100.0}{\text{Proctor Density}}$

Percent Compaction =  $\frac{98.2 \times 100.0}{100.0} = 98.2\%$

**TEST RESULTS:**  
 Pass  
 Failed Moisture  
 Failed Compaction  
 BY: S. De Hon TIME: 1300

QC OFFICER APPROVAL \_\_\_\_\_ DATE 3/21/02

QA OFFICER APPROVAL D Young 4 DATE 3-25-02

RRJ 3-21-02

# E TROCARE OF UTAH, INC.

## FIELD DENSITY TEST

(EC-1905, rev. 5)

# ORIGINAL

PROJECT: LARW MW K 11a. (2) CLASS A OTHER \_\_\_\_\_

LIFT IDENTIFICATION: ELR1202214 DATE: 2/11/02

WASTE OR TEST ID NUMBER(S): 03 2017

TEST LOCATION: N1123 E 1254 TEST METHOD: D1556 A D2922

**D2922 DENSITY DETERMINATION**  
(NUCLEAR DENSITY GAUGE)  
GAUGE ID NO. 19481

On-Call Standard: \_\_\_\_\_ Off-Call Standard: \_\_\_\_\_

Density Counts \_\_\_\_\_ Density Counts 2501

Moisture Counts \_\_\_\_\_ Moisture Counts 490

Depth Setting \_\_\_\_\_ Count Time \_\_\_\_\_  
(inches) 8 (minutes) 1

Moisture Density \_\_\_\_\_ Density \_\_\_\_\_  
Counts 224 Counts 1545

Wet Dry \_\_\_\_\_ Density \_\_\_\_\_  
Density (PCF) 120.7 (PCF) 101.0

Moisture Density \_\_\_\_\_ Moisture \_\_\_\_\_  
Density (PCF) 19.7 (%) 19.4

**D1556 DENSITY DETERMINATION**  
(SAND CONE)

Bulk Density of sand (PCF) \_\_\_\_\_

Mass of Sand to Fill Cone & Plate (g) \_\_\_\_\_

Mass of bottle & cone before filling cone, plate, & hole (g) \_\_\_\_\_

Mass of bottle & cone, after filling cone, plate, & hole (g) \_\_\_\_\_

Mass of sand to fill cone, plate, & hole (g) \_\_\_\_\_

Mass of sand to fill cone & plate (g) \_\_\_\_\_

Mass of sand to fill hole (g) \_\_\_\_\_

Mass of wet soil & container (g) \_\_\_\_\_

Mass of container (g) \_\_\_\_\_

Mass of wet soil (g) \_\_\_\_\_

Wet Bulk density Mass of wet  
Density = of sand (PCF) x soil (g)  
(PCF) Mass of sand filling hole

Wet = \_\_\_\_\_  
Density (PCF)

**MOISTURE DETERMINATION**

Container ID D7

Mass of wet soil & container (g)	<u>447.3</u>
Mass of dry soil & container (g)	<u>407.7</u>
Mass of water (g)	<u>35.6</u>
Mass of dry soil & container (g)	<u>417.4</u>
Mass of container (g)	<u>227.8</u>
Mass of dry soil (g)	<u>199.4</u>
Moisture content (%)	<u>19.8</u>

Dry Density =  $\frac{\text{Wet Density (PCF)} \times 100.0}{\text{Moisture content (\%)} + 100.0}$

Dry Density =  $\frac{120.7 \times 100.0}{19.8 + 100.0} = 100.2 \text{ pcf}$

Percent Compaction =  $\frac{\text{Dry Density} \times 100.0}{\text{Proctor Density}}$

Percent Compaction =  $\frac{100.2 \times 100.0}{100.0} = 100.2 \%$

SOIL DATA: PROCTOR # 55020221-2

Proctor Dry Density (PCF) 100.0

Proctor Optimum Moisture (%) 23.0

Required Moisture (%): 23.0 to 28.0

Required Compaction (%): 95.0%

TEST RESULTS:

Pass

Failed Moisture

Failed Compaction

BY: Paul TIME: 1300

QC OFFICER APPROVAL: \_\_\_\_\_ DATE: 3/21/02

QA OFFICER APPROVAL: O. Young DATE: 3-25-02

ENVIROCARE OF UTAH, INC.

FIELD DENSITY TEST

(EC-1905, rev. 5)

ORIGINAL

PROJECT: LARW MW K 11a.(2) CLASS A OTHER \_\_\_\_\_

LIFT IDENTIFICATION: ECR12020314 DATE 3/19/02

WASTE OR TEST ID NUMBER(S): 03A Lot 17

TEST LOCATION: M1123 B 1254 TEST METHOD: D1556 K D2922

**D2922 DENSITY DETERMINATION**  
(NUCLEAR DENSITY GAUGE)  
GAUGE ID NO. 19481

On-Call Standard: \_\_\_\_\_  
Density \_\_\_\_\_  
Counts \_\_\_\_\_  
Moisture \_\_\_\_\_  
Counts \_\_\_\_\_  
Depth Setting \_\_\_\_\_  
(inches) 8  
Moisture \_\_\_\_\_  
Counts 209  
Wet \_\_\_\_\_  
Density \_\_\_\_\_  
(PCF) 118.5  
Moisture \_\_\_\_\_  
Density \_\_\_\_\_  
(PCF) 19.3

Off-Cell Standard: \_\_\_\_\_  
Density \_\_\_\_\_  
Counts 2504  
Moisture \_\_\_\_\_  
Counts 1020  
Count Time \_\_\_\_\_  
(minutes) 1  
Density \_\_\_\_\_  
Counts 1433  
Dry \_\_\_\_\_  
Density \_\_\_\_\_  
(PCF) 99.2  
Moisture \_\_\_\_\_  
Fraction \_\_\_\_\_  
(%) 19.4

**D1556 DENSITY DETERMINATION**  
(SAND CONE)

Bulk Density of sand (PCF) \_\_\_\_\_  
Mass of Sand to Fill Cone & Plate (g) \_\_\_\_\_

Mass of bottle & cone before filling cone, plate, & hole (g) \_\_\_\_\_  
Mass of bottle & cone, after filling cone, plate, & hole (g) \_\_\_\_\_  
Mass of sand to fill cone, plate, & hole (g) \_\_\_\_\_  
Mass of sand to fill cone & plate (g) \_\_\_\_\_  
Mass of sand to fill hole (g) \_\_\_\_\_  
Mass of wet soil & container (g) \_\_\_\_\_

Mass of container (g) \_\_\_\_\_  
Mass of wet soil (g) \_\_\_\_\_

Wet Bulk density of sand (PCF) \_\_\_\_\_  
Density of sand (PCF) \_\_\_\_\_  
Mass of wet soil (g) \_\_\_\_\_  
Mass of sand filling hole (g) \_\_\_\_\_  
Wet Density (PCF) \_\_\_\_\_


**MOISTURE DETERMINATION**

Container ID X1

Mass of wet soil & container (g)	<u>324.8</u>
Mass of dry soil & container (g)	<u>308.7</u>
Mass of water (g)	<u>19.1</u>
Mass of dry soil & container (g)	<u>307.7</u>
Mass of container (g)	<u>226.8</u>
Mass of dry soil (g)	<u>80.9</u>
Moisture content (%)	<u>23.4</u>

Dry Density =  $\frac{\text{Wet Density (PCF)}}{\text{Moisture content (\%)} + 100.0} \times 100.0$

Dry Density =  $\frac{118.5}{23.4 + 100.0} \times 100.0 = 95.9$  pcf

Percent Compaction =  $\frac{\text{Dry Density} \times 100.0}{\text{Proctor Density}}$

Percent Compaction =  $\frac{95.9}{100.0} \times 100.0 = 95.9$  %

**SOIL DATA:** PROCTOR # 55020221-2

Proctor Dry Density (PCF) 100.0

Proctor Optimum Moisture (%) 23.8

Required Moisture (%): 23.0 to 28.0

Required Compaction (%): 96.0%

**TEST RESULTS:**

X Pass  
\_\_\_\_ Failed Moisture  
\_\_\_\_ Failed Compaction

BY: MD TIME: 1400

E. Roberts 3/21/02  
QC OFFICER APPROVAL DATE

D. Youngs 4 3-25-02  
QA OFFICER APPROVAL DATE

RJD 3-21-02

# TROCARE OF UTAH, INC.

## FIELD DENSITY TEST

(EC-1905, rev. 5)

ORIGINAL

PROJECT: LARW MW K 11a. (2) CLASS A OTHER   

LIFT IDENTIFICATION: ECR12020314 DATE: 3/14/02

WASTE OR TEST ID NUMBER(S): 64 Lot 18

TEST LOCATION: N 1130 E 1370 TEST METHOD: 1 D1556 2 D2922

**D2922 DENSITY DETERMINATION**  
(NUCLEAR DENSITY GAUGE)  
GAUGE ID NO. 19481

On-Call Standard:    Off-Call Standard:   

Density Density  
Counts    Counts 2501

Moisture Moisture  
Counts    Counts 650

Depth Setting Count Time  
(inches) 2 (minutes) 1

Moisture Density  
Counts 207 Counts 1458

Wet Dry  
Density Density  
(PCF) 123.1 (PCF) 105.0

Moisture Moisture  
Density Fraction  
(PCF) 18.1 (%) 17.3

**D1556 DENSITY DETERMINATION**  
(SAND CONE)

Bulk Density of sand (PCF) 92.1

Mass of Sand to Fill Cone & Plate (g) 1710.7

Mass of bottle & cone before filling cone, plate, & hole (g) 6118.7

Mass of bottle & cone, after filling cone, plate, & hole (g) 3150.8

Mass of sand to fill cone, plate, & hole (g) 2967.9

Mass of sand to fill cone & plate (g) 1710.7

Mass of sand to fill hole (g) 1257.2

Mass of wet soil & container (g) 1245.5

Mass of container (g) 12.3

Mass of wet soil (g) 1233.2

Wet Bulk density Mass of wet  
Density of sand (PCF) x soil (g)  
(PCF) Mass of sand filling hole

Wet = 127.4  
Density (PCF)

**MOISTURE DETERMINATION**

Container ID 05

Mass of wet soil & container (g)	4551.3
Mass of dry soil & container (g)	405.3
Mass of water (g)	50.0
Mass of dry soil & container (g)	405.3
Mass of container (g)	227.8
Mass of dry soil (g)	177.5
Moisture content (%)	29.2

Dry Density =  $\frac{\text{Wet Density (PCF)} \times 100.0}{\text{Moisture content (\%)} + 100.0}$

Dry Density =  $\frac{127.4 \times 100.0}{29.2 + 100.0} = 99.4$  pcf

Percent Compaction =  $\frac{\text{Dry Density} \times 100.0}{\text{Proctor Density}}$

Percent Compaction =  $\frac{99.4 \times 100.0}{100.0} = 99.4$  %

**SOIL DATA:** PROCTOR #55020221-2

Proctor Dry Density (PCF) 100.0

Proctor Optimum Moisture (%) 23.0

Required Moisture (%): 23.0 to 28.0

Required Compaction (%): 95.0%

**TEST RESULTS:**

Pass

Failed Moisture

Failed Compaction

BY: J. Dalton TIME: 1300

   3/21/02  
QC OFFICER APPROVAL DATE

   4 3-25-02  
QA OFFICER APPROVAL DATE

ENVIROCARE OF UTAF INC.

FIELD DENSITY TEST

(EC-1905, rev. 5)

ORIGINAL

PROJECT: LARW MW K 11a.(2) CLASS A OTHER \_\_\_\_\_

LIFT IDENTIFICATION: ECR12020314 DATE 3/19/02

WASTE OR TEST ID NUMBER(S): 64A Lot 18

TEST LOCATION: N130 B1370 TEST METHOD: D1556 1 D2922

D2922 DENSITY DETERMINATION  
(NUCLEAR DENSITY GAUGE)  
GAUGE ID NO. 19481

On-Cell Standard:	Off-Cell Standard:
Density	Density
Counts _____	Counts <u>2504</u>
Moisture	Moisture
Counts _____	Counts <u>4020</u>
Depth Setting	Count Time
(inches) <u>8</u>	(minutes) <u>1</u>
Moisture	Density
Counts <u>210</u>	Counts <u>1535</u>
Wet	Dry
Density	Density
(PCF) <u>121.0</u>	(PCF) <u>101.7</u>
Moisture	Moisture
Density	Fraction
(PCF) <u>19.4</u>	(%) <u>19.1</u>

D1556 DENSITY DETERMINATION  
(SAND CONE)

Bulk Density of sand (PCF)	_____
Mass of Sand to Fill Cone & Plate (g)	_____
Mass of bottle & cone before filling cone, plate, & hole (g)	_____
Mass of bottle & cone, after filling cone, plate, & hole (g)	_____
Mass of sand to fill cone, plate, & hole (g)	_____
Mass of sand to fill cone & plate (g)	_____
Mass of sand to fill hole (g)	_____
Mass of wet soil & container (g)	_____
Mass of container (g)	_____
Mass of wet soil (g)	_____
Wet Bulk density of sand (PCF)	_____
Mass of wet soil (g)	_____
Mass of sand filling hole (g)	_____
Wet Density (PCF)	_____

MOISTURE DETERMINATION

Container ID	<u>ABC</u>
Mass of wet soil & container (g)	<u>227.4</u>
Mass of dry soil & container (g)	<u>209.1</u>
Mass of water (g)	<u>20.5</u>
Mass of dry soil & container (g)	<u>209.1</u>
Mass of container (g)	<u>129.4</u>
Mass of dry soil (g)	<u>79.5</u>
Moisture content (%)	<u>25.8</u>

Dry Density =  $\frac{\text{Wet Density (PCF)}}{\text{Moisture content (\%)} + 100.0} \times 100.0$

Dry Density =  $\frac{121.0}{25.8 + 100.0} \times 100.0 = 94.2$  pcf

Percent Compaction =  $\frac{\text{Dry Density} \times 100.0}{\text{Proctor Density}}$

Percent Compaction =  $\frac{94.2}{100.0} \times 100.0 = 94.2$  %

SOIL DATA: PROCTOR # 550202242

Proctor Dry Density (PCF) 100.0  
 Proctor Optimum Moisture (%) 23.1  
 Required Moisture (%): 23.0 to 28.0  
 Required Compaction (%): 95.0%

TEST RESULTS:

K Pass  
 \_\_\_\_\_ Failed Moisture  
 \_\_\_\_\_ Failed Compaction  
 BY: MD TIME: 1400

QC OFFICER APPROVAL \_\_\_\_\_ DATE 3/21/02

QA OFFICER APPROVAL O. Young 4 DATE 3-25-02

RF 3-21-02

# ENVIROCARE OF UTAH, INC.

## FIELD PERMEABILITY TEST (EC-1906 rev 2)

**ORIGINAL**

REVISION: 08/16/00

PROJECT: LARW MW 11e(2) CLASS A OTHER \_\_\_\_\_  
 Test Location: N 1500 E 1347 Elevation/Lift 5227020714 Lot No. 8

**TESTING DATA:**

TESTED BY: Brennan Dick  
 Soil Saturation Start: Date: 3-20-02 Time: 1045 Max. Dry Density 100 pcf  
 Soil Saturation Finish: Date: 3-20-02 Time: 1445 Opt. Moisture 23.5 %  
 Depth of Wet Front (L) 3.4 cm  
 Radius of Measuring Tube (Rt) 0.14 cm Density test # 54  
 Radius of Permeameter Ring (Rr) 13.02 cm Dry Density 96.4 pcf  
 Height of Water, (Ht) 157.1 cm Moisture content 25.5 %  
 Soil/Water temp, in ring, after test N/R °C N/R 11e(2) Compaction 91.4 %

$dH = \text{Change in Head (cm)} = \underline{11.0}$  cm  
 $dT = \text{Time (minutes)} = \underline{8}$  min  
 $R = \underline{1.000}$  (From Figure 1) \* (R = 1.000 for 11e(2))


$$K_s = \frac{(2) (dH/dT) (L)}{(60) ((Ht) + (0.5)(L))} \left[ \frac{(Rt)^2}{(Rr)^2} \right] \times (R)$$

$$K_s = \frac{(2) (11.0 / 8) (3.4)}{(60) ((157.1) + (0.5)(3.4))} \left[ \frac{(0.14)^2}{(13.02)^2} \right] \times 1.000$$

$K_s = \underline{1.5 \times 10^{-7}}$  cm/sec

**Timed Water Drop Reading**

min.	min.	min.
0:00	29.0	4:20 23.1
0:20	28.0	4:40 22.4
0:40	28.1	5:00 22.0
1:00	27.4	5:20 21.5
1:20	27.3	5:40 21.2
1:40	26.9	6:00 20.7
2:00	26.4	6:20 20.2
2:20	26.0	6:40 20.0
2:40	25.4	7:00 19.4
3:00	25.3	7:20 18.9
3:20	24.8	7:40 18.3
3:40	24.1	8:00 18.0
4:00	23.7	



Soil/Water Temp (°C)	Corr. Factor (R)
0	1.783
1	1.723
2	1.664
3	1.611
4	1.560
5	1.511
6	1.465
7	1.421
8	1.379
9	1.339
10	1.301
11	1.265
12	1.230
13	1.197
14	1.165
15	1.135
16	1.106
17	1.077
18	1.051
19	1.025
20	1.000
21	0.976
22	0.953
23	0.931
24	0.910
25	0.889
26	0.869
27	0.850
28	0.832
29	0.814
30	0.797
31	0.780
32	0.764
33	0.749
34	0.733
35	0.719
36	0.705
37	0.692
38	0.678
39	0.665
40	0.653

Required Permeability  $2.1 \times 10^{-7}$  Test Results Pass Fail By Brennan Dick Date 3/20/02

QC APPROVAL [Signature] DATE 3/21/02 QA APPROVAL [Signature] DATE 3-25-02  
 RDL 3-21-02

**EC-1905 Calculation Check**

Lift ID: LRBC9010501 Spring Start-Up 530S; 925E  
 Date: 10/7/04 Spring Start Up

Lift / Lot Number	Proctor Dry Dens	Proctor Opti.Moist	Mass of Soil+Cont	Dry Mass soil+cont	Water Mass	Cont Mass	Mass of dry soil	Moist Cont	Wet Dens	Dry Dens	% Comp	Moist. Diff. Act. - Opti.	Proctor ID Number	Liner/RB OK?	Liner/RB OK?
1st/1	97.0	25.5	325.7	294.6	31.1	166.1	128.5	24.2	133.7	107.6	111.0	-1.3	A010214-4	TRUE	Yes

**Permeability Testing Lot 1**

Depth of Wet Front	0.2	cm
Radius of Tube	0.32	cm
Radius of Ring	22	cm
Height of Water	173.3	cm
Soil/Water Temp	22	°C
R (from Table)	0.953	
Change in Head	N/A	cm
Time	8	min
Linear Regression	1.6355	
<b>K<sub>s</sub></b>	<b>1.3E-08</b>	<b>cm/sec</b>

**EC-1905 Calculation Check**

Lift ID: LRF10041011 In active Lift Start Up 530S; 925E  
 Date: 10/11/04

Lift / Lot Number	Proctor Dry Dens	Proctor Opti.Moist	Mass of Soil+Cont	Dry Mass soil+cont	Water Mass	Cont Mass	Mass of dry soil	Moist Cont	Wet Dens	Dry Dens	% Comp	Moist. Diff. Act. - Opti.	Proctor ID Number	Liner/RB OK?	Liner/RB OK?
1st/1	98.0	24.5	336.2	301.4	34.8	171.2	130.2	26.7	125.9	99.4	101.4	2.2	A010425-1	TRUE	Yes
1st/2	98.0	24.5	339.1	304.3	34.8	166.6	137.7	25.3	125.8	100.4	102.4	0.8	A010425-1	TRUE	Yes

**Permeability Testing Lot 2**

Depth of Wet Front	3.1	cm
Radius of Tube	0.32	cm
Radius of Ring	22	cm
Height of Water	175.5	cm
Soil/Water Temp	22	°C
R (from Table)	0.953	
Change in Head	N/A	cm
Time	8	min
Linear Regression	3.7272	
<b><math>K_s</math></b>	<b>4.4E-07</b>	<b>cm/sec</b>

**EC-1905 Calculation Check**

Lift ID: LRI9041005 I9 Radon Barrier 870S; 865E  
 Date: 10/5/04 Inactive Lift Start Up for I9, L9

Lift / Lot Number	Proctor Dry Dens	Proctor Opti.Moist	Mass of Soil+Cont	Dry Mass soil+cont	Water Mass	Cont Mass	Mass of dry soil	Moist Cont	Wet Dens	Dry Dens	% Comp	Moist. Diff. Act. - Opti.	Proctor ID Number	Liner/RB OK?	Liner/RB OK?
1st/1	97.9	24.2	412.6	372.7	39.9	217.4	155.3	25.7	121.3	96.5	98.6	1.5	S5011015-1	TRUE	Yes
1st/2	97.9	24.2	390.0	358.8	31.2	218.0	140.8	22.2	126.1	103.2	105.4	-2.0	S5011015-1	TRUE	Yes
1st/2A	97.9	24.2	322.8	292.6	30.2	170.7	121.9	24.8	128.7	103.1	105.3	0.6	S5011015-1	TRUE	Yes

**EC-1905 Calculation Check**

Lift ID: LRJ7011026 (Inactive Lift Start-up) J7 Radon Barrier 868S; 615E

Date: 4/4/02 12th Lift

Lift / Lot Number	Proctor Dry Dens	Proctor Opti.Moist	Mass of Soil+Cont	Dry Mass soil+cont	Water Mass	Cont Mass	Mass of dry soil	Moist Cont	Wet Dens	Dry Dens	% Comp	Moist. Diff. Act. - Opti.	Proctor ID Number	Liner/RB OK?
12th/1	102.2	21.5	330.5	311.8	18.7	230.5	81.3	23.0	122.0	99.2	97.1	1.5	S5011011-3	Yes
12th/1 (West)	102.2	21.5	317.1	300.3	16.8	217.1	83.2	20.2	129.1	107.4	105.1	-1.3	S5011011-3	Yes
12th/1 (East)	102.2	21.5	330.6	314.0	16.6	230.6	83.4	19.9	120.3	100.3	98.2	-1.6	S5011011-3	Yes

**Permeability Testing Lot 1**

Depth of Wet Front	1.7	cm
Radius of Tube	0.32	cm
Radius of Ring	22	cm
Height of Water	162.0	cm
Soil/Water Temp	22	°C
R (from Table)	0.953	
Change in Head	19.8	cm
Time	8	min
<b>K<sub>s</sub></b>	<b>1.7E-07</b>	<b>cm/sec</b>

**Permeability Testing Lot 1**

Depth of Wet Front	1.3	cm
Radius of Tube	0.32	cm
Radius of Ring	22	cm
Height of Water	165.3	cm
Soil/Water Temp	22	°C
R (from Table)	0.953	
Change in Head	5.1	cm
Time	8	min
<b>K<sub>s</sub></b>	<b>3.4E-08</b>	<b>cm/sec</b>

**Permeability Testing Lot 1**

Depth of Wet Front	1.7	cm
Radius of Tube	0.32	cm
Radius of Ring	22	cm
Height of Water	157.7	cm
Soil/Water Temp	20	°C
R (from Table)	1	
Change in Head	2	cm
Time	8	min
<b>K<sub>s</sub></b>	<b>1.9E-08</b>	<b>cm/sec</b>

**Permeability Test Check**

**Lift ID: LRJ7011026 (Inactive Lift Start-up) J7 Radon Barrier 868S; 615E**

**Test 1**

Depth of Wet Front	<u>4.4</u>	cm
Radius of Tube	<u>0.16</u>	cm
Radius of Ring	<u>21.9</u>	cm
Height of Water	<u>131.9</u>	cm
Soil/Water Temp	<u>23</u>	°C
R (from Table)	<u>0.931</u>	
Change in Head	<u>11.3</u>	cm
Time	<u>8</u>	min
<b><math>K_s</math></b>	<b>7.7E-08</b>	<b>cm/sec</b>

**EC-1905 Calculation Check**

Lift ID: LRP1010725 Spring Start-Up P1 Radon Barrier 1620S; 30W

Date: 6/17/04 SS 10<sup>-6</sup>

Lift / Lot Number	Proctor Dry Dens	Proctor Opti.Moist	Mass of Soil+Cont	Dry Mass soil+cont	Water Mass	Cont Mass	Mass of dry soil	Moist Cont	Wet Dens	Dry Dens	% Comp	Moist. Diff. Act. - Opti.	Proctor ID Number	Liner/RB OK?	Liner/RB OK?
1st/1	100.0	22.5	323.3	310.4	12.9	217.5	92.9	13.9	134.2	117.8	117.8	-8.6	A010717-2	TRUE	Yes

**Permeability Testing Lot 1**

Depth of Wet Front	2.0	cm
Radius of Tube	0.32	cm
Radius of Ring	22	cm
Height of Water	164.5	cm
Soil/Water Temp	20	°C
R (from Table)	1	
Change in Head	N/A	cm
Time	8	min
Liner Regression	1.3902	
<b>K<sub>s</sub></b>	<b>1.2E-07</b>	<b>cm/sec</b>

**EC-1905 Calculation Check**

Lift ID: LRP1011012 Radon Barrier P1 (In-Active Lift Start-Up) 1483S; 35W  
 Date: 4/29/02 14th Lift (Processed Clay)

Lift / Lot Number	Proctor Dry Dens	Proctor Opti.Moist	Mass of Soil+Cont	Dry Mass soil+cont	Water Mass	Cont Mass	Mass of dry soil	Moist Cont	Wet Dens	Dry Dens	% Comp	Moist. Diff. Act. - Opti.	Proctor ID Number	Liner/RB OK?
14th/1	96.0	25.5	230.6	214.9	15.7	130.6	84.3	18.6	134.3	113.2	118.0	-6.9	S5011008	Yes
14th/2	96.0	25.5	317.3	301.8	15.5	217.3	84.5	18.3	127.8	108.0	112.5	-7.2	S5011008	Yes

**Permeability Testing Lot 1**

Depth of Wet Front	0.5	cm
Radius of Tube	0.32	cm
Radius of Ring	22	cm
Height of Water	161.5	cm
Soil/Water Temp	25	°C
R (from Table)	0.889	
Change in Head	1.3	cm
Time	8	min
<b>K<sub>s</sub></b>	<b>3.1E-09</b>	<b>cm/sec</b>

**Sand Cone Lot # 2**

Density of sand	95.3	pcf
Mass of sand to fill cone & plate	1787.1	g
Mass of sand & bottle before filling hole	6538.2	g
Mass of sand & bottle after filling hole & cone	3109.9	g
Mass of sand to fill hole & cone	3428.3	g
Mass of sand to fill hole	1641.2	g
Mass of soil & container	2212.3	g
Mass of container	12.1	g
Mass of wet soil	2200.2	g
<b>Wet density of soil</b>	<b>127.8</b>	<b>pcf</b>
Wet density per nuclear density gauge	132.2	pcf
Wet density correlation $\geq .95$ and $\leq 1.05$	1.03	

**Permeability Test Check**

**Lift ID: LRP1011012 Radon Barrier P1 (In-Active Lift Start-Up) 1483S; 35W**

**Test 1**

Depth of Wet Front	<u>4.4</u>	cm
Radius of Tube	<u>0.16</u>	cm
Radius of Ring	<u>21.9</u>	cm
Height of Water	<u>131.9</u>	cm
Soil/Water Temp	<u>23</u>	°C
R (from Table)	<u>0.931</u>	
Change in Head	<u>11.3</u>	cm
Time	<u>8</u>	min
<b><math>K_s</math></b>	<b>7.7E-08</b>	<b>cm/sec</b>

**EC-1905 Calculation Check**

Lift ID: LRQ1040622 Q1 In-Active Start-up 1620S; 30W

Date: 6/22/04 7th Lift 10<sup>6</sup>

Lift / Lot Number	Proctor Dry Dens	Proctor Opti.Moist	Mass of Soil+Cont	Dry Mass soil+cont	Water Mass	Cont Mass	Mass of dry soil	Moist Cont	Wet Dens	Dry Dens	% Comp	Moist. Diff. Act. - Opti.	Proctor ID Number	Liner/RB OK?	Liner/RB OK?
7th/1	100.0	22.5	506.6	438.1	68.5	116.8	321.3	21.3	128.5	105.9	105.9	-1.2	A010717-2	TRUE	Yes
7th/1A	100.0	22.5	269.9	250.4	19.5	166.2	84.2	23.2	122.1	99.1	99.1	0.7	A010717-2	TRUE	Yes
7th/2	100.0	22.5	276.1	258.4	17.7	172.6	85.8	20.6	125.8	104.3	104.3	-1.9	A010717-2	TRUE	Yes
7th/2A	100.0	22.5	294.0	270.3	23.7	166.5	103.8	22.8	126.5	103.0	103.0	0.3	A010717-2	TRUE	Yes