

Reclamation Plan

White Mesa Mill

Blanding, Utah

Radioactive Materials License No. UT1900479

Revision 5.0

September 2011

**Prepared by:
Denison Mines (USA) Corp.
1050 17th Street, Suite 950
Denver, CO 80265
(303) 628-7798**

TABLE OF CONTENTS

	Page
INTRODUCTION.....	I-1
Summary of Plan	I-1
Plan Organization	I-2
1 SITE CHARACTERISTICS.....	1-1
1.1 Climate and Meteorology.....	1-5
1.1.1 Regional	1-5
1.1.2 Storms (FES Section 2.1.4, updated).....	1-9
1.1.3 On Site	1-9
1.2 Topography	1-12
1.3 Archeological Resources.....	1-12
1.3.1 Archeological Sites	1-12
1.3.2 Current Status of Excavation	1-15
1.4 Surface Water.....	1-17
1.4.1 Surface Water Description (FES Section 2.6.1.1)	1-17
1.4.2 Surface Water Quality as of the Date of the FES (FES Section 2.6.1.2).....	1-21
1.4.3 Surface Water Background Quality	1-25
1.5 Groundwater.....	1-30
1.5.1 Groundwater Characteristics.....	1-30
1.5.2 Seep and Spring Occurrence and Hydrogeology	1-41
1.5.3 Groundwater Quality	1-46
1.5.4 Background Groundwater Quality in the Perched Aquifer.....	1-51
1.5.5 Quality of Ground Water at the Compliance Monitoring Point	1-57
1.5.6 Springs and Seeps	1-57
1.5.7 Groundwater Appropriations Within a Five Mile Radius.....	1-61

1.6	Geology	1-90
1.6.1	Regional Geology	1-91
1.6.2	Blanding Site Geology	1-104
1.6.3	Seismic Risk Assessment.....	1-122
1.7	Biota (1978 ER Section 2.9)	1-123
1.7.1	Terrestrial (1978 ER Section 2.9.1)	1-123
1.7.2	Aquatic Biota (1978 ER Section 2.9.2)	1-132
1.7.3	Background Radiation (2007 ER, Section 3.13.1).....	1-133
1.7.4	Mill Site Background (1978 ER Section 2.10).....	1-136
1.7.5	Current Monitoring Data.....	1-137
2	EXISTING FACILITY	2-1
2.1	Facility Construction History	2-1
2.1.1	Mill and Tailings Management Facility.....	2-1
2.2	Facility Operations	2-2
2.2.1	Operating Periods.....	2-2
2.2.2	Mill Circuit.....	2-3
2.2.3	Tailings Management Facilities	2-5
2.3	Monitoring Programs	2-8
2.3.1	Monitoring and Reporting Under the Mill’s GWDP	2-8
2.3.2	Monitoring and Inspections Required Under the License	2-12
3	TAILINGS RECLAMATION PLAN	3-1
3.1	Location and Property Description	3-1
3.2	Facilities to be Reclaimed	3-3
3.2.1	Summary of Facilities to be Reclaimed	3-3
3.2.2	Tailings and Evaporative Cells	3-4
3.3	Design Criteria	3-9
3.3.1	Regulatory Criteria.....	3-9

3.3.2	Radon Flux Attenuation	3-11
3.3.3	Infiltration Analysis	3-12
3.3.4	Freeze/Thaw Evaluation	3-13
3.3.5	Soil Cover Erosion Protection	3-14
3.3.6	Slope Stability Analysis	3-15
3.3.7	Tailings Dewatering.....	3-15
3.3.8	Liquefaction	3-17
3.3.9	Settlement	3-18
3.3.10	Soil Cover-Animal Intrusion.....	3-19
3.3.11	Soil Cover Vegetation.....	3-20
3.3.12	Cover Material/Cover Material Volumes	3-20
4	MILL DECOMMISSIONING PLAN.....	4-1
	REFERENCES.....	R-1

LIST OF TABLES

Table	Description	Page
Table I-1	Revisions to Attachments and Appendices in Reclamation Plan	I-1
Table 1.1-1	Period of Record General Climate Summary – Precipitation.....	1-7
Table 1.1-2	Period of Record General Climate Summary - Temperature.....	1-8
Table 1.3-1	Distribution of Recorded Sites According to Temporal Position	1-14
Table 1.4-1	Drainage Areas of Project Vicinity and Region	1-20
Table 1.4-2	Summary of FES and Subsequent Sampling Results For Cottonwood Wash and Westwater Creek	1-26
Table 1.5-1	Surveyed Locations and Elevations of Seeps and Springs and the Frog Pond (December, 2009)	1-41
Table 1.5-2	Water Quality of the Navajo Sandstone Aquifer in the Mill Vicinity	1-48
Table 1.5-3	Results of Quarterly Sampling Ruin Spring (2003-2004)	1-58
Table 1.5-4	Seeps and Springs Sampling.....	1-60
Table 1.5-5	Wells Located Within a 5-Mile Radius of the White Mesa Uranium Mill (Denison, 2009a).....	1-62
Table 1.6-1	Generalized Stratigraphic Section of Subsurface Rocks Based on Oil-Well Logs (Table 2.6-1 UMETCO).....	1-94
Table 1.6-2	Generalized Stratigraphic Section of Exposed Rocks in the Project Vicinity (Table 2.6-2 UMETCO)	1-95
Table 1.6-3	Modified Mercalli Scale	1-113
Table 1.7-1	Community Types and Expanse Within the Project site Boundary.....	1-125
Table 1.7-2	Ground Cover For Each Community Within the Project Site Boundary.....	1-125
Table 1.7-3	Birds Observed in the Vicinity of the White Mesa Project	1-128
Table 1.7-4	Endangered, Threatened and Candidate Species in the Mill Area.....	1-131
Table 1.7-5	Species Managed Under Conservation Agreements/Strategies at the Mill Area.....	1-132
Table 2.3-1	Groundwater Monitoring Constituents Listed in Table 2 of the GWDP	2-11
Table 2.3-2	Operational Phase Surface Water Monitoring Program	2-20
Table 3.3-1	Average Radon Flux From Tailings Cells 2004-2010.....	3-12
Table 3.3-2	Results of Slope Stability Analyses	3-15
Table 3.3-3	Estimate of Future Settlement in Tailings Cells	3-19
Table 3.3-4	Reclamation Cover Material Quantity Summary	3-21

LIST OF FIGURES

Figure	Description	Page
Figure 1-1	White Mesa Mill Regional Location Map.....	1-2
Figure 1-2	White Mesa Mill Location Map	1-3
Figure 1.1-1	Wind Rose - 2010.....	1-11
Figure 1.4-1	Drainage Map of the Vicinity of the White Mesa Mill. Adapted from: Dames & Moore (1978b), Plate 2.6-5	1-18
Figure 1.4-2	Streamflow Summary in the Blanding, Utah Vicinity (Adapted from Dames & Moore (1978b), Plate 2.6-6, updated)	1-22
Figure 1.4-3	Surface Water Quality Sampling Stations in the White Mesa Mill Vicinity Prior to Mill Operations (Adapted from Dames & Moore (1978b), Plate 2.6-10).....	1-23
Figure 1.5-1	Generalized Stratigraphy of White Mesa Mill (Adapted from the 2007 ER, Figure 3.7-1).....	1-32
Figure 1.5-2	Approximate Elevation of Top of Brushy Basin (Adapted from HGC, 2010, Figure 3)	1-34
Figure 1.5-3	2nd Kriged Perched Water Levels 2nd Quarter, 2010 (Adapted from HGC, 2010, Figure 4).....	1-37
Figure 1.5-4	Depth to Perched Water 2nd Quarter, 2010 (Adapted from HGC, 2010, Figure 6)	1-39
Figure 1.5-5	Perched Zone Saturated Thickness 2nd Quarter, 2010 (Adapted from HGC, 2010, Figure 5).....	1-40
Figure 1.5-6	Seeps and Springs on USGS Topographic Base, White Mesa (Adapted from HGC, 2010, Figure 7).....	1-42
Figure 1.5-7	Geologic Map on USGS Topographic Base (HGC, 2010 Figure 8).....	1-44
Figure 1.5-8	Groundwater (Well or Spring) Sampling Stations in the White Mesa Vicinity (Adapted from the 2007 ER, Figure 3.7-8)	1-50
Figure 1.5-9	Ground Water Appropriation Applications Within a 5-Mile Radius	1-89
Figure 1.6-1	Colorado Plateau Geology Map (Adapted from the 2007 ER, Figure 3.4- 1).....	1-92
Figure 1.6-2	White Mesa Millsite Geology of Surrounding Area	1-105
Figure 1.6-3	Seismicity Within 320km of the White Mesa Mill	1-112
Figure 1.6-4	Seismicity Within 200km of the White Mesa Mill	1-115
Figure 1.6-5	Seismicity of the Western United States 1950 to 1976.....	1-117
Figure 1.6-6	Colorado Lineament	1-120

Figure 1.7-1	Vegetation Community Types on the White Mesa Mill Site	1-126
Figure 2.3-1	Site Plan and Perched Well Locations White Mesa Site (Adapted from HydroGeochem, Figure A-1)	2-10
Figure 2.3-2	High Volume Air Monitoring Stations (Adapted from the 2007 ER, Figure 3.3-2).....	2-14
Figure 3.1-1	White Mesa Mill Regional Map Showing Land Position	3-2

LIST OF DRAWINGS

REC-0	Title Sheet and Project Location Map
REC-1	Plan View of Reclamation Features
REC-2	Mill Site and Ore Pad Final Grading Plan
REC-3	Sedimentation Basin Detail
TRC-1	Interim Fill Grading Plan
TRC-2	Compacted Cover Grading Plan
TRC-3	Final Cover Surface Layout
TRC-4	Reclamation Cover Erosion Protection
TRC-5	Cover Over Cell 4A & 4B Cross Sections
TRC-6	Cover Over Cell 3 Cross Sections
TRC-7	Cover Over Cell 2 Cross Sections
TRC-8	Reclamation Cover Details

LIST OF ATTACHMENTS

Attachment	Description
A	Plans and Technical Specifications for Reclamation of White Mesa Mill Facility, Blanding, Utah.
B	Construction Quality Assurance/Quality Control Plan for Reclamation of White Mesa Mill Facility, Blanding, Utah.
C	Cost Estimates for Reclamation of White Mesa Facility in Blanding, Utah.
D	Radiation Protection Manual for Reclamation

LIST OF APPENDICES

Appendix	Description
A	Semi-Annual Effluent Report (January through June, 2011) for the Mill
B	Hydrogeology of the Perched Groundwater Zone and Associated Seeps and Springs Near the White Mesa Uranium Mill Site, Blanding, Utah, November 12, 2010, prepared by Hydro Geo Chem, Inc. (the “2010 HGC Report”)
C	The Mill’s Stormwater Best Management Practices Plan, Revision 1.3, June 12, 2008, Emergency Response Plan, Revision 2.1, August 18, 2009, and Spill Prevention, Control, and Countermeasures Plan, 2011.
D	Updated Tailings Cover Design Report, White Mesa Mill, September 2011. MWH Americas, Inc.
E	National Emission Standards for Hazardous Air Pollutants Radon Flux Measurement Program, White Mesa Mill Site, 2010, Tellco Environmental
F	Semi-Annual Monitoring Report January 1 – June 30, 2011, White Mesa Mill Meteorological Station, August 19, 2011, McVehil-Monnett Associates, Inc.
G	Preliminary Mill Decommissioning Plan, White Mesa Mill, September 2011, MWH Americas, Inc.

INTRODUCTION

This Reclamation Plan (the “Plan”) has been prepared by Denison Mines (USA) Corp. (“Denison”)¹ for Denison’s White Mesa Uranium Mill (the “Mill”), located approximately six miles south of Blanding, Utah. This Plan presents Denison’s plans and estimated costs for the reclamation of tailings Cells 1, 2, 3, 4A, and 4B at the Mill site, and for decommissioning of the Mill and Mill site.²

Summary of Plan

The uranium and vanadium processing areas of the Mill, including all equipment, structures and support facilities will be decommissioned and disposed of in tailings or buried at the Mill site as appropriate. All equipment (including tankage and piping, agitation, process control instrumentation and switchgears, and contaminated structures) will be cut up, removed, and buried in tailings prior to final cover placement. Concrete structures and foundations will be demolished and removed for disposal in tailings or covered in place with soil as appropriate.

The sequence of demolition will proceed so as to allow the maximum use of support areas of the facility, such as the office and shop areas. Any uncontaminated or decontaminated equipment to be considered for salvage will be released in accordance with United States Nuclear Regulatory Commission (“NRC”) guidance and in compliance with the conditions of the Denison’s State of Utah Radioactive Materials License No. UT1900479 (the “License”). As with the equipment for disposal, any contaminated soils from the Mill and surrounding areas and any ore or feed materials on the Mill site will be disposed of in the tailings cells in accordance with Attachment A, Plans and Technical Specifications.

¹ Prior to December 16, 2006, Denison was named “International Uranium (USA) Corporation.”

² Cell 1 was previously referred to as Cell 1-I. It is now referred to as Cell 1.

The estimated reclamation costs for surety are set out in Attachment C. Attachment C will be reviewed and updated on a yearly basis.

Plan Organization

General site characteristics pertinent to this Plan are contained in Section 1.0. Descriptions of the facility construction, operations and monitoring are given in Section 2.0. The current environmental monitoring program is described in Section 2.3. Seismic risk is assessed in Section 1.6.3.

The reclamation plan itself, including descriptions of facilities to be reclaimed and design criteria, is presented in Section 3.0. Attachments A through D comprise the Plans and Technical Specifications, Construction Quality Assurance/Quality Control (QA/QC) Plan, Cost Estimates, and Radiation Protection Manual for Reclamation.

Supporting documents, which have been reproduced as appendices for ease of review, include:

- *Semi-Annual Effluent Report* (January through June, 2011), for the Mill (Appendix A);
- *Hydrogeology of the Perched Groundwater Zone and Associated Seeps and Springs Near the White Mesa Uranium Mill Site, Blanding, Utah*, November 12, 2010, prepared by Hydro Geo Chem, Inc. (the “2010 HGC Report”) (Appendix B);
- The Mill’s *Stormwater Best Management Practices Plan*, Revision 1.3, June 12, 2008, *Emergency Response Plan*, Revision 2.1, August 18, 2009, and *Spill Prevention, Control, and Countermeasures Plan*, 2011. (Appendix C);
- *Updated Tailings Cover Design Report*, September 2011. MWH Americas, Inc. (Appendix D);
- *National Emission Standards for Hazardous Air Pollutants Radon Flux Measurement Program, White Mesa Mill Site*, 2010, Tellco Environmental (Appendix E); and

- *Semi-Annual Monitoring Report January 1 – June 30, 2010, White Mesa Mill Meteorological Station*, August 19, 2011, McVehil-Monnett Associates, Inc. (Appendix F).
- *Mill Decommissioning Plan, September, 2011*. MWH Americas, Inc. (Appendix G)

As required by Part I.H.11 of the Mill's State of Utah Ground Water Discharge Permit No. UGW370004 (the "GWDP"), Denison has completed an infiltration and contaminant transport model of the final tailings cover system to demonstrate the long-term ability of the cover to protect nearby groundwater quality (MWH, 2010). The updated cover design is included in the Updated Tailings Cover Design Report (MWH, 2011b) included as Appendix D to this Reclamation Plan, and includes a monolithic evapotranspiration (ET) cover for the tailings cells. The revised cover design and basis will be used for this version of the Plan.

Revisions to this Reclamation Plan include information related to the updated tailings cover design and the construction of tailings Cell 4B, as well as results of data collection and monitoring since Version 4.0 of this Plan (Denison, 2009). Revisions to the attachments and appendices of the Reclamation Plan are listed in a tabular format in Table I-1.

Table I-1
Revisions to Attachments and Appendices in Reclamation Plan

Attachments/ Appendices	Reclamation Plan v. 4.0 (2009)	Reclamation Plan v. 5.0 (2011)
Attachment A	Plans and Specifications for Reclamation of White Mesa Mill Facility, Blanding, Utah	Updated - Plans and Technical Specifications for Reclamation of White Mesa Mill Facility, Blanding, Utah
Attachment B	Quality Plan for Construction Activities, White Mesa Project, Blanding, Utah	Updated - Construction Quality Assurance/Quality Control Plan for Reclamation of White Mesa Mill Facility, Blanding, Utah
Attachment C	Cost Estimates for Reclamation of White Mesa Facility in Blanding, Utah	Updated - Cost Estimates for Reclamation of White Mesa Facility in Blanding, Utah
Attachment D	Reclamation Material Characteristics	Deleted – pertinent information now included in Updated Tailings Cover Design Report (Appendix D); New Attachment D - Radiation Protection Manual for Reclamation
Attachment E	Evaluation of Potential Settlement Due to Earthquake-Induced Liquefaction and Probabilistic Seismic Risk Assessment	Deleted – updated analyses and latest seismic hazard analysis included in Updated Tailings Cover Design Report (Appendix D)
Attachment F	Radon Emanation Calculations (Revised)	Deleted – updated analyses included in Updated Tailings Cover Design Report (Appendix D)
Attachment G	Channel and Toe Apron Design Calculations of White Mesa Facilities in Blanding, Utah.	Deleted – updated analyses included in Updated Tailings Cover Design Report (Appendix D)
Attachment H	Rock Test Results - Blanding Area Gravel Pits	Deleted – test results included in Updated Tailings Cover Design Report (Appendix D)

Table I-1
Revisions to Attachments and Appendices in Reclamation Plan (continued)

Attachments/ Appendices	Reclamation Plan v. 4.0 (2009)	Reclamation Plan v. 5.0 (2011)
Appendix A	<i>Semi-Annual Effluent Reports (January through June, 2008), (June through December, 2008) and (January through June, 2009), for the Mill</i>	Updated - <i>Semi-Annual Effluent Report</i> (January through June, 2011), for the Mill
Appendix B	<i>Site Hydrogeology and Estimation of Groundwater Travel Times In The Perched Zone White Mesa Uranium Mill Site Near Blanding, Utah, August 27, 2009, prepared by Hydro Geo Chem, Inc. (the “2009 HGC Report”)</i>	Updated - <i>Hydrogeology of the Perched Groundwater Zone and Associated Seeps and Springs Near the White Mesa Uranium Mill Site, Blanding, Utah, November 12, 2010, prepared by Hydro Geo Chem, Inc. (the “2010 HGC Report”)</i>
Appendix C	<i>The Mill’s Stormwater Best Management Practices Plan, Revision 1.3: June 12, 2008</i>	Updated - <i>The Mill’s Stormwater Best Management Practices Plan, Revision 1.3, June 12, 2008, Emergency Response Plan, Revision 2.1, August 18, 2009, and Spill Prevention, Control, and Countermeasures Plan, 2011.</i>
Appendix D	<i>Tailings Cover Design, White Mesa Mill, October 1996. Titan Environmental Corporation</i>	Updated - <i>Updated Tailings Cover Design Report, White Mesa Mill, September 2011. MWH Americas, Inc.</i>
Appendix E	<i>National Emission Standards for Hazardous Air Pollutants Radon Flux Measurement Program, White Mesa Mill Site, 2008, Tellco Environmental</i>	Updated - <i>National Emission Standards for Hazardous Air Pollutants Radon Flux Measurement Program, White Mesa Mill Site, 2010, Tellco Environmental</i>
Appendix F	<i>Semi-Annual Monitoring Report July 1 -- December 31, 2008 and Annual Monitoring Summary for 2008, White Mesa Mill Meteorological Station, January 20, 2009, McVehil-Monnett Associates, Inc.</i>	Updated - <i>Semi-Annual Monitoring Report January 1 - June 30, 2010, White Mesa Mill Meteorological Station, August 19, 2011, McVehil-Monnett Associates, Inc.</i>
Appendix G	N/A	New appendix - <i>Preliminary Mill Decommissioning Plan, White Mesa Mill, September 2011, MWH Americas, Inc.</i>


1 SITE CHARACTERISTICS

Denison operates the Mill, which is located approximately six miles south of Blanding, Utah (see Figures 1-1 and 1-2). The Mill was initially licensed by the NRC in May 1980 under NRC Source Material License No. SUA-1358. Upon the State of Utah becoming an Agreement State for uranium mills in August 2004, the Mill's NRC license was replaced with the Mill's current State of Utah License and the Mill's GWDP.

The License was up for timely renewal on March 31, 2007 in accordance with Utah Administrative Code ("UAC") R313-22-36.³ In accordance with R313-22-36, Denison submitted an application to the Executive Secretary on February 27, 2007 for renewal of the License under R313-22-37 (the "2007 License Renewal Application"). Similarly, the GWDP is up for timely renewal on March 8, 2010, in accordance with UAC") R317-6-6.7. On September 2, 2009, Denison filed an application (the "2009 GWDP Renewal Application") to the Executive Secretary for renewal of the GWDP for another 5 years under R313-6-6.7.

The Mill is also subject to State of Utah Air Quality Approval Order DAQE-AN1205005-06 (the "Air Approval Order") which was re-issued on July 20, 2006 and is not up for renewal at this time.

³ The License was originally issued by the NRC as a source material license under 10 CFR Part 40 on March 31, 1980. It was renewed by NRC in 1987 and again in 1997. After the State of Utah became an Agreement State for uranium mills in August 2004, the License was re-issued by the Executive Secretary as a State of Utah Radioactive Materials License on February 16, 2005, but the remaining term of the License did not change.




White Mesa Mill

Denison Mines (USA) Corp.		
Project: WHITE MESA MILL		
County: San Juan	State: Utah	
FIGURE 1-1 REGIONAL LOCATION MAP		
Date: Nov 2009	Design:	Drafted By: D. Sledd

Scale 1" = 5 miles A portion of USGS Map No NJ12-9 Cortez, CO-UT

W:\USA\Utah\Mill\dwgs\Reclamation\Plans\Rev_07-2011\Work01_Harold\Fig.1-2_LocationMap.dwg Layout1 GMoseley



Denison Mines (USA) Corp													
<table border="1"> <tr> <th>REVISIONS</th> <th>Project:</th> <td colspan="2">White Mesa Mill</td> </tr> <tr> <td>Date</td> <td>By</td> <td>County: San Juan</td> <td>State: UT</td> </tr> <tr> <td>07-11</td> <td>GM</td> <td colspan="2">Location:</td> </tr> </table>	REVISIONS	Project:	White Mesa Mill		Date	By	County: San Juan	State: UT	07-11	GM	Location:		<p style="text-align: center;">LOCATION MAP FIGURE 1-2</p>
REVISIONS	Project:	White Mesa Mill											
Date	By	County: San Juan	State: UT										
07-11	GM	Location:											
UT83-SF	Author:	Date: May 1999	Drafted By: RAH										

Revision 3.0 of this Plan was submitted to and approved by NRC in 2000. A copy of Revision 3.0 of this Plan was also submitted to the Executive Secretary as part of the 2007 License Renewal Application. Revision 4.0 of this Plan was submitted to the Executive Secretary in November 2009. Denison has prepared this Revision 5.0 of the Plan, which updates the Plan to incorporate changes since 2009 and to address interrogatories from the Executive Secretary (DRC, 2010 and 2011).

This Section 1.0 of the Plan incorporates by reference, updates or supplements, information previously submitted in previous environmental analyses performed at the Mill, as described below.

A Final Environmental Statement Related to Operation of White Mesa Uranium Project, Energy Fuels Nuclear, Inc., May, 1979, Docket No. 40-8681 (the “FES”) was prepared by NRC for the original License application in May 1979, which is incorporated by reference into, updated or supplemented by this Section 1.0. The basis for the FES was the *Environmental Report, White Mesa Uranium Project San Juan County, Utah*, dated January 1978, prepared by Dames & Moore (the “1978 ER”). In addition, the following environmental evaluations and other reports have also been performed for the Mill and are incorporated by reference into, updated or supplemented by this Section 1.0:

- the Environmental Assessment (“EA”) that was prepared for this Plan in February 2000 by NRC (the “2000 EA”);
- the EA that was prepared in August, 2002 by NRC (the “2002 EA”) in connection with a License amendment issued by NRC authorizing receipt and processing at the Mill of certain alternate feed materials from the Maywood Formerly Utilized Sites Remedial Action Program site in Maywood, New Jersey;

- the *Statement of Basis* that was prepared in December 2004 by the State of Utah Department of Environmental Quality (“UDEQ”) Division of Radiation Control (“DRC”) in connection with the issuance of the GWDP (the “GWDP Statement of Basis”);
- the *Environmental Report in Support of the License Renewal Application, State of Utah Radioactive Materials License No. UT1900479*, February 28, 2007 (the “2007 ER”);
- the *Revised Background Groundwater Quality Report: Existing Wells For Denison Mines (USA) Corp.’s White Mesa Mill Site, San Juan County, Utah*, October 2007, prepared by INTERA, Inc. (the “Existing Well Background Report”);
- the *Revised Addendum: -- Evaluation of Available Pre-Operational and Regional Background Data, Background Groundwater Quality Report: Existing Wells For Denison Mines (USA) Corp.’s White Mesa Mill Site, San Juan County, Utah*, November 16, 2007, prepared by INTERA, Inc. (the “Regional Background Report”); and
- the *Revised Addendum: -- Background Groundwater Quality Report: New Wells For Denison Mines (USA) Corp.’s White Mesa Mill Site, San Juan County, Utah*, April 30, 2008, prepared by INTERA, Inc. (the “New Well Background Report”, and together with the Existing Well Background Report and the Regional Background Report, the “Background Reports”).

1.1 Climate and Meteorology

1.1.1 Regional

The climate of southeastern Utah is classified as dry to arid continental. Although varying somewhat with elevation and terrain, the climate in the vicinity of the Mill can be considered as semi-arid with normal annual precipitation of about 13.32 inches. See Table 1.1-1. Most precipitation is in the form of rain with snowfall accounting for about 29 percent of the annual total precipitation. There are two separate rainfall seasons in the region, the first in late summer and early autumn (August to October) and the second during the winter months (December to

March). The mean annual relative humidity is about 44 percent and is normally highest in January and lowest in July. The average annual Class A pan evaporation rate is 68 inches (National Oceanic and Atmospheric Administration and U.S. Department of Commerce, 1977), with the largest evaporation rate typically occurring in July. This evaporation rate is not appropriate for determining water balance requirements for the tailings management system and must be reduced by the Class A pan coefficient to determine the latter evaporation rate. Values of pan coefficients range from 60 to 81 percent. Denison assumes for water balance calculations an average value of 70 percent to obtain an annual lake evaporation rate for the Mill area of 47.6 inches. Given the annual average precipitation rate of 13.32 inches, the net evaporation rate is 34.28 inches per year.

The weather in the Blanding area is typified by warm summers and cold winters. The National Weather Service Station in Blanding, Utah is located about 6.25 miles north of the Mill. Data from the station is considered representative of the local weather conditions (1978 ER, Section 2.7.2). The mean annual temperature in Blanding was 50.3°F, based on the current Period of Record Summary (1904 - 2006). January is usually the coldest month and July is usually the warmest month. See Table 1.1-2.

**Table 1.1-1
Period of Record General Climate Summary – Precipitation**

Station:(420738) BLANDING														
From Year=1904 To Year=2006														
	Precipitation											Total Snowfall		
	Mean	High	Year	Low	Year	1 Day Max.	>= 0.01 in.	>= 0.10 in.	>= 0.50 in.	>= 1.00 in.	Mean	High	Year	
	in.	in.	-	in.	-	in.	dd/yyyy or yyyymmdd	# Days	# Days	# Days	# Days	in.	in.	-
January	1.39	5.31	1993	0.00	1972	1.49	15/1978	6	4	1	0	10.8	46.9	1979
February	1.21	3.87	1913	0.00	1906	1.50	03/1908	6	3	1	0	7.3	39.7	1913
March	1.05	3.72	1906	0.00	1932	1.13	01/1970	6	3	1	0	4.4	17.9	1970
April	0.87	4.35	1926	0.00	1908	1.33	04/1987	5	2	0	0	1.9	15.2	1957
May	0.71	2.62	1926	0.00	1910	1.26	25/1994	4	2	0	0	0.2	4.0	1978
June	0.45	2.84	1948	0.00	1906	1.40	28/1938	3	1	0	0	0.0	0.0	1905
July	1.15	3.55	1914	0.00	1920	1.74	21/1985	6	3	1	0	0.0	2.5	1906
August	1.38	4.95	1968	0.03	1985	4.48	01/1968	7	4	1	0	0.0	0.0	1905
September	1.28	4.80	1927	0.00	1912	1.85	29/1905	5	3	1	0	0.0	3.5	1905
October	1.45	7.01	1916	0.00	1915	2.00	19/1908	5	3	1	0	0.3	6.0	1984
November	1.05	4.17	1905	0.00	1929	2.79	27/1919	4	3	1	0	3.3	19.0	1931
December	1.33	6.84	1909	0.00	1917	3.50	23/1909	5	3	1	0	9.8	55.0	1909
Annual	13.32	24.42	1909	4.93	1956	4.48	19680801	62	36	7	1	38.2	121.0	1909
Winter	3.93	11.95	1909	0.29	1964	3.50	19091223	17	10	2	0	27.9	100.2	1979
Spring	2.63	7.77	1926	0.10	1972	1.33	19870404	15	8	1	0	6.5	28.7	1970
Summer	2.98	6.90	1987	0.12	1960	4.48	19680801	16	8	2	0	0.0	2.5	1906
Fall	3.78	8.70	1972	0.50	1917	2.79	19191127	14	9	2	1	3.7	19.5	1908

Table updated on Jul 28, 2006

For monthly and annual means, thresholds, and sums:
Months with 5 or more missing days are not considered
Years with 1 or more missing months are not considered
Seasons are climatological not calendar seasons

Winter = Dec., Jan., and Feb. Spring = Mar., Apr., and May
Summer = Jun., Jul., and Aug. Fall = Sep., Oct., and Nov.

**Table 1.1-2
Period of Record General Climate Summary - Temperature**

Station:(420738) BLANDING															
From Year=1904 To Year=2006															
	Monthly Averages			Daily Extremes				Monthly Extremes				Max. Temp.		Min. Temp.	
	Max.	Min.	Mean	High	Date	Low	Date	Highest Mean	Year	Lowest Mean	Year	>= 90 F	<= 32 F	<= 32 F	<= 0 F
	F	F	F	F	dd/yyyy or yyyymmdd	F	dd/yyyy or yyyymmdd	F	-	F	-	# Days	# Days	# Days	# Days
January	39.1	17.2	28.2	63	31/2003	-20	12/1963	40.2	2003	12.6	1937	0.0	6.2	30.3	1.8
February	44.9	22.3	33.6	71	28/1906	-23	08/1933	44.2	1995	18.8	1933	0.0	2.0	26.1	0.7
March	52.7	27.8	40.3	86	31/1906	-3	28/1975	51.0	2004	33.0	1948	0.0	0.3	23.4	0.0
April	62.2	34.3	48.2	88	19/1905	10	24/1913	56.9	1992	39.4	1928	0.0	0.0	12.4	0.0
May	72.3	42.1	57.2	98	31/2002	15	16/1910	65.0	2000	50.1	1917	0.4	0.0	2.7	0.0
June	83.3	50.7	67.0	110	22/1905	28	03/1908	75.3	2002	61.2	1907	6.3	0.0	0.2	0.0
July	88.7	57.9	73.3	109	19/1905	36	15/1934	81.1	2003	66.3	1916	15.1	0.0	0.0	0.0
August	86.2	56.2	71.2	106	18/1905	38	23/1968	77.2	1926	65.6	1968	9.0	0.0	0.0	0.0
September	78.2	48.3	63.3	100	01/1905	20	26/1908	70.2	2001	56.6	1922	1.3	0.0	0.3	0.0
October	66.0	38.0	52.0	99	08/1905	10	30/1971	59.6	2003	44.6	1969	0.1	0.0	6.6	0.0
November	51.4	26.7	39.1	74	04/1905	-7	25/1931	47.3	1999	32.4	1952	0.0	0.4	23.6	0.1
December	41.2	19.2	30.2	65	03/1929	-13	23/1990	39.4	1980	19.4	1931	0.0	4.5	30.0	0.9
Annual	63.8	36.7	50.3	110	19050622	-23	19330208	55.1	2003	47.2	1932	32.2	13.5	155.6	3.4
Winter	41.7	19.5	30.7	71	19060228	-23	19330208	37.5	1907	19.3	1933	0.0	12.7	86.4	3.3
Spring	62.4	34.7	48.6	98	20020531	-3	19750328	54.8	2004	43.6	1909	0.4	0.3	38.5	0.0
Summer	86.0	54.9	70.5	110	19050622	28	19080603	76.4	2002	67.4	1941	30.4	0.0	0.2	0.0
Fall	65.2	37.7	51.4	100	19050901	-7	19311125	58.3	1926	47.8	1912	1.4	0.4	30.5	0.1

Table updated on Jul 28, 2006

For monthly and annual means, thresholds, and sums:
Months with 5 or more missing days are not considered
Years with 1 or more missing months are not considered
Seasons are climatological not calendar seasons

Winter = Dec., Jan., and Feb. Spring = Mar., Apr., and May
Summer = Jun., Jul., and Aug. Fall = Sep., Oct., and Nov.

Winds are usually light to moderate in the area during all seasons, although occasional stronger winds may occur in the late winter and spring. The predominant winds are from the north through north-east (approximately 30 percent of the time) and from the south through south-west (about 25 percent of the time). Winds are generally less than 15 mph, with wind speeds faster than 25 mph occurring less than one percent of the time (1978 ER, Section 2.7.2). As an element of the pre-construction baseline study and ongoing monitoring programs, the Mill operates an onsite meteorological station, described in greater detail below. Further details about weather and climate conditions are provided in the 1978 ER (Section 2.7) and in the FES (Section 2.1).

1.1.2 Storms (FES Section 2.1.4, updated)

Thunderstorms are frequent during the summer and early fall when moist air moves into the area from the Gulf of Mexico. Related precipitation is usually light, but a heavy local storm can produce over an inch of rain in one day. The maximum 24-hour precipitation reported to have fallen during period 1904-2006 at Blanding was 4.48 inches (11.36 cm). Hailstorms are uncommon in this area. Although winter storms may occasionally deposit comparable amounts of moisture, maximum short-term precipitation is usually associated with summer thunderstorms.

Tornadoes have been observed in the general region, but they occur infrequently. Strong winds can occur in the area along with thunderstorm activity in the spring and summer. The Mill area is susceptible to occasional dust storms, which vary greatly in intensity, duration, and time of occurrence. The basic conditions for blowing dust in the region are created by wide areas of exposed dry topsoil and strong, turbulent winds. Dust storms usually occur following frontal passages during the warmer months and are occasionally associated with thunderstorm activities.

1.1.3 On Site


On-site meteorological monitoring at the Mill was initiated in early 1977 and continues today. The original purpose of the meteorological monitoring program was to document the regional

atmospheric baseline and to provide data to assist in assessing potential air quality and radiological impacts arising from operation of the Mill.

After the Mill construction was completed, the monitoring programs were modified to facilitate the assessment of Mill operations. The current meteorological monitoring program includes data collection for wind speed, wind direction, atmospheric stability according to the standard Pasquill scheme (via measurements of deviations in wind direction, referred to as sigma-theta), and precipitation as either rain or snow. The recorded on-site meteorological conditions are reported to Denison on a semi-annual basis and are described in semi-annual reports prepared for Denison and maintained at the Mill. Figure 1.1-1 shows the windrose for the Mill site for the period of January – December 2010, the most recent full year of compiled meteorological data.

WIND ROSE PLOT:
White Mesa Mill
Meteorological Station

DISPLAY:
Wind Speed
Direction (blowing from)



COMMENTS:	DATA PERIOD:	COMPANY NAME:	
	2010 Jan 1 - Dec 31 00:00 - 23:00	Denison Mines (USA) Corporation	
	CALM WINDS:	MODELER:	
	0.03%	McVehil-Monnett Associates	
AVG. WIND SPEED:	TOTAL COUNT:	DATE:	PROJECT NO.:
3.43 m/s	8714 hrs.	1/14/2011	2397-10

WRPLOT View - Lakes Environmental Software

Denison Mines (USA) Corp **DENISON MINES**

REVISIONS		Project: White Mesa Mill	
Date	By	County: San Juan	State: UT
07-11	GM	Location:	
		WIND ROSE - 2010 (McVehil-Monnett Associates) FIGURE 1.1-1	
Author:		Date: 11-23-09	Drafted By: DLS

W:\USA\Utah\Mill\designs\Reclamation_Plans\Rev_07-2011\Work01_Melanie_Davis\Fig.1.1-1_WindRose_2010.dwg WindRose_2010 GMoseley

1.2 Topography

The following text is reproduced from Section 2.3 of the FES.

The site is located on a "peninsula" platform tilted slightly to the south-southeast and surrounded on almost all sides by deep canyons, washes, or river valleys. Only a narrow neck of land connects this platform with high country to the north, forming the foothills of the Abajo Mountains. Even along this neck, relatively deep stream courses intercept overland flow from the higher country. Consequently, this platform (White Mesa) is well protected from runoff flooding, except for that caused by incidental rainfall directly on the mesa itself. The land on the mesa immediately surrounding the Mill site is relatively flat.

1.3 Archeological Resources

The following discussion of archeological sites is adapted from Section 2.5.2.3 of the FES.

1.3.1 Archeological Sites

Archeological surveys of portions of the entire Mill site were conducted between the fall of 1977 and the spring of 1979. The total area surveyed contained parts of Section 21, 22, 27, 28, 32, and 33 of T37S, R22E, and encompassed 2,000 acres (809 ha), of which 200 acres (81 ha) are administered by the U. S. Bureau of Land Management ("BLM") and 320 acres (130 ha) are owned by the State of Utah. The remaining acreage is privately owned. During the surveys, 121 sites were recorded and all were determined to have an affiliation with the San Juan Anasazi who occupied this area of Utah from 0 A.D. to 1300 A.D. All but 22 of the sites were within the Mill site boundaries.

Table 1.3-1, adapted from FES Table 2.18, summarizes the recorded sites according to their probable temporal positions. The dates of occupation are the best estimates available, based on professional experience and expertise in the interpretation of archeological evidence. Available evidence suggests that settlement on White Mesa reached a peak in perhaps 800 A.D. Occupation remained at approximately that level until sometime near the end of Pueblo II or in the Pueblo II/Pueblo III transition period. After this period, the population density declined sharply, and it may be assumed that the White Mesa area was, for the most part, abandoned by about 1250 A.D.

Archeological test excavations were conducted by the Antiquities Section, Division of State History, in the spring of 1978, on 20 sites located in the area later to be occupied by tailings cells 2, 3 and 4 (now comprised of Cell 4A and proposed Cell 4B). Of these sites, 12 were deemed by the State Archeologist to have significant National Register potential and four to have possible significance. The primary determinant of significance in this study was the presence of structures, though storage features and pottery artifacts were also common.

In the fall of 1978, a surface survey was conducted on much of the previously unsurveyed portions of the proposed Mill site. Approximately 45 archeological sites were located during this survey, some of which are believed to be of equal or greater significance than the more significant sites from the earlier study. Determination of the actual significance of all untested sites would require additional field investigation.

Table 1.3-1
Distribution of Recorded Sites According to Temporal Position

Temporal position	Approximate dates (A.D.) ^a	Number of sites
Basket Maker III	575-750	2
Basket Maker III/Pueblo I	575-850	27
Pueblo I	750-850	12
Pueblo I/Pueblo II	850-950	13
Pueblo II	950-1100	14
Pueblo II/Pueblo III	1100-1150	12
Pueblo III	1150-1250	8
Pueblo II+	<i>B</i>	5
Multicomponent	<i>C</i>	3
Unidentified	<i>D</i>	14

a Includes transitional periods.

b Although collections at these locations were lacking in diagnostic material, available evidence indicates that the site would have been used or occupied no earlier than 900 A.D. and possibly later.

c Ceramic collections from each of these sites indicate an occupation extending from Pueblo I through Pueblo II and into Pueblo III.

d These sites did not produce evidence strong enough to justify any identification.

Source: Adapted from Dames & Moore (1978b) (1978 ER), Table 2.3-2, FES, Page 2-20, Table 2.18, and from supplementary reports on project archeology.

Pursuant to 10 CFR Part 63.3, the NRC submitted on March 28, 1979, a request to the Keeper of the National Register for a determination of eligibility for the area which had been surveyed and tested. The area contained 112 archeological sites and six historical sites. The determination by the Keeper of the National Register on April 6, 1979, was that the White Mesa Archeological District is eligible for inclusion in the National Register.

1.3.2 Current Status of Excavation

Archeological investigations for the entire Mill site and for Cells 1 through Cell 4 (now comprised of Cell 4A and Cell 4B) were completed with the issuance of four separate reports covering 30 sites, excluding re-investigations. (Lindsay 1978, Nielson 1979, Casjens et al 1980, and Agenbroad et al 1981).

The sites reported as excavated are as follows:

6380	6394	6437
6381	6395	6684
6384	6396	6685
6385	6397	6686
6386	6403	6697
6387	6404	6698
6388	6420	6699
6391	6429	6754
6392	6435	6757
6393	6436	7754

Sites for which excavation has not been required are:

6379	6441	7658	7690
6382	6443	7659	7691
6405	6444	7660	7693

The sites remaining to be excavated or investigated for significance are:

6408	6445	7657	7687
6421	6739	7661	7689
6427	6740	7665	7696
6430	7653	7668	7700
6432	7655	7675	7752
6439	7656	7684	7876

The following site was excavated in 2009 in connection with the construction of the new decontamination pad at the Mill:

42Sa27732

The following sites were excavated in the summer of 2010 in connection with the construction of Cell 4B and the final report is in preparation:

42Sa6391	42Sa6431	42Sa28129	42Sa28133
42Sa6392	42Sa6757	42Sa28130	42Sa28134
42Sa6393	42Sa8014	42Sa28131	
42Sa6397	42Sa28128	42Sa28132	


1.4 Surface Water

The following description of undisturbed surface water conditions is adapted from Section 2.6.1 of the FES and Section 3.7.1 of the 2007 ER updated to include current data.

The Mill was designed and constructed to prevent runoff of storm water by a) diverting runoff from precipitation on the Mill site to the tailings cells; and b) diverting runoff from surrounding areas away from the Mill site. In addition to these designed control features, the facility has developed a *Stormwater Best Management Practices Plan*, Revision 1.3: June 12, 2008 which includes a description of the site drainage features and the best management practices employed to assure appropriate control and routing of stormwater. A copy of the Mill's *Stormwater Best Management Practices Plan* is included as Appendix C to this Plan.

1.4.1 Surface Water Description (FES Section 2.6.1.1)

The Mill site is located on White Mesa, a gently sloping (1 percent SSW) plateau that is physically defined by the adjacent drainages which have cut deeply into regional sandstone formations. There is a small drainage area of approximately 62 acres (25 ha) above the site that could yield surface runoff to the site. Runoff from the Mill area is conducted by the general surface topography to either Westwater Creek, Corral Creek, or to the south into an unnamed branch of Cottonwood Wash. Local porous soil conditions, topography and low acreage annual rainfall of 13.32 inches cause these streams to be intermittently active, responding to spring snowmelt and local rainstorms (particularly thunderstorms). Surface runoff from approximately 384 acres (155 ha) of the Mill site drains westward and is collected by Westwater Creek, and runoff from another 384 acres (155 ha) drains east into Corral Creek. The remaining southern and southwestern portions of the site drain indirectly into Cottonwood Wash (Dames & Moore, 1978b, p. 2-143). The site and vicinity drainages carry water only on an intermittent basis. The major drainages in the project vicinity are depicted in Figure 1.4-1 and their drainages tabulated



- 1 USGS GAUGE NO. 09376900
- 2 USGS GAUGE NO. 09378630
- 3 USGS GAUGE NO. 09378700

Denison Mines (USA) Corp.		DENISON MINES	
Project WHITE MESA MILL			
REVISIONS		County:	State: UT
Date	By	Location:	
Figure 1.4-1 Drainage Map of the Vicinity of the White Mesa Mill			
Scale: 1:250,000		Date: Nov 2009	
Author: bm		Drafted By: D.Sledd	

in Table 1.4-1. Total runoff from the site area (total yield per watershed area) is estimated to be less than 0.5 inch (1.3cm) annually (Dames & Moore, 1978b, p. 2-143).

There are no perennial surface waters on or in the vicinity of the Mill site. This is due to the gentle slope of the mesa on which the site is located, the low average annual rainfall of 13.32 inches (33.8 cm) per year at Blanding, local soil characteristics and the porous nature of local stream channels. Prior to construction, three small ephemeral catch basins were present on the site to the northwest and northeast of the Mill site.

Corral Creek is an intermittent tributary to Recapture Creek. The drainage area of that portion of Corral Creek above and including drainage from the eastern portion of the site is about 5 square miles (13 km²). Westwater Creek is also an intermittent tributary of Cottonwood Wash. The Westwater Creek drainage basin covers nearly 27 square miles (70 km²) at its confluence with Cottonwood Wash 1.5 miles (2.5 km) west of the Mill site. Both Recapture Creek and Cottonwood Wash are similarly intermittently active, although they carry water more often and for longer periods of time due to their larger watershed areas. They both drain to the south and are tributaries of the San Juan River. The confluences of Recapture Creek and Cottonwood Wash with the San Juan River are approximately 18 miles (29 km) south of the Mill site. The San Juan River, a major tributary for the upper Colorado River, has a drainage of 23,000 square miles (60,000 km²) measured at the USGS gauge to the west of Bluff, Utah (Dames & Moore, 1978b, p. 2-130).

**Table 1.4-1
Drainage Areas of Project Vicinity and Region**

Basin description	Drainage area	
	km ²	sq. miles
Corral Creek at confluence with Recapture Creek	15.0	5.8
Westwater Creek at confluence with Cottonwood Wash	68.8	26.6
Cottonwood Wash at USGS gage west of project site	<531	<205
Cottonwood Wash at confluence with San Juan River	<860	<332
Recapture Creek at USGS gage	9.8	3.8
Recapture Creek at confluence with San Juan River	<518	<200
San Juan River at USGS gage downstream at Bluff, Utah	<60,000	<23,000

Source: Adapted from Dames & Moore (1978b), Table 2.6-3


Storm runoff in these streams is characterized by a rapid rise in the flow rates, followed by rapid recession primarily due to the small storage capacity of the surface soils in the area. For example, on August 1, 1968, a flow of 20,500 cfs (581 m³/sec) was recorded in Cottonwood Wash near Blanding. The average flow for that day, however, was only 4,340 cfs (123 m³/sec). By August 4, the flow had returned to 16 cfs (0.5 m³/sec) (Dames & Moore, 1978b, p. 2-135). Monthly streamflow summaries updated from Figure 2.4 of the FES are presented in Figure 1.4-2 for Cottonwood Wash, Recapture Creek and Spring Creek. Flow data are not available for the two smaller water courses closest to the Mill site, Corral Creek and Westwater Creek, because these streams carry water infrequently and only in response to local heavy rainfall and snowmelt, which occurs primarily in the months of April, August, and October. Flow typically ceases in Corral and Westwater Creeks within 6 to 48 hours after precipitation or snowmelt ends.

1.4.2 Surface Water Quality as of the Date of the FES (FES Section 2.6.1.2)


Sampling of surface water quality in the Mill vicinity began in July 1977 and continued through March 1978. Baseline data describe and evaluate existing conditions at the Mill site and vicinity. Sampling of the temporary on-site surface waters (two catch basins) was attempted but without success because of the lack of naturally occurring water in these basins. Sampling of ephemeral surface waters in the vicinity was possible only during major precipitation events, as these streams are normally dry at other times. See FES Section 2.6.1.2

The locations of the surface water sample sites used prior to Mill operations are presented in Figure 1.4-3. The water quality values obtained for these sample sites are given in Dames & Moore (1978b) Table 2.6-7, and FES Table 2.22. Water quality samples were collected during the spring at several intermittently active streams that drain the Mill area. These streams include Westwater Creek (S1R, S9) Corral Creek below the small irrigation pond (S3R), the junction of


AVERAGE ANNUAL FLOW=950 AF - (1966-2001)
 DRAINAGE AREA=3.77 SQ. MI.
 AVERAGE ANNUAL YIELD=252.1 AF/SQ. MI.



AVERAGE ANNUAL FLOW=6547 AF - (1965-1986)
 DRAINAGE AREA=205 SQ. MI.
 AVERAGE ANNUAL YIELD=32 AF/SQ. MI.



AVERAGE ANNUAL FLOW=7757 AF - (1966-1971)
 DRAINAGE AREA=4.95 SQ. MI.
 AVERAGE ANNUAL YIELD=153 AF/SQ. MI.



NOTES

1. FOR THE LOCATION OF WATER COURSES SUMMARIZED, SEE FIGURE 3.7-1
2. SOURCE OF DATA. WATER RESOURCES DATA RECORDS. COMPILED AND PUBLISHED BY USGS.

Denison Mines (USA) Corp.



Project: WHITE MESA MILL

County: San Juan State: Utah


FIGURE 1.4-2
Streamflow Summary
Blanding, UT Vicinity

Date: Nov, 2009


Design:

Drafted By: DLS

W:\USA\Utah\Mill\dwgs\Reclamation\Plans\Rev_07-2011\Work01_Harold\Fig.1.4-3_SurfaceWaterSampling.dwg Layout1 GMoseley



- PROPERTY BOUNDARY
- RESERVATION BOUNDARY
- CANYON RIM
- S** SURFACE WATER SAMPLING LOCATION



Denison Mines (USA) Corp		DENISON MINES	
Project: White Mesa Mill		County: San Juan	State: UT
Date: 07-11		Location:	
By: GM		SURFACE WATER QUALITY SAMPLING STATIONS IN THE WHITE MESA VICINITY	
		FIGURE 1.4-3	
Author:		Date: Nov 2009	Drafted By: DLS

UT83-SF

Corral Creek and Recapture Creek (S4R), and Cottonwood Creek (S8R). Samples were also taken from a surface pond southeast of the Mill (S5R). No samples were taken at S2R on Corral Creek or at the small wash (S6R) located south of the site.

Natural surface water quality in the vicinity of the Mill is generally poor. Waters in Westwater Creek (S1R and S9) were characterized by high total dissolved solids (TDS; mean of 674 mg/liter) and sulfate levels (mean 117 mg of SO₄ per liter). The waters were typically hard (total hardness measured as CaCO₃; mean 223 mg/liter) and had an average pH of 8.25. Estimated water velocities for Westwater Creek averaged 0.3 fps (0.08 m/sec) at the time of sampling.

Samples from Cottonwood Creek (S8R) at the time of the FES were generally similar in quality to Westwater Creek water samples, although the TDS and sulfate levels were lower (TDS averaged 264 mg/liter; SO₄ averaged 40 mg/liter) during heavy spring flow conditions [80 fps (24 m/sec) water velocity].

The concentrations of TDS increased downstream in Corral Creek, averaging 3,180 mg/liter at S3R and 6,660 mg/liter (one sample) at S4R. Total hardness averaged in excess of 2,000 mg/liter, and pH values were slightly alkaline. Estimated water velocities in Corral Creek were typically less than 0.1 fps (0.03 m/sec) during sampling.

The spring sample collected at the surface pond south of the Mill site (S5R) indicated a TDS concentration of less than 300 mg/liter. The water was slightly alkaline with moderate dissolved sulfate levels averaging 42 mg/liter.

During heavy runoff, the concentration of total suspended solids in these streams increased sharply to values in excess of 1,500 mg/liter (FES, Table 2.22). High concentrations of certain trace elements were measured in some sampling areas. Levels of mercury (total) were reported as high as 0.002 mg/liter (S3R, 7/25/77; S8R, 7/25/77). Total iron measured in the pond (S5R, 11/10/77) was 9.4 mg/liter. The FES concluded (Section 2.6.1.2 of the FES) that these values

appear to reflect groundwater quality in the vicinity and are probably due to evaporative concentration and not due to human perturbation of the environment. Corral Creek was also sampled at the time of the FES, but it has not been included in subsequent operational monitoring at the Mill. See Table 2.22 of the FES for sampling results for Corral Creek.

1.4.3 Surface Water Background Quality

Surface water samples are collected for Cottonwood Wash and Westwater Creek as part of the Mill's operational monitoring program. Samples were also taken prior to Mill construction and summarized in the FES as well as at various times and for various parameters since then. A comparison of the FES results and subsequent sampling results during Mill operation is set out in Table 1.4-2. Surface water values over time for both Cottonwood Wash and Westwater Creek are included in the Semi-Annual Effluent Reports.

Table 1.4-2
Summary of FES and Subsequent Sampling Results For Cottonwood Wash and Westwater Creek

Parameter	FES Cottonwood Wash (7/25/77-3/28/78)*	Cottonwood Wash (9/16/81-6/20/09)	Cottonwood Wash 2010	Cottonwood Wash 2011	FES Westwater Creek (11/10/77-3/23/78)*	Westwater Creek (2/22/82-6/20/09)	Westwater Creek 2010	Westwater Creek 2011
Field Specific Conductivity (µmhos/cm)	240-550	-	1612 ³ 1625 ³ 1600 ³	-	320-620	-	1707 ³ 1782 ³ 1650 ³	-
Field pH	6.6 to 8.1	-	6.42 ³ 6.67 ³	-	7.6-8.3	-	7.03 ³ 6.98 ³	-
Dissolved Oxygen	-	-	-	-	-	-	-	-
Temperature (°C)	6.0 to 35	-	16.17 ³ 15.85 ³ 15.05 ³	-	3-14	-	17.99 ³ 17.21 ³ 10.1 ³	-
Estimated Flow m/hr	0.4 to 80	-	-	-	0.28 to 39.9	-	-	-
pH	7.5 to 8.21	-	7.47 ³	-	8.2 to 8.35	-	7.38 ³	-
TDS (@180°C)	253 to 944	10 to 803*	900 ³ mg/L	978 ⁵ mg/L	496 to 969	93-1370*	1270 ³ mg/L	853 ⁶ mg/L
Redox Potential	210 to 260	-	501 ³ 492 ³	-	186 to 220	401 ³ 342 ³	-	-
Alkalinity (as CaCO ₃)	134 to 195	76 to 257*	-	-	147 to 229	230*	-	-
Hardness, total (as CaCO ₃)	148 to 195	-	-	-	117 to 289	-	-	-
Carbonate (as CO ₃)	0.0	ND	ND ³	6 ⁵ mg/L	0.0 to 2.3	ND	ND ³	ND ⁵
Bicarbonate (as HCO ₃)	-	316 mg/L	340 ³ mg/L	316 ⁵ mg/L	-	465 mg/L	-	371 ⁵ mg/L
Aluminum, dissolved	0.16 to 3.0	-	-	-	0.1 to 4.0	-	-	-
Ammonia (as N)	<0.1 to 0.16	ND	ND ³	ND ⁵	<0.1 to 0.75	ND	0.50 ³ mg/L	0.06 ⁵ mg/L
Arsenic, total	0.02 to 0.041	-	-	-	0.007 to 0.037	-	-	-
Arsenic, Dissolved	-	ND	ND ³	ND ⁵	-	ND	ND ³	12.3 ⁵ ug/L
Barium, total	0.2 to 1.2	-	-	-	<0.2 to 0.81	-	-	-
Beryllium, dissolved	-	ND	ND ³	ND ⁵	-	ND	ND ³	0.91 ⁵ ug/L
Boron, total	<0.1 to 0.2	-	-	-	<0.1 to 0.1	-	-	-
Cadmium, total	<0.002 to 0.01	-	-	-	<0.002 to 0.006	-	-	-
Cadmium, dissolved	-	ND	ND ³	ND ⁵	-	ND	ND ³	0.9 ⁵ ug/L

**Table 1.4-2
Summary of FES and Subsequent Sampling Results For Cottonwood Wash and Westwater Creek (continued)**

Parameter	FES Cottonwood Wash (7/25/77-3/28/78)*	Cottonwood Wash (9/16/81-6/20/09)	Cottonwood Wash 2010	Cottonwood Wash 2011	FES Westwater Creek (11/10/77-3/23/78)*	Westwater Creek (2/22/82-6/20/09)	Westwater Creek 2010	Westwater Creek 2011
Calcium, dissolved	54 to 178	90.3 mg/L	92.2 ³ mg/L	94.2 ⁶ mg/L	76 to 172	191 mg/L	179 ³ mg/L	247 ⁵ mg/L
Calcium	-	37 to 71*	-	-	-	94.5*	-	-
Chlorine	-	-	-	-	-	41*	-	-
Chloride	6 to 24	5 to 33.3*	112 ³ mg/L	134 ⁵ mg/L	17 to 125	76*	40 ³ mg/L	21 ⁵ mg/L
Sodium	-	18 to 104*	-	-	-	160.5*	-	-
Sodium, dissolved	21 to 66	205 mg/L	214 ³ mg/L	227 ⁵ mg/L	31 to 60	196 mg/L	160 ³ mg/L	112 ⁵ mg/L
Silver, dissolved	0.002 to <0.005	ND	ND ³	ND ⁵	<0.005 to 0.006	ND	ND ³	ND ⁵
Sulfate, dissolved (as SO ₄)	39.7 to 564	57 to 245*	389 ³ mg/L	389 ⁵ mg/L	85 to 163	408*	607 ³ mg/L	354 ⁵ mg/L
Vanadium, dissolved	<0.005 to <0.018	ND	ND ³	ND ⁵	<0.001 to 0.008	ND	ND ³	ND ⁵
Manganese, dissolved	0.02 to 0.84	ND	ND ³	ND ⁵	0.03 to 0.60	37 ug/L	87 ³ ug/L	268 ⁵ ug/L
Chromium, total	<0.01 to 0.14	-	-	-	<0.01 to 0.60	-	-	-
Chromium, dissolved	-	ND	ND ³	ND ⁵	-	ND	ND ³	ND ⁵
Copper, total	0.005 to 0.09	-	-	-	<0.005 to 0.05	-	-	-
Copper, dissolved	-	ND	ND ³	ND ⁵	-	ND	ND ³	16 ⁵ ug/L
Cobalt, dissolved	-	ND	ND ³	ND ⁵	-	ND	ND ³	ND ⁵
Fluoride, dissolved	0.2 to 0.36	0.4 mg/L	0.38 ³ mg/L	0.38 ⁵ mg/L	0.2 to 0.4	0.7 mg/L	0.60 ³ mg/L	0.54 ⁵ mg/L
Iron, total	5.9 to 150	-	-	-	0.28 to 44	-	-	-
Iron, dissolved	0.11 to 1.9	ND	ND ³	ND ⁵	0.17 to 2.5	89 ug/L	56 ³ ug/L	4540 ⁵ ug/L
Lead, total	0.05 to 0.14	-	-	-	<0.05 to 0.1	-	-	-
Lead, dissolved	-	ND	ND ³	ND ⁵	-	ND	ND ³	41.4 ⁵ ug/L
Magnesium	-	10.5 to 38.1*	-	-	-	23.5*	-	-
Magnesium, dissolved	17 to 28	25 mg/L	24.8 ³ mg/L	25.2 ⁵ mg/L	13 to 26	-	44.7 ³ mg/L	34.7 ⁵ mg/L
Mercury, total	0.00006 to 0.002	-	-	-	<0.00003 to <0.0005	-	-	-
Mercury, dissolved	-	ND	ND ³	ND ⁵	-	ND	ND ³	ND ⁵
Molybdenum, dissolved	0.002 to 0.10	ND	ND ³	ND ⁵	0.002 to 0.006	ND	29 ³ ug/L	ND ⁵
Nitrate (as N)	0.12 to 1.77	0.1 mg/L	ND ³	ND ⁵	<0.05 to 0.05	0.8 mg/L	ND ³	ND ⁵
Nickel, dissolved	-	ND	ND ³	ND ⁵	-	-	ND ³	ND ⁵
Phosphorus, total (as P)	0.05 to 3.2	-	-	-	0.05 to 0.88	-	-	-

**Table 1.4-2
Summary of FES and Subsequent Sampling Results For Cottonwood Wash and Westwater Creek (continued)**

Parameter	FES Cottonwood Wash (7/25/77-3/28/78)*	Cottonwood Wash (9/16/81-6/20/09)	Cottonwood Wash 2010	Cottonwood Wash 2011	FES Westwater Creek (11/10/77-3/23/78)*	Westwater Creek (2/22/82-6/20/09)	Westwater Creek 2010	Westwater Creek 2011
Potassium, dissolved	1.2 to 6.9	1.77 to 4 mg/L	5.77 ³ mg/L	5.9 ⁵ mg/L	2.0 to 3.2	4.05*	6.57 ³ mg/L	3.9 ⁵ mg/L
Selenium, dissolved	<0.005 to 0.08	ND	ND ³	ND ⁵	<0.005 to 0.003	ND	ND ³	ND ⁵
Silica, dissolved (as SiO ₂)	8 to 18	-	-	-	7 to 11	-	-	-
Strontium, total	0.34 to 0.64	-	-	-	0.44 to 0.76	-	-	-
Thallium, dissolved	-	ND	ND ³	ND ⁵	-	ND	ND ³	ND ⁵
Tin, dissolved	-	-	ND ³	ND ⁵	-	ND	ND ³	ND ⁵
Uranium, total	0.004 to 0.27	-	-	-	0.006 to 0.004	-	-	-
Uranium, dissolved	0.004 to 0.015	8.42 ug/L	8.24 ³ ug/L	8.68 ⁵ ug/L	0.002 to 0.015	15.1 ug/L	46.6 ³ ug/L	6.64 ⁵ ug/L
Zinc, dissolved	0.008 to 0.06	ND	ND ³	ND ⁵	0.04 to 0.12	ND	22 ³ ug/L	28 ⁵ ug/L
Total Organic Carbon	7 to 12	-	-	-	6 to 16	-	-	-
Chemical Oxygen Demand	61 to 163	-	-	-	23 to 66	-	-	-
Oil and Grease	2	-	-	-	1	-	-	-
Total Suspended Solids	146 to 2,025	0 to 24,300*	494 ⁴ mg/L	7.0 ⁶ mg/L	12 to 1940	<4 to 1,190*	13 ⁴ mg/L	-
Total Dissolve Solids	-	188 to 1,130*	331-624 ⁵ mg/L	425-463 ⁷ mg/L	-	1370 mg/L	1140 ⁴ mg/L	-
Gross Alpha	-	<1.0E-9 to 9.0E-7*	-	-	1E-10 to 4.5E-9	<1.0E-9*	-	-
Gross Alpha minus Rn & U	-	-	0.5 ⁴ pCi/L	0.2 ⁶ pCi/L	-	-	0.3 ⁴ pCi/L	0.5 ⁵ pCi/L
Gross Beta	-	-	-	-	0 to 8E-9	-	-	-
Uranium, dissolved	1.02E-9 to 2.79E-9	2.23E-9 to 6.02E-6*	0.0060 ⁴ mg/L	10.2 ⁶ ug/L	1.03E-9 to 1.35E-9	8.8E-7*	0.0057 ⁴ mg/L	-
Uranium, total ²	21.83E-7	-	-	-	6.09E-7	-	-	-
Uranium, suspended	-	<2.0E-10 to 2.0E-7*	0.0014 ⁴ mg/L	ND ⁶	0 to 1E-9	6.09E-7*	0.0005 ⁴ mg/L	-
Th-230, dissolved	-	<2.0E-10 to 4.14E-6*	0.05 ⁴ pCi/L	0.07 ⁶ pCi/L	-	<2.0E-10*	ND ⁴ pCi/L	-
Th-230, suspended	-	<2.0E-10 to <9.0E-7*	0.7 ⁴ pCi/L	0.2 ⁶ pCi/L	2E-10	3.0E-10*	0.2 ⁴ pCi/L	-
Ra-226, dissolved	-	<2.0E-10 to 2.0E-9*	0.09 ⁴ pCi/L	0.06 ⁶ pCi/L	-	2.0E-10*	0.18 ⁴ pCi/L	-
Ra-226, suspended	-	<2.0E-10 to <2.0E-7*	1.3 ⁴ pCi/L	ND ⁶	7E-10 to 1.1E-9	<2.0E-10*	4.3 ⁴ pCi/L	-
Pb-210	-	-	-	-	0 to 1E-10	-	-	-
Acetone	-	ND	ND ³	ND ⁵	-	ND	ND ³	ND ⁵
Benzene	-	ND	ND ³	ND ⁵	-	ND	ND ³	ND ⁵

**Table 1.4-2
Summary of FES and Subsequent Sampling Results For Cottonwood Wash and Westwater Creek (continued)**

Parameter	FES Cottonwood Wash (7/25/77-3/28/78)*	Cottonwood Wash (9/16/81-6/20/09)	Cottonwood Wash 2010	Cottonwood Wash 2011	FES Westwater Creek (11/10/77-3/23/78)*	Westwater Creek (2/22/82- 6/20/09)	Westwater Creek 2010	Westwater Creek 2011
Carbon Tetrachloride	-	ND	ND ³	ND ⁵	-	ND	ND ³	ND ⁵
Chloroform	-	ND	ND ³	ND ⁵	-	ND	ND ³	ND ⁵
Chloromethane	-	ND	ND ³	ND ⁵	-	ND	ND ³	ND ⁵
Methyl ethyl ketone	-	ND	ND ³	ND ⁵	-	ND	ND ³	ND ⁵
Methylene chloride	-	ND	ND ³	ND ⁵	-	ND	ND ³	ND ⁵
Napthalene	-	ND	ND ³	ND ⁵	-	ND	ND ³	ND ⁵
Toluene	-	ND	ND ³	ND ⁵	-	ND	ND ³	ND ⁵
Xylenes, total	-	ND	ND ³	ND ⁵	-	ND	ND ³	ND ⁵

Source: FES Table 2.22 and Mill Sample Data

*Data are from historic sampling events. All other data were collected during the 2009 annual Seeps and Springs and Semi-Annual Effluent sampling events.

² Calculated by Denison for activity comparison using the Specific Activity for U-nat (6.77E-7 Ci U-nat/g U-nat)

³ Data are from the 2010 Seeps and Springs sampling event.

⁴ Data are from 2010 SAER sampling events.

⁵ Data are from 2011 Seeps and Springs sampling event.

⁶ Data are from 2011 SAER quarterly sampling events.

1.5 Groundwater

1.5.1 Groundwater Characteristics

This Section is excerpted from the Report entitled: *Hydrogeology of the Perched Groundwater Zone and Associated Seeps and Springs Near the White Mesa Uranium Mill Site*, November 12, 2010, prepared by Hydro Geo Chem, Inc. (“HGC”) (the “2010 HGC Report”) (HGC, 2010b), a copy of which is included as Appendix B. The HGC 2010 report supplements the “HGC 2009” report summarized in Revision 4.0 of the Reclamation Plan, and provides additional information in response to Part I.H, Section 10 of the GWDP. Specifically, the additional information contained in the HGC 2010 report includes information on seeps and springs in the vicinity of the Mill, the relationship of the seeps and springs with the perched water system, and estimated travel times for shallow groundwater to travel from the tailings cells to the nearest discharge points, all of which address items requested by Part I.H, Section 10 of the GWDP.

1.5.1.1 Geologic Setting

The Mill is located within the Blanding Basin of the Colorado Plateau physiographic province. Typical of large portions of the Colorado Plateau province, the rocks underlying the site are relatively undeformed. The average elevation of the site is approximately 5,600 ft (1,707 m) above mean sea level (amsl).

The site is underlain by unconsolidated alluvium and indurated sedimentary rocks consisting primarily of sandstone and shale. The indurated rocks are relatively flat lying with dips generally less than 3 degrees. The alluvial materials consist mostly of aeolian silts and fine-grained aeolian sands with a thickness varying from a few feet to as much as 25 to 30 ft (7.6 to 9.1 m) across the site. The alluvium is underlain by the Dakota Sandstone and Burro Canyon Formation, which are sandstones having a total thickness ranging from approximately 100 to 140 ft (31 to 43 m). Beneath the Burro Canyon Formation lies the Morrison Formation, consisting,

in descending order, of the Brushy Basin Member, the Westwater Canyon Member, the Recapture Member, and the Salt Wash Member. The Brushy Basin and Recapture Members of the Morrison Formation, classified as shales, are very fine grained and have a very low permeability. The Westwater Canyon and Salt Wash Members also have a low average vertical permeability due to the presence of interbedded shales. See Figure 1.5-1 for a generalized stratigraphic column for the region.


Beneath the Morrison Formation lies the Summerville Formation, an argillaceous sandstone with interbedded shales, and the Entrada Sandstone. Beneath the Entrada lies the Navajo Sandstone. The Navajo and Entrada Sandstones constitute the primary aquifer in the area of the site. The Entrada and Navajo Sandstones are separated from the Burro Canyon Formation by approximately 1,000 to 1,100 ft (305 to 335 m) of materials having a low average vertical permeability. Groundwater within this system is under artesian pressure in the vicinity of the site, and is used only as a secondary source of water at the site.

1.5.1.2 Hydrogeologic Setting

The site is located within a region that has a dry to arid continental climate, with average annual precipitation of less than 13.3 in. and an annual lake evaporation rate of approximately 47.6 inches. Recharge to aquifers occurs primarily along the mountain fronts (for example, the Henry, Abajo, and La Sal Mountains), and along the flanks of folds such as Comb Ridge Monocline.

Although the water quality and productivity of the Navajo/Entrada aquifer are generally good, the depth of the aquifer (approximately 1,200 ft below land surface (bls)) makes access difficult. The Navajo/Entrada aquifer is capable of yielding significant quantities of water to wells (hundreds of gallons per minute (gpm)). Water in wells completed across these units at the site rises approximately 800 ft above the base of the overlying Summerville Formation.

APPROXIMATE THICKNESS



W:\USA\Utah\Mill\Reclamation Plans\RecPlan4.0\Figure 1.5-1 Stratigraphic Column.dwg Figure 3 23/11/2009 dslbedd


Taken from Stratigraphic Section near Water Well #3

Denison Mines (USA) Corp.		DENISON MINES	
Project		WHITE MESA MILL	
REVISIONS		County:	State: UT
Date	By	Location:	
		<p align="center">Figure 1.5-1 Generalized Stratigraphy of White Mesa Mill</p>	
Scale: N/A		Date: Aug 2009	
Author: HRR		Drafted By: D.Sledd	

1.5.1.3 Perched Zone Hydrogeology


Perched groundwater beneath the site occurs primarily within the Burro Canyon Formation. Perched groundwater at the site has a generally low quality due to high total dissolved solids (“TDS”) in the range of 1,100 to over 7,900 milligrams per liter (mg/L) and is used primarily for stock watering and irrigation in the areas upgradient (north) of the site. The saturated thickness of the perched water zone generally increases to the north of the site, increasing the yield of the perched zone to wells installed north of the site. Perched water is supported within the Burro Canyon Formation by the underlying, fine grained Brushy Basin Member. Figure 1.5-2 is a contour map showing the approximate elevation of the contact of the Burro Canyon Formation with the Brushy Basin Member, which essentially forms the base of the perched water zone at the site. Wells and piezometers shown in Figure 1.5-2 consist of surveyed perched zone monitoring wells and piezometers that include temporary perched zone monitoring wells (TW-4-series wells, including MW-4, TW4-4, TW4-19, TW4-20, and MW-26) associated with an area of elevated perched zone chloroform concentrations located east and northeast (cross gradient to upgradient) of the tailings cells (HGC, 2007). Contact elevations are based on monitoring well drilling and geophysical logs and surveyed land surface elevations. As indicated, the contact generally dips to the south/southwest beneath the site.

The permeability of the Dakota Sandstone and Burro Canyon Formation at the site is generally low. No significant joints or fractures within the Dakota Sandstone or Burro Canyon Formation have been documented in any wells or borings installed across the site (Knight Piésold, 1998). Any fractures observed in cores collected from site borings are typically cemented, showing no open space.



EXPLANATION

- Perched Monitoring Well
- Ⓜ Ruin Spring
- Ⓜ Seep or Spring



**HYDRO
GEO
CHEM, INC.**

**APPROXIMATE ELEVATION OF TOP
OF BRUSHY BASIN (FEET AMSL)
(generated by kriging data from on-site wells)**

APPROVED	DATE	REFERENCE	FIGURE
SJS		H:/718000/cell4bjuly2010/springQ2/phbbQ2.srf	1.5-2

Based on samples collected during installation of wells MW-16 (no longer used) and MW-17 (the locations of the various monitoring wells are indicated on Figure 1.5-2), located immediately downgradient of the tailings cells at the site, porosities of the Dakota Sandstone range from 13.4 percent to 26 percent, averaging 20 percent, and water saturations range from 3.7 percent to 27.2 percent, averaging 13.5 percent. The average volumetric water content is approximately 3 percent. The hydraulic conductivity of the Dakota Sandstone based on packer tests in borings installed at the site ranges from $2.71\text{E-}06$ centimeters per second (cm/s) to $9.12\text{E-}04$ cm/s, with a geometric average of $3.89\text{E-}05$ cm/s.

The average porosity of the Burro Canyon Formation is similar to that of the Dakota Sandstone. Based on samples collected from the Burro Canyon Formation at MW-16 (no longer used), located immediately downgradient of tailings Cell 3, porosity ranges from 2 percent to 29.1 percent, averaging 18.3 percent, and water saturations of unsaturated materials range from 0.6 percent to 77.2 percent, averaging 23.4 percent. Titan reported (Titan, 1994a) that the hydraulic conductivity of the Burro Canyon Formation ranges from $1.9\text{E-}07$ to $1.6\text{E-}03$ cm/s, with a geometric mean of $1.1\text{E-}05$ cm/s, based on the results of 12 pump/recovery tests performed in monitoring wells and 30 packer tests performed in borings prior to 1994.

Subsequent hydraulic testing of perched zone wells has yielded a range of $2\text{E-}07$ to 0.01 cm/s (HGC, 2010b). In general, the highest permeabilities and well yields are immediately northeast and east (upgradient to cross gradient) of the tailings cells. A relatively continuous, higher permeability zone has been inferred to exist in this portion of the site. Analysis of drawdown data collected from this zone during long-term pumping of MWH-4, MW-26 (TW4-15), and TW4-19 yielded estimates of hydraulic conductivity ranging from $4\text{E-}05$ to $1\text{E-}03$ cm/s. The decrease in perched zone permeability to the south to southwest of this area indicates that this higher permeability zone “pinches out” to the south and southwest.


Permeabilities downgradient of the tailings cells are generally low. Hydraulic tests at wells located at the downgradient edge of the cells, and south and southeast of the cells yielded

geometric average hydraulic conductivities of $2.3E-05$ and $4.3E-05$ cm/s depending on the testing and analytical methods. The low permeabilities and shallow hydraulic gradients downgradient of the tailings cells result in average perched groundwater pore velocity estimates that are among the lowest on site (approximately 1.7 ft/yr to 3.2 ft/yr based on calculations presented in HGC, 2009a).

Because of the generally low permeability of the perched zone beneath the site, well yields are typically low (less than 0.5 gpm), although yields of as much as 4 gpm are possible in wells intercepting larger saturated thickness and higher permeability zones on the east side of the site. Sufficient productivity can generally be obtained only in areas where the saturated thickness is greater, which is the primary reason that the perched zone has been used on a limited basis as a water supply to the north (upgradient) of the site, but has not been used downgradient of the site.

1.5.1.4 Perched Groundwater Flow


Perched groundwater flow at the site is generally to the south/southwest. Figure 1.5-3 displays the local perched groundwater elevation contours at the Mill, as measured in the second quarter of 2010. A local depression of the perched water table occurs near wells MW-4, TW4-4, TW4-19, TW4-10, and MW-26. These wells are pumped to reduce chloroform mass in the perched zone east and northeast of the tailings cells. As shown in Figure 1.5-3, the perched groundwater gradient changes from generally southwesterly in the western portion of the site to generally southerly in the eastern portion of the site. Perched zone hydraulic gradients currently range from a maximum of approximately 0.08 ft/ft east of tailings Cell 2 (near pumping well TW4-4) to approximately 0.01 ft/ft downgradient of the tailings cells.



EXPLANATION

- Perched Monitoring Well
- Ruin Spring Seep or Spring
- Estimated Dry Area (Kriged Brushy Basin Surface > Kriged Perched Water Surface)

NOTES: MW-4, TW4-4, TW4-15 (MW-26), TW4-19 and TW4-20 are pumping wells;
 Water levels for MW-33, MW-34, MW-35 (installed August 2010),
 are from the 3rd Quarter, 2010



HYDRO
 GEO
 CHEM, INC.

**2nd QUARTER, 2010 PERCHED WATER
 ELEVATION CONTOURS (FEET AMSL)
 (generated by kriging data from on-site wells)**


APPROVED	DATE	REFERENCE	FIGURE
SJS		H:/718000/cell4bjuly2010/springQ2/phwlQ2.srf	1.5-3

1.5.1.5 Perched Zone Hydrogeology Beneath and Downgradient of The Tailings Cells

Perched water, as of the 2nd Quarter, 2010, ranged from depths of approximately 16 feet in the northeastern portion of the site (adjacent to the wildlife ponds) to approximately 117 feet at the southwest margin of Cell 3 (Figure 1.5-4). The saturated thickness of the perched zone as of the 2nd Quarter, 2010 ranged from approximately 93 ft in the northeast portion of the site to less than 6 ft in the southwest portion of the site (Figure 1.5-5). The relatively large saturated thicknesses in the northeastern portion of the site are likely related to seepage from the wildlife ponds located northeast and east of the tailings cells.

Perched zone hydraulic gradients currently range from a maximum of approximately 0.05 feet per foot (ft/ft) east of Cell 2 to approximately 0.01 ft/ft downgradient of Cell 3, between Cell 3 and MW-20. The average hydraulic gradient between the downgradient edge of tailings Cell 3 and Ruin Spring was approximated by HGC to be approximately 0.012 ft/ft. HGC also estimated a hypothetical worst case average perched zone hydraulic gradient, assuming the perched water elevation to be coincident with the base of tailings Cell 3, to be approximately 0.019 ft/ft (HGC, 2009a).

HGC also estimated the average permeability of the perched zone downgradient of tailings Cell 3, based on pump/recovery test and slug test data obtained from perched zone wells located along the downgradient edge of and south of Cell 3, to be between 2.3E-05 cm/s and 4.3E-05 cm/s (HGC, 2009a).




EXPLANATION

NOTE: Depths to water for MW-34 and MW-35 (installed August 2010), are from the 3rd Quarter, 2010

108 Depth to Perched Water (feet)


Ruin Spring
Seep or Spring



HYDRO
GEO
CHEM, INC.

**2nd QUARTER, 2010 DEPTHS TO PERCHED WATER
WHITE MESA SITE**

APPROVED SJS	DATE	REFERENCE H:/718000/cell4bjuly2010/ springQ2/phdtwQ2.srf	FIGURE 1.5-4
-----------------	------	--	-----------------



EXPLANATION

NOTE: Saturated thicknesses for MW-34 and MW-35 (installed August 2010), are from the 3rd Quarter, 2010

12 Perched Zone Saturated Thickness (feet)

Ruin Spring
 Seep or Spring



HYDRO
 GEO
 CHEM, INC.

2nd QUARTER, 2010 PERCHED ZONE SATURATED THICKNESS WHITE MESA SITE

APPROVED	DATE	REFERENCE	FIGURE
SJS		H:/718000/cell4bjuly2010/springQ2/phsatQ2.srf	1.5-5


1.5.2 Seep and Spring Occurrence and Hydrogeology

In response to Part I.H, Section 10 of the GWDP, the HGC 2010 report discusses the hydrogeology of the seeps and springs at the margins of Mill, and the relationship of these seeps and springs to the hydrogeology of the site. The following paragraphs are excerpted from HGC (2010b).


All seeps and springs examined have associated cottonwood trees that suggest a relatively consistent source of water. Seeps and springs occurring at the margins of White Mesa are typically associated with sandstones of the Burro Canyon Formation, except Cottonwood Seep, associated with the lower portion of the Brushy Basin Member of the Morrison Formation. Figure 1.5-6 shows the December 2009 surveyed locations of seeps and springs and the Frog Pond. As shown on Figure 1.5-6, all springs and seeps are located within drainages, and except for Cottonwood Seep, are located at the mesa margins. Table 1.5-1 provides surveyed locations and elevations of the seeps and springs and the Frog Pond. The December, 2009 seep and spring survey data shown in Table 1.5-1 will be used in all future reporting where seep and spring locations and elevations are relevant.

**Table 1.5-1
Surveyed Locations and Elevations of Seeps and Springs and the Frog Pond
(December, 2009)**

Location	Latitude (N)	Longitude (W)	Elevation
FROG POND	37°33'03.5358"	109°29'04.9552"	5589.56
CORRAL CANYON	37°33'07.1392"	109°29'12.3907"	5623.97
ENTRANCE	37°32'01.6487"	109°29'33.7005"	5559.71
CORRAL SPRINGS	37°29'37.9192"	109°29'35.8201"	5383.35
RUIN SPRING	37°30'06.0448"	109°31'23.4300"	5380.03
COTTONWOOD	37°31'21.7002"	109°32'14.7923"	5234.33
WEST WATER	37°31'58.5020"	109°31'25.7345"	5468.23
Re-Surveyed July 2010			
RUIN SPRING	37°30'06.0456"	109°31'23.4181"	5380.01
COTTONWOOD	37°31'21.6987"	109°32'14.7927"	5234.27
WEST WATER	37°31'58.5013"	109°31'25.7357"	5468.32




● WESTWATER Seep or Spring
5468
Elevation (feet) above mean sea level



SEEPS AND SPRINGS ON USGS TOPOGRAPHIC BASE WHITE MESA					
Approved	Date	Author	Date	File Name	Figure
SJS	09/17/10	DRS	07/16/10	7180002G	1.5-6

Figure 1.5-3 shows second quarter 2010 perched water level contours and the locations of seeps and springs on an aerial photographic base. These contours are based on water levels measured in the perched groundwater monitoring wells shown in the figure, and do not include elevations of the seeps. Based on Figure 1.5-3, Corral Canyon Seep is located upgradient of the tailings cells, and Entrance Spring and Corral Springs are located cross gradient of the tailings cells. Both Entrance Spring and Corral Springs are separated from the tailings cells by a groundwater divide. Ruin Spring is located downgradient of the tailings cells, and Westwater Seep appears to be cross gradient of the tailings cells. Cottonwood Seep is neither cross gradient nor downgradient of the tailings cells because it is interpreted to receive water from a source other than the perched groundwater system hosted by the Burro Canyon Formation.

The relationship between seeps and springs and the geology of White Mesa are shown in Figure 1.5-7. The geology in Figure 1.5-7 is based on Kirby (2008) and Hintze, et al. (2000), and has been modified locally by field reconnaissance. The Burro Canyon Formation and the Dakota Sandstone are undifferentiated on the geologic map. As shown on Figure 1.5-7, all seeps and springs except Cottonwood Seep are associated with outcrops of the Burro Canyon Formation (and/or Dakota Sandstone). Some are also associated with mixed eolian and alluvial deposits stratigraphically above the Burro Canyon Formation and/or Dakota Sandstone. Ruin Spring and Westwater Seep are located at the contact between the Burro Canyon Formation and underlying Brushy Basin Member. Westwater Seep (where typically sampled) occurs within alluvium at the Burro Canyon Formation/Brushy Basin Member contact whereas Ruin Spring occurs at the contact but above the alluvium in the associated drainage. Corral Canyon Seep, Entrance Spring, and Corral Springs occur within alluvium near the contact of the alluvium with the Burro Canyon Formation, but at an elevation above the contact between the Burro Canyon Formation and Brushy Basin Member. In contrast, Cottonwood Seep is mapped within the Brushy Basin Member, approximately 1,500 feet west of the contact of the Burro Canyon Formation and Brushy Basin Member, and stratigraphically approximately 200 feet below the contact. The




EXPLANATION

- Tailings cell
- Qh Artificial cut and fill
- Qa Stream alluvium
- Qlbb Slumps and landslides, Brushy Basin
- Qea Mixed eolian and alluvial deposits
- Kdbc Dakota Sandstone and Burro Canyon Formation (undifferentiated)
- Jmbb Brushy Basin Member of the Morrison Formation



--- Contact - dashed where uncertain



**GEOLOGIC MAP
ON USGS TOPOGRAPHIC BASE
WHITE MESA**

Approved	Date	Author	Date	File Name	Figure
SJS	09/09/10	DRS	07/27/10	7180005G	1.5-7

Burro Canyon Formation does not exist at Cottonwood Seep because it has been eroded. Cottonwood Seep is interpreted to receive water from a source stratigraphically below the Burro Canyon Formation and from a hydrogeologic system other than the perched water system at the site. Westwater Seep, Corral Canyon Seep, Entrance Spring, and Corral Canyon Seep may receive water from both alluvial and bedrock (perched water) sources. Corral Springs, located immediately downgradient of a stock pond, may receive water primarily from alluvium recharged from the stock pond.

Springs occurring within alluvium deposited within drainages cutting the Burro Canyon Formation may or may not receive a contribution from perched water. Except for Ruin Spring (and “2nd Seep” immediately to the north of Cottonwood Seep), each spring and seep occurs in alluvial materials within a drainage that will supply surface water during wet periods and help to recharge any alluvial materials within the drainage as well as bedrock near the drainage. Any alluvial materials within the drainage or marginal bedrock that are recharged during precipitation events will likely, at least temporarily, yield water to the seeps.

The results of the HGC (2010b) investigation show that only Ruin Spring and Westwater Seep originate at the contact between Burro Canyon Formation and underlying Brushy Basin Member, that Ruin Spring receives its flow predominantly from perched water, and that Westwater Seep likely receives a significant portion of its flow from perched water. Corral Canyon Seep, Entrance Spring, and Corral Springs occur within alluvium in drainages cutting Burro Canyon Formation at elevations above the contact between the Burro Canyon Formation and the Brushy Basin Member. The data presented by HGC (2010b) imply that Westwater Seep is the closest discharge point west of the tailings cells and Ruin Spring is the closest discharge point south-southwest of the tailings cells. HGC (2010b) provides additional discussion regarding the relationship between the perched groundwater system and surrounding seeps, in order to satisfy requests of the GWDP, however the assumption that the seep or spring elevation is representative of the perched water elevation is likely to be correct only in cases where the feature receives most or all of its flow from the perched water, and where the supply is relatively

continuous (for example, Ruin Spring). The uncertainty that results from including seeps and springs in the contouring of perched water levels must be considered when interpreting data presented in HGC (2010b). Although there are uncertainties associated with incorporation of seep and spring elevations into maps depicting perched water elevations or maps depicting the Burro Canyon Formation/Brushy Basin Member contact elevations, future perched water elevation maps will incorporate seep and spring elevations, and future contact elevation maps will incorporate Westwater Seep and Ruin Spring elevations.

Using the same methodology presented in HGC (2009a), perched water pore velocities and travel times between the tailings cells and Ruin Spring and between the tailings cells and Westwater Seep were calculated using second Quarter, 2010 water levels. As discussed in more detail in HGC (2010b), the calculated travel times between the southeastern corner of Cell 4B to Ruin Spring ranges from approximately 3,225 to 5,850 years. The calculated travel time between the southwest corner of Cell 1 to Westwater Seep ranges from approximately 2,330 to 2,890 years.

1.5.3 Groundwater Quality

1.5.3.1 Entrada/Navajo Aquifer

The Entrada and Navajo Sandstones are prolific aquifers beneath and in the vicinity of the site. Water wells at the site are screened in both of these units, and therefore, for the purposes of this discussion, they will be treated as a single aquifer. Water in the Entrada/Navajo Aquifer is under artesian pressure, rising 800 to 900 ft above the top of the Entrada's contact with the overlying Summerville Formation; static water levels are 390 to 500 ft below ground surface.

Within the region, this aquifer is capable of yielding domestic quality water at rates of 150 to 225 gpm, and for that reason, it serves as a secondary source of water for the Mill. Additionally, two domestic water supply wells drawing from the Entrada/Navajo Aquifer are located 4.5 miles

southeast of the Mill site on the Ute Mountain Ute Reservation. Although the water quality and productivity of the Navajo/Entrada aquifer are generally good, the depth of the aquifer (>1,000 ft bls) makes access difficult.

Table 1.5-2 is a tabulation of groundwater quality of the Navajo Sandstone aquifer as reported in the FES and subsequent sampling. TDS ranges from 216 to 1,110 mg/liter in three samples taken over a period from January 27, 1977, to May 4, 1977. High iron concentrations are found in the Navajo Sandstone. Because the Navajo Sandstone aquifer is isolated from the perched groundwater zone by approximately 1,000 to 1,100 ft of materials having a low average vertical permeability, sampling of the Navajo Sandstone is not required under the Mill's previous NRC Point of Compliance monitoring program or under the GWDP. However, samples were taken at two other deep aquifer wells (#2 and #5) on site (See Figure 1.5-8 for the locations of these wells), on June 1, 1999 and June 8, 1999, respectively, and the results are included in Table 1.5-2.

**Table 1.5-2
Water Quality of the Navajo Sandstone Aquifer in the Mill Vicinity**

Parameter	FES, Test Well (G2R) (1/27/77 - 3/23/78 ¹)	Well #2 6/01/99 ¹	Well #5 6/08/99 ¹
Field Specific Conductivity (umhos/cm)	310 to 400		
Field pH	6.9 to 7.6		
Temperature (°C)	11 to 22		
Estimated Flow m/hr (gpm)	109(20)		
pH	7.9 to 8.16		
Determination, mg/liter			
TDS (@ 180°C)	216 to 1110		
Redox Potential	211 to 220		
Alkalinity (as CaCO ₃)	180 to 224		
Hardness, total (as CaCO ₃)	177 to 208		
Bicarbonate		226	214
Carbonate (as CO ₃)	0.0	<1.0	<1.0
Aluminum		0.003	0.058
Aluminum, dissolved	<0.1		
Ammonia (as N)	0.0 to 0.16	<0.05	<0.05
Antimony		<0.001	<0.001
Arsenic, total	.007 to 0.014	0.018	<0.001
Barium, total	0.0 to 0.15	0.119	0.005
Beryllium		<0.001	<0.001
Boron, total	<0.1 to 0.11		
Cadmium, total	<0.005 to 0.0	<0.001	0.018
Calcium		50.6	39.8
Calcium, dissolved	51 to 112		
Chloride	0.0 to 50	<1.0	2.3
Sodium		7.3	9.8
Sodium, dissolved	5.3 to 23		
Silver		<0.001	<0.001
Silver, dissolved	<0.002 to 0.0		
Sulfate		28.8	23.6
Sulfate, dissolved (as SO ₄)	17 to 83		
Vanadium		0.003	0.003
Vanadium, dissolved	<.002 to 0.16		
Manganese		0.011	0.032
Manganese, dissolved	0.03 to 0.020		
Chromium, total	0.02 to 0.0	0.005	0.005
Copper, total	0.005 to 0.0	0.002	0.086
Fluoride		0.18	0.18
Fluoride, dissolved	0.1 to 0.22		

¹ Zero values (0.0) are below detection limits.


**Table 1.5-2
Water Quality of the Navajo Sandstone Aquifer in the Mill Vicinity (continued)**

Parameter	FES, Test Well (G2R) (1/27/77 - 3/23/78 ¹)	Well #2 6/01/99 ¹	Well #5 6/08/99 ¹
Iron, total	0.35 to 2.1	0.43	0.20
Iron, dissolved	0.30 to 2.3		
Lead, total	0.02 - 0.0	<0.001	0.018
Magnesium		20.4	21.3
Magnesium, dissolved	15 to 21		
Mercury, total	<.00002 to 0.0	<0.001	<0.001
Molybdenum		0.001	<0.001
Molybdenum, dissolved	0.004 to 0.010		
Nickel		<0.001	0.004
Nitrate + Nitrate as N		<0.10	<0.10
Nitrate (as N)	<.05 to 0.12		
Phosphorus, total (as P)	<0.01 to 0.03		
Potassium		3.1	3.3
Potassium, dissolved	2.4 to 3.2		
Selenium		<0.001	<0.001
Selenium, dissolved	<.005 to 0.0		
Silica, dissolved (as SiO ₂)	5.8 to 12		
Strontium, total (as U)	0.5 to 0.67		
Thallium		<0.001	<0.001
Uranium, total (as U)	<.002 to 0.16	0.0007	0.0042
Uranium, dissolved (as U)	<.002 to 0.031		
Zinc		0.010	0.126
Zinc, dissolved	0.007 to 0.39		
Total Organic Carbon	1.1 to 16		
Chemical Oxygen Demand	<1 to 66		
Oil and Grease	1		
Total Suspended Solids	6 to 1940	<1.0	10.4
Turbidity		5.56	19.1
Determination (pCi/liter)			
Gross Alpha			<1.0
Gross Alpha ± precision	1.6±1.3 to 10.2±2.6		
Gross Beta			<2.0
Gross Beta ± precision	8±8 to 73±19		
Radium 226 ± precision			0.3±0.2
Radium 228			<1.0
Ra-226 ± precision	0.1±.3 to 0.6±0.4		
Th-230 ± precision	0.1±0.4 to 0.7±2.7		
Pb-210 ± precision	0.0±4.0 to 1.0±2.0		
Po-210 ± precision	0.0±0.3 to 0.0±0.8		


Source: Adapted from FES Table 2.25 with additional Mill sampling data

¹ Zero values (0.0) are below detection limits.

W:\Legacy\USA\UTAH\Mill\Reclamation\Plans\Rev_07-2011\Work01\Fig.1.5-8_GroundwaterSampling.dwg Layout1 GMoseley



- PROPERTY BOUNDARY
- RESERVATION BOUNDARY
- CANYON RIM
- G4R GROUNDWATER (WELL OR SPRING) SAMPLING LOCATION
- 5 WATER SUPPLY WELL



Denison Mines (USA) Corp		DENISON MINES	
Project: White Mesa Mill		County: San Juan	State: UT
Date: 09-11		Location:	
GROUNDWATER (WELL OR SPRING) SAMPLING STATIONS IN THE WHITE MESA VICINITY			
FIGURE 1.5-8			
Author: bm		Date: Aug 2009	Drafted By: D.Stedd

UT83-SF

1.5.3.2 Perched Groundwater Zone

Perched groundwater in the Dakota/Burro Canyon Formation is used on a limited basis to the north (upgradient) of the site because it is more easily accessible. The quality of the Burro Canyon perched water beneath and downgradient from the site is poor and extremely variable. The concentrations of TDS measured in water sampled from upgradient and downgradient wells range between approximately 600 and 5,300 mg/l. Sulfate concentrations measured in three upgradient wells varied between 670 and 1,740 mg/l (Titan, 1994a). The perched groundwater therefore is used primarily for stock watering and irrigation. The saturated thickness of the perched water zone generally increases to the north of the site. See Section 1.5.3 below for a more detailed discussion of background ground water quality in the perched aquifer.

1.5.4 Background Groundwater Quality in the Perched Aquifer

A significant amount of historic groundwater quality data had been collected by Denison and previous operators of the Mill for many wells at the facility.

At the time of original issuance of the GWDP, the Executive Secretary had not yet completed an evaluation of the historic data, particularly with regard to data quality, and quality assurance issues. The Executive Secretary also noted several groundwater quality issues that needed to be resolved prior to a determination of background groundwater quality at the site, such as a number of constituents that exceeded their respective Groundwater Quality Standard (“GWQS”) and long term trends in uranium in downgradient wells MW-14, MW-15 and MW-17, and a spatial high of uranium in those three downgradient wells.

As a result of the foregoing, the Executive Secretary required that an Existing Well Background Report be prepared to address and resolve these issues. Prior to the approval of the Existing Well Background Report, Ground Water Compliance Levels (“GWCLs”) were set in Table 2 of the GWDP as 0.25 and 0.5 time the GWQS for Class II and III groundwater respectively.

Denison submitted the Existing Well Background Report to the Executive Secretary. The Executive Secretary reviewed the Background Reports and GWCLs that reflect background groundwater quality have been set for all monitoring wells except newly installed MW-35, MW-36, and MW-37. In the case of MW-35, MW-36 and MW-37, background data are being collected for the establishment of GWCLs that reflect background groundwater quality. The Background Reports were prepared by INTERA, Inc. (“INTERA”).

As required by the GWDP, the Existing Well Background Report addressed all available historic data, which included pre-operational and operational data, for the compliance monitoring wells under the GWDP that were in existence at the date of issuance of the GWDP. The Regional Background Report focuses on all pre-operational site data and all available regional data to develop the best available set of background data that could not conceivably have been influenced by Mill operations. The New Well Background Report, which is required by Part I.H.4 of the GWDP, analyzes the data collected from the new wells (MW-3A, MW-23, MW-24, MW-25, MW-27, MW-28, MW-29, MW-30 and MW-31), which were installed in 2005, to determine background concentrations for constituents listed in the GWDP for each new well.

The purpose of the Existing Well Background Report and the New Well Background Report was to satisfy several objectives: first, in the case of the Existing Well Background Report, to perform a quality assurance evaluation and data validation of the existing and historical on-site groundwater quality data in accordance with the requirements of Part I.H.3 of the GWDP, and to develop a database consisting of historical groundwater monitoring data for “existing” wells and constituents.

Second, in the case of the New Well Background Report, to compile a database consisting of monitoring results for new wells, which were collected subsequent to issuance of the GWDP, in accordance with the Mill’s Groundwater Quality Assurance Plan (“QAP”) data quality objectives.

Third, to perform a statistical, temporal and spatial evaluation of the existing well and new well data bases to determine if there have been any impacts to groundwater from Mill activities. Since the Mill is an existing facility that has been in operation since 1980, such an analysis of historic groundwater monitoring data was required in order to ensure that the monitoring results to be used to determine background groundwater quality at the site and GWCLs have not been impacted by Mill activities.

Finally, in the event the analysis demonstrates that groundwater has not been impacted by Mill activities, to develop a GWCL for each constituent in each well.

The Regional Background Report was prepared as a supplement to the Existing Well Background Report to provide further support to the conclusion that Mill activities have not impacted groundwater.

In evaluating the historic data for the existing wells, INTERA used the following approach:

- If historic data for a constituent in a well do not demonstrate a statistically significant upward trend, then the proposed GWCL for that constituent is accepted as representative of background, regardless of whether or not the proposed GWCL exceeds the GWQS for that constituent. This is because the monitoring results for the constituent can be considered to have been consistently representative since commencement of Mill activities or installation of the well; and
- If historic data for a constituent in a monitoring well represent a statistically significant upward trend or downward trend in the case of pH, then the data is further evaluated to determine whether the trend is the result of natural causes or Mill activities. If it is concluded that the trend results from natural causes, then the GWCL proposed in the Existing Well Background Report will be appropriate.

After applying the foregoing approach, INTERA concluded that, other than some detected chloroform and related organic contamination at the Mill site, which is the subject of a separate investigation and remedial action, and that is the result of pre-Mill activities, there have been no impacts to groundwater from Mill activities.

In reaching this conclusion, INTERA noted that, even though there are a number of increasing trends in various constituents at the site, none of the trends are caused by Mill activities, for the following reasons:

- Chloride is unquestionably the best indicator parameter, and there are no significant trends in chloride in any of the wells;
- There are no noteworthy correlations between chloride and uranium in wells with increasing trends in uranium, other than in upgradient wells MW-19 and MW-18, which INTERA concluded are not related to any potential tailings seepage. INTERA noted that it is inconceivable to have an increasing trend in any other parameter caused by seepage from the Mill tailings without a corresponding increase in chloride;
- There are significant increasing trends upgradient in MW-1, MW-18 or MW-19 in uranium, sulfate, TDS, iron, selenium, thallium, ammonia and fluoride and far downgradient in MW-3 in uranium and selenium, sulfate, TDS and pH (decreasing trend). INTERA concluded that this provides very strong evidence that natural forces at the site are causing increasing trends in these constituents (decreasing in pH) in other wells and supports the conclusion that natural forces are also causing increasing trends in other constituents as well; and

- On a review of the spatial distribution of constituents, it is quite apparent that the constituents of concern are dispersed across the site and not located in any systematic manner that would suggest a tailings plume.

INTERA concluded that, after extensive analysis of the data, and given the conclusion that there have been no impacts to groundwater from Mill activities, the proposed GWCLs set out in Table 16 of the Existing Well Background Report are appropriate, and are indicative of background ground water quality. INTERA did advise, however, that proposed GWCLs for all the trending constituents should be re-evaluated upon GWDP renewal to determine if they are still appropriate at the time of renewal.

In evaluating the new well data, INTERA used the same approach in the New Well Background Report that was used in the Existing Background Report for existing well data. In addition, INTERA compared the groundwater monitoring results for the new wells to the results for the existing wells analyzed in the Existing Well Background Report and to the pre-operational and regional results analyzed in the Regional Background Report. This was particularly important for the new wells because there is no historic data for any constituents in those wells that goes back to commencement of Mill operations. A long-term trend in a constituent may not be evident from the available data for the new wells. By comparing the means for the constituents in the new wells to the results for the existing wells and regional background data, INTERA was able to determine if the concentrations of any constituents in the new wells are consistent with background at the site.

INTERA concluded that after applying the foregoing approach, there have been no impacts to groundwater in the new monitoring wells from Mill activities. INTERA concluded that the groundwater monitoring results for the new wells are consistent with the results for the existing wells analyzed in the Existing Well Background Report and for the pre-operational and regional wells, seeps and springs analyzed in the Regional Background Report. INTERA noted that there

were some detections of chloroform and related organic contamination and degradation products and nitrate and nitrite in the new wells, which are the subject of a separate investigation, but that such contamination was the result of pre-Mill activities.

As a result, given its conclusion that there have been no impacts to groundwater from Mill activities, INTERA concluded that the proposed GWCLs for new wells set out in Table 10 of the New Well Background Report are appropriate, and are indicative of background ground water quality. Again, INTERA noted that GWCLs for trending constituents should be re-evaluated upon GWDP renewal to determine if they are still appropriate at the time of renewal.

During the course of discussions with Denison staff, and further DRC review, DRC decided to supplement the analysis provided in the Background Reports by commissioning the University of Utah to perform a geochemical and isotopic groundwater study at the Mill. This resulted in the University of Utah completing a study entitled *Summary of work completed, data results, interpretations and recommendations for the July 2007 Sampling Event at the Denison Mines, USA, White Mesa Uranium Mill Near Blanding Utah*, May 2008, prepared by T. Grant Hurst and D. Kip Solomon, Department of Geophysics, University of Utah (the “University of Utah Study”). The purpose of the University of Utah Study was to verify if the increasing and elevated trace metal concentrations (such as uranium) found in the monitoring wells at the Mill were due to potential leakage from the on-site tailings cells. To investigate this potential problem, the study examined groundwater flow, chemical composition, noble gas and isotopic composition, and age of the on-site groundwater. Similar evaluations were also made on samples of the tailings wastewater and nearby surface water stored in the northern wildlife ponds at the facility. Fieldwork for the University of Utah Study was conducted July 17 - 26 of 2007. The conclusions in the University of Utah Study supported Denison’s conclusions in the Background Reports.

1.5.5 Quality of Ground Water at the Compliance Monitoring Point

All of the analytical results from groundwater sampling are reported quarterly in Groundwater Monitoring Reports, which are filed with the Executive Secretary pursuant to Part I.F.1 of the GWDP.

1.5.6 Springs and Seeps

As discussed in Section 1.5.1.4, perched groundwater at the Mill site discharges in springs and seeps along Westwater Creek Canyon and Cottonwood Canyon to the west-southwest of the site, and along Corral Canyon to the east of the site, where the Burro Canyon Formation outcrops. Water samples have been collected and analyzed from springs and seeps in the Mill vicinity as part of the baseline field investigations reported in the 1978 ER (See Table 2.6-6 in the 1978 ER).

During the period 2003-2004, Denison implemented a sampling program for seeps and springs in the vicinity of the Mill which had been sampled in 1978, prior to the Mill's construction. Four locations were designated for sampling (shown on Figure 1.5-8). These are Ruin Spring (G3R), Cottonwood Seep (G4R), west of Westwater Creek (G5R) and Corral Canyon (G1R). During the 2-year study period only two of the four locations were able to be sampled, Ruin Spring and Cottonwood Canyon. The other two locations, Corral Creek and the location west of Westwater Creek were not flowing (seeping) and samples could not be collected. With regard to the Cottonwood seep, while water was present, the volume was not sufficient to complete all determinations, and only organic analyses were conducted. The results of the organic analysis did not detect any detectable organics.

Samples at Ruin Spring were analyzed for major ions, physical properties, metals, radionuclides, volatile and semi-volatile organic compounds, herbicides and pesticides, and synthetic organic compounds. With the exception of one chloromethane detection, all organic determinations were

**Table 1.5-3
Results of Quarterly Sampling Ruin Spring (2003-2004) (continued)**

Parameter	Ruin Spring							
	Q1-03	Q2-03	Q3-03	Q4-3	Q1-04	Q2-04	Q3-04	Q4-04
Major Ions (mg/L)								
Chromium	ND	ND	ND	ND	ND	ND	ND	ND
Copper	ND	ND	0.082	ND	ND	ND	ND	ND
Iron	ND	ND	ND	ND	ND	ND	ND	ND
Lead	ND	ND	ND	ND	ND	ND	ND	ND
Manganese	ND	ND	ND	ND	ND	ND	ND	ND
Mercury	ND	ND	ND	ND	ND	ND	ND	ND
Molybdenum	ND	ND	ND	ND	ND	ND	ND	ND
Nickel	ND	ND	ND	ND	ND	ND	ND	ND
Selenium	0.013	0.012	0.012	0.012	0.012	0.012	0.012	0.012
Silver	ND	ND	ND	ND	ND	ND	ND	ND
Thallium	ND	ND	ND	ND	ND	ND	ND	ND
Uranium	0.009	0.011	0.010	0.010	0.011	0.011	0.009	0.010
Vanadium	ND	ND	ND	ND	ND	ND	ND	ND
Zinc	0.014	ND						
Radionuclides (pCi/L)								
Gross Alpha Minus Rn & U	-	-	-	-	ND	ND	1.4	ND
Lead 210	42	ND						
Radium 226	0.3	ND	0.3	ND	ND	ND	1.3	ND
Thorium 230	0.3	0.2	0.5	ND	ND	ND	0.4	ND
Thorium 232	-	-	ND	ND	ND	ND	ND	-
Thorium 228	-	-	ND	ND	ND	ND	-	-

Source: Table 3.7-9 of 2007 ER.

During 2009, the Mill implemented an annual sampling program for seeps and springs. The seeps and springs sampling program is included in the Sampling Plan for Seeps and Springs in the Vicinity of the White Mesa Uranium Mill Revision: 0, March 17, 2009 (and as submitted to UDEQ for approval, Draft Sampling Plan for Seeps and Springs, Revision 1, June 10, 2011). The annual sampling program for seeps and springs requires sampling once per year at the four seeps and springs described above, plus a fifth seep, Corrals Seep, to the extent water flow is sufficient for sampling. Samples were collected in July 2009, August and November 2010, and May and July 2011 Under the Plan only springs and seeps that had sufficient water flow for sampling. The results of the annual sampling are shown in Table 1.5-4.

1.5.7 Groundwater Appropriations Within a Five Mile Radius

Two hundred sixty one groundwater appropriation applications, within a five-mile radius of the Mill site, are on file with the Utah State Engineer's office. A summary of the applications is presented in Table 1.5-5 and shown on Figure 1.5-9. The majority of the applications are by private individuals and for wells drawing small, intermittent quantities of water, less than eight gpm, from the Burro Canyon formation. For the most part, these wells are located upgradient (north) of the Mill site. Domestic water, stock watering, and irrigation are listed as primary uses of the majority of the wells. It is important to note that no wells completed in the perched groundwater of the Burro Canyon formation exist directly downgradient of the site within the five-mile radius. Two water wells, which available data indicate are completed in the Entrada/Navajo sandstone (Clow, 1997), exist approximately 4.5 miles southeast of the site on the Ute Mountain Ute Reservation. These wells supply domestic water for the Ute Mountain Ute White Mesa Community, situated on the mesa along Highway 191 (see Figure 1.5-9). Data supplied by the Tribal Environmental Programs Office indicate that both wells are completed in the Entrada/Navajo sandstone, which is approximately 1,200 feet below the ground surface. Insufficient data are available to define the groundwater flow direction in the Entrada/Navajo sandstone in the vicinity of the Mill.

**Table 1.5-5
Wells Located Within a 5-Mile Radius of the White Mesa Uranium Mill (Denison, 2009a)**

WR Number	Diversion Type/Location	Well Log	Status	Priority	Uses	CFS	ACFT	Owner Name
09-1006	Underground		U	19771110	IS	0.500	0.000	DOROTHY PERKINS
	S30 W20 E4 02 37S 22E SL							NORTH RESERVOIR ROAD (37-1)
09-1008	Underground		T	19771110	IS	0.500	0.000	ARDEN NIELSON
	S460 E117 W4 01 37S 22E SL							P.O. BOX #378
09-1009	Underground		U	19771110	I	0.500	0.000	BAR M. K. RANCHES INCORPORATED
	N1200 E990 W4 14 37S 22E SL							P.O. BOX 576
09-1009	Underground		U	19771110	I	0.500	0.000	BAR M. K. RANCHES INCORPORATED
	0 W990 N4 14 37S 22E SL							P.O. BOX 576
09-1009	Underground		U	19771110	I	0.500	0.000	BAR M. K. RANCHES INCORPORATED
	N990 W990 S4 11 37S 22E SL							P.O. BOX 576
09-101	Underground	<u>well info</u>	P	19450702	DIS	0.004	0.000	ILO M. BROWN
	N1275 E2708 SW 01 37S 22E SL							BLANDING UT 84535
09-1013	Underground		P	19771207	DI	0.015	0.000	LEWIS A. BLACK
	N2510 E75 S4 34 36S 22E SL							P.O. BOX #403
09-1016	Underground		T	19780103	DIS	0.500	0.000	KENNETH P. MCDONALD
	N559 0 S4 34 36S 22E SL							60 NORTH 100 WEST (16-5)
09-1017	Underground		P	19780105	DI	0.015	0.000	JOHN BRAKE
	N150 E137 S4 34 36S 22E SL							P.O. BOX #173
09-1018	Underground		T	19780104	DIS	0.015	0.000	MARGARET E. THOMPSON

	37S 22E SL							
<u>09-1124</u>	Underground		P	19860818	IS	0.015	0.000	JOHN BRAKE
	N310 E280 S4 34 36S 22E SL							1300 S. 300 W. (60-9)
<u>09-1128</u>	Underground		P	19800310	DIS	0.015	0.000	JAMES A. LAWS
	S1610 E560 N4 02 37S 22E SL							P.O. BOX 1210
<u>09-1144</u>	Underground		P	19800630	DIS	0.015	0.000	LEE R. & MARYLYNN SMITH
	N1272 E149 S4 34 36S 22E SL							P.O. BOX 1169
<u>09-1145</u>	Underground		P	19800630	DIS	0.015	0.000	LEE R. & MARYLYNN SMITH
	N1272 E149 S4 34 36S 22E SL							P.O. BOX 1169
<u>09-1146</u>	Underground		P	19800630	DIS	0.015	0.000	LEE R. & MARYLYNN SMITH
	N1272 E149 S4 34 36S 22E SL							P.O. BOX 1169
<u>09-1147</u>	Underground		P	19800630	DIS	0.015	0.000	LEE R. & MARYLYNN SMITH
	N1272 E149 S4 34 36S 22E SL							P.O. BOX 1169
<u>09-1153</u>	Underground		P	19800825	IS	0.015	0.000	PARLEY V. & REVA V. REDD
	N1350 E1150 SW 34 36S 22E SL							PARLEY AND REVA REDD FAMILY LIVING TRUST (1981)
<u>09-1156</u>	Underground	<u>well info</u>	P	19800909	DIS	0.015	0.000	AL B. CLARKE AND SHIRLEY W. CLARKE
	N2580 W921 S4 01 37S 22E SL							1555 BROWN'S CANYON ROAD
<u>09-1157</u>	Underground		T	19800912	O	0.700	511.540	IUC WHITE MESA LLC
	N1200 E280 SW 21 37S 22E SL							1050 17TH STREET, SUITE 950
<u>09-1157</u>	Underground		T	19800912	O	0.700	511.540	IUC WHITE MESA LLC

Denison Mines (USA) Corp.
White Mesa Mill Reclamation Plan

	N200 W200 SE 28 37S 22E SL							1050 17TH STREET, SUITE 950
<u>09-1157</u>	Underground		T	19800912	O	0.700	511.540	IUC WHITE MESA LLC
	N1200 W200 SE 33 37S 22E SL							1050 17TH STREET, SUITE 950
<u>09-1157</u>	Underground		T	19800912	O	0.700	511.540	IUC WHITE MESA LLC
	N1200 0 SE 21 37S 22E SL							1050 17TH STREET, SUITE 950
<u>09-116</u>	Underground		P	19460903	S	0.005	0.000	TODD MILTON HURST
	S150 W925 E4 35 36S 22E SL							747 NORTH 300 WEST (34-2)
<u>09-1167</u>	Underground		P	19801209	DIS	0.012	0.000	LYNDA HARRELSON
	S1430 W270 N4 02 37S 22E SL							133 SOUTH 100 WEST A
<u>09-1173</u>	Underground		T	19810202		0.000	1.000	CARBONIT EXPLORATION INCORPORATED
	S1550 W1300 NE 32 38S 22E SL							C/O K & A/HELTON
<u>09-1176</u>	Underground		P	19800912	O	0.600	0.000	IUC WHITE MESA LLC.
	N1400 W3000 SE 28 37S 22E SL							1050 17TH STREET, SUITE 950
<u>09-1176</u>	Underground	<u>well info</u>	P	19800912	O	0.600	0.000	IUC WHITE MESA LLC.
	N1300 W2400 SE 28 37S 22E SL							1050 17TH STREET, SUITE 950
<u>09-1176</u>	Underground	<u>well info</u>	P	19800912	O	0.600	0.000	IUC WHITE MESA LLC.
	N2100 W2200 SE 28 37S 22E SL							1050 17TH STREET, SUITE 950
<u>09-1176</u>	Underground		P	19800912	O	0.600	0.000	IUC WHITE MESA LLC.
	N1290 W170 SE 33 37S 22E SL							1050 17TH STREET, SUITE 950
<u>09-1176</u>	Underground		P	19800912	O	0.600	0.000	IUC WHITE MESA LLC.

	37S 22E SL							WEST (68-2)
<u>09-1238</u>	Underground	<u>well info</u>	P	19811223	DI	0.015	0.000	ALYCE M. RENTZ
	N1300 E50 S4 01 37S 22E SL							BROWN CANYON ROAD 103-8
<u>09-1248</u>	Underground		P	19820209	D	0.015	0.000	REED HURST
	S1470 E125 N4 02 37S 22E SL							354 S. 300 W. #56
<u>09-1262</u>	Underground	<u>well info</u>	P	19820811	DI	0.015	0.000	GERALD B. HEINER
	N132 E2244 W4 02 37S 22E SL							P.O. BOX 1127
<u>09-1287</u>	Underground	<u>well info</u>	P	19830207	DIS	0.015	0.000	ALVIN H. KAER
	N476 E2256 W4 02 37S 22E SL							P.O. BOX 1133
<u>09-1290</u>	Underground		P	19830323	DI	0.015	0.000	CARLA L. AND MARK E. ENDRES
	S932 W363 N4 03 37S 22E SL							444 WEST 1600 SOUTH
<u>09-1346</u>	Underground		P	19840305	S	0.015	0.000	J. GLEN & EVA L. SHUMWAY
	S1321 W1980 E4 15 37S 22E SL							578 SOUTH 200 WEST 61-1
<u>09-138</u>	Underground		P	19500525	S	0.015	0.000	LORRAINE AND VERL J. ROSE
	S1326 W1205 E4 02 37S 22E SL							1166 SOUTH 100 EAST
<u>09-1396</u>	Underground		T	19841026	O	0.000	3.000	WINTERSHALL OIL & GAS CORPORATION
	S2722 E10 NW 01 37S 22E SL							1020 15TH STREET, SUITE 122E
<u>09-1402</u>	Underground		T	19841113	O	0.000	6.000	C/O PERMITCO WINTERSHALL OIL & GAS CORPORATION
	S2722 E10 NW 01 37S 22E SL							1020 15TH STREET, SUITE 22E
<u>09-141</u>	Underground	<u>well info</u>	P	19500918	S	0.015	0.000	WILLARD M. GUYMON

	N1287 W448 SE 10 37S 22E SL							BLANDING UT 84511
<u>09-1457</u>	Underground		T	19860103	O	0.000	3.000	WINTERSHALL OIL & GAS CORPORATION C/O PERMITCO
	S2722 E10 NW 12 37S 22E SL							1020 15TH STREET SUITE 22E
<u>09-1468</u>	Underground		A	19860414	DIS	0.015	0.000	RONALD D. & CATHERINE A. KIRK
	S570 E1458 W4 01 37S 22E SL							BROWN CANYON ROAD (103-9)
<u>09-1477</u>	Underground	<u>well info</u>	P	19931108	DI	0.015	0.000	JOANN WATKINS
	N750 W2180 SE 01 37S 22E SL							EAST BROWN CANYON ROAD 103- 14
<u>09-1535</u>	Underground		T	19871013	O	0.000	3.000	QUINTANA PETROLEUM CORPORATION
	S2722 E10 SW 01 37S 22E SL							ATTN: LISA GREEN, AGENT FOR QUINTANA PETROLEUM
<u>09-1548</u>	Underground		T	19871202	O	0.000	8.000	YATES PETROLEUM CORPORATION
	N2558 E10 SW 01 37S 22E SL							C/O PERMITS WEST INC.
<u>09-1664</u>	Underground		P	19890913	DIS	0.015	0.000	F. GREG STRINGHAM
	N340 W305 SE 34 36S 22E SL							1244 SOUTH 100 EAST (80-1)
<u>09-1673</u>	Underground	<u>well info</u>	A	19940524	IS	0.015	0.000	HENRY CLYDE WATKINS
	S3000 E200 NW 01 37S 22E SL							1000 BROWNS CANYON 103-14
<u>09-1686</u>	Underground		T	19900402	O	0.000	8.000	GENERAL ATLANTIC RESOURCES INC.
	S2722 E10 NW 01 37S 22E SL							C/O PERMITS WEST INC. ATTN: BRIAN

								WOOD
<u>09-1709</u>	Underground		P	19900504	I	0.000	1.120	GORDON REDD MANAGEMENT INC.
	N2505 E1629 S4 34 36S 22E SL							82 SOUTH MAIN STREET
<u>09-1734</u>	Underground		T	19901010	O	0.000	2.000	CELSIUS ENERGY COMPANY
	S2722 E10 NW 01 37S 22E SL							C/O PERMITS WEST INC.
<u>09-1785</u>	Underground		A	19911031	DIS	0.100	0.000	BERTHA SNYDER
	S200 E800 W4 01 37S 22E SL							409 EAST 1000 NORTH
<u>09-1794</u>	Underground	<u>well info</u>	T	19920313	DI	0.100	0.000	JAMES D. REDD
	N1115 E2320 SW 02 37S 22E SL							SANTA FE HEIGHTS 104-9
<u>09-1801</u>	Underground		T	19920714	O	0.000	9.000	TEXAS INC. AMPOLEX
	S2722 E10 NW 01 37S 22E SL							C/O BILLY HASS
<u>09-1822</u>	Underground	<u>well info</u>	A	19930315	IS	0.000	4.730	DENNIS F. AND EDITH G. ANDERSON
	S250 W250 NE 03 37S 22E SL							1307 SOUTH MAIN
<u>09-1843</u>	Underground	<u>well info</u>	P	19940323	DIS	0.000	1.560	JEROLD PERKINS
	S201 E1530 NW 03 37S 22E SL							1092 EAST BROWNS CANYON ROAD (103-18)
<u>09-1844</u>	Underground	<u>well info</u>	T	19940331	IS	0.000	3.760	PRESTON KIRK REDD
	N2125 E846 SW 02 37S 22E SL							292 WEST CENTER STREET BOX 67-7
<u>09-1845</u>	Underground		T	19940331	IS	0.000	3.760	PRESTON KIRK REDD
	N1115 E1220 SW 02 37S 22E SL							292 WEST CENTER STREET BOX 67-7
<u>09-1848</u>	Underground	<u>well info</u>	P	19940411	S	0.000	0.750	M. DALE SLADE

	N35 E40 SW 04 37S 23E SL							332 WEST 400 SOUTH (64-5)
<u>09-1862</u>	Underground		T	19950118	O	0.500	0.000	KOKEPELLI BOTTLING
	N200 W2250 E4 36 36S 22E SL							36 EAST 500 SOUTH (77-15)
<u>09-1875</u>	Underground		T	19950417	DIS	0.000	4.730	STAN & SANDRA PERKINS
	N2105 W235 SE 34 36S 22E SL							686 NORTH DAYBREAK DRIVE
<u>09-1878</u>	Underground		P	19950505	S	0.000	1.680	BRUCE J. LYMAN
	S92 W2566 E4 33 36S 23E SL							SHIRTAIL JUNCTION (105-7)
<u>09-1880</u>	Underground	<u>well info</u>	P	19950620	DIS	0.000	4.730	MITCHELL H. & JANA L. BAILEY
	S945 E1095 NW 15 37S 22E SL							SHIRTAIL CORNER 105-14
<u>09-1886</u>	Underground	<u>well info</u>	A	19950807	DIS	0.000	1.730	PAUL A. OR SHARON BROWN
	N868 W1260 SE 01 37S 22E SL							BROWN'S CANYON ROAD (103-16)
<u>09-1912</u>	Underground	<u>well info</u>	T	19960521	DI	0.000	4.730	THOMAS A. MAY
	N500 W545 S4 02 37S 22E SL							2202 SOUTH CINCO CEDROS ROAD (104- 8)
<u>09-193</u>	Underground		P	19560316	S	0.015	0.000	ALMA U. JONES
	S50 W1420 E4 33 37S 22E SL							BLANDING UT 84511
<u>09-1934</u>	Underground	<u>well info</u>	P	19960830	DIS	0.000	1.882	RONALD F. & MERLE MCDONALD
	N1816 W651 S4 01 37S 22E SL							1500 BROWN'S CANYON ROAD (103-2)
<u>09-1947</u>	Underground	<u>well info</u>	P	19961126	DIS	0.000	3.110	THOMAS A. MAY
	N174 W901 S4 02 37S 22E SL							2202 SOUTH CINCO CEDROS ROAD (104- 8)
<u>09-1953</u>	Underground		T	19970430	DIS	0.000	4.730	JERRY HOLLIDAY

Denison Mines (USA) Corp.
White Mesa Mill Reclamation Plan

	S2393 W2494 NE 02 37S 22E SL							P.O. BOX 502
<u>09-1955</u>	Underground	<u>well info</u>	T	19970527	DI	0.000	4.730	JIM & MARY BOURNE
	N3055 W1059 SE 01 37S 22E SL							468 NORTH 500 WEST
<u>09-1959</u>	Underground		T	19970729	I	0.000	4.730	LLOYD D. & CLARABELLA ELLEN
	N2339 E191 SW 35 36S 22E SL							859 SOUTH 100 EAST (82-9)
<u>09-1964</u>	Underground	<u>well info</u>	P	20030512	DIS	0.000	0.990	BEN J. BLACK
	N516 E625 W4 02 37S 22E SL							83 WEST 300 SOUTH 75-5
<u>09-1968</u>	Underground	<u>well info</u>	A	19970915	DIS	0.000	4.730	BRUCE & PEGGY ROYER
	N600 W880 SE 01 37S 22E SL							PO BOX 1145
<u>09-197</u>	Underground	<u>well info</u>	P	19560512	DS	2.000	0.000	UTE MOUNTAIN UTE TRIBE
	N1005 W207 S4 23 38S 22E SL							TOWAOC CO 81334
<u>09-1972</u>	Underground		T	19971023	DIS	0.000	4.730	DALE & MARTHA LYMAN
	N1095 W725 E4 21 37S 22E SL							P.O. BOX 729
<u>09-1979</u>	Underground	<u>well info</u>	P	19980217	DIS	0.000	3.774	PAUL REDD & LISA MACDONALD
	N110 W2339 W4 34 36S 22E SL							466 WEST 800 SOUTH 60-15
<u>09-1982</u>	Underground		T	19980320	DIS	0.000	4.730	JEANNINE B. ERICKSEN
	N1420 W1560 SE 01 37S 22E SL							771 SOUTH 700 EAST
<u>09-1983</u>	Underground	<u>well info</u>	P	19980413	DI	0.000	1.894	DON C. & REBECCA P. LARSON
	S251 E933 W4 35 36S 22E SL							301 E. EAGLE VIEW LN. 95-19
<u>09-1990</u>	Underground	<u>well info</u>	P	20040304	DI	0.000	4.450	DUSTIN AND BEVERLY

Denison Mines (USA) Corp.
White Mesa Mill Reclamation Plan

	36S 22E SL							STREET
<u>09-2065</u>	Underground		T	20011221	DIS	0.000	4.730	JAMES G. AND STACY MONTELLA
	S100 W650 E4 02 37S 22E SL							978 EAST BROWN CANYON ROAD (103-19)
<u>09-2068</u>	Underground	<u>well info</u>	P	20070502	DIS	0.000	2.904	BRUCE E. STEVENS
	S80 W710 NE 02 37S 22E SL							1314 SOUTH 1100 EAST 102-16
<u>09-2069</u>	Underground	<u>well info</u>	A	20070912	DIS	0.000	1.506	JOE (JR) AND SHIRLEY A. GRISHAM
	S1110 W277 E4 02 37S 22E SL							2044 SOUTH PERKINS LANE 103- 20
<u>09-2070</u>	Underground	<u>well info</u>	P	20020409	DI	0.000	1.450	RICHARD I. AND MARIEANN WATKINS
	S162 W4489 E4 01 37S 22E SL							1302 BROWN CANYON ROAD 103- 24
<u>09-2074</u>	Underground		T	20020521	S	0.000	4.730	BRUCE J. LYMAN
	N1020 W1220 SE 15 37S 22E SL							SHIRTAIL JUNCTION 105-7
<u>09-2075</u>	Underground		T	20020603	OX	0.000	16.140	USA CORPORATION INTERNATIONAL URANIUM
	S769 W1812 NE 33 37S 22E SL							P.O. BOX 809
<u>09-2075</u>	Underground		T	20020603	OX	0.000	16.140	USA CORPORATION INTERNATIONAL URANIUM
	S1039 W1600 NE 33 37S 22E SL							P.O. BOX 809
<u>09-2075</u>	Underground		T	20020603	OX	0.000	16.140	USA CORPORATION INTERNATIONAL URANIUM
	S1156 W1591 NE 33 37S 22E SL							P.O. BOX 809
<u>09-2075</u>	Underground		T	20020603	OX	0.000	16.140	USA CORPORATION

								INTERNATIONAL URANIUM
	S1023 W1576 NE 33 37S 22E SL							P.O. BOX 809
<u>09-2075</u>	Underground		T	20020603	OX	0.000	16.140	USA CORPORATION INTERNATIONAL URANIUM
	S903 W1563 NE 33 37S 22E SL							P.O. BOX 809
<u>09-2075</u>	Underground		T	20020603	OX	0.000	16.140	USA CORPORATION INTERNATIONAL URANIUM
	S1434 W1537 NE 33 37S 22E SL							P.O. BOX 809
<u>09-2087</u>	Underground	well info	A	20020815	DIS	0.000	3.010	BEN J. BLACK
	N516 E631 W4 02 37S 22E SL							303 EAST BROWNS CANYON RD.
<u>09-2094</u>	Underground		P	20020924	DI	0.000	0.838	SUMNER H. PATTERSON
	N125 W907 E4 34 36S 22E SL							788 SOUTH MAIN STREET 78-11
<u>09-2097</u>	Underground		P	20021004	IS	0.000	4.730	NORMAN F. NIELSON
	S581 E53 W4 01 37S 22E SL							63 NORTH 100 WEST (17-2)
<u>09-2100</u>	Underground		T	20021118	OX	0.000	32.280	INTERNATIONAL URANIUM USA CORPORATION
	N36 W2249 SE 28 37S 22E SL							P.O. BOX 809
<u>09-2100</u>	Underground		T	20021118	OX	0.000	32.280	INTERNATIONAL URANIUM USA CORPORATION
	N139 W2146 SE 28 37S 22E SL							P.O. BOX 809
<u>09-2100</u>	Underground		T	20021118	OX	0.000	32.280	INTERNATIONAL URANIUM USA CORPORATION
	N138 W1890 SE 28 37S 22E SL							P.O. BOX 809

<u>09-2100</u>	Underground		T	20021118	OX	0.000	32.280	INTERNATIONAL URANIUM USA CORPORATION
	N148 W1696 SE 28 37S 22E SL							P.O. BOX 809
<u>09-2100</u>	Underground		T	20021118	OX	0.000	32.280	INTERNATIONAL URANIUM USA CORPORATION
	S6 W1614 NE 33 37S 22E SL							P.O. BOX 809
<u>09-2100</u>	Underground		T	20021118	OX	0.000	32.280	INTERNATIONAL URANIUM USA CORPORATION
	S178 W1598 NE 33 37S 22E SL							P.O. BOX 809
<u>09-211</u>	Underground	<u>well info</u>	P	19570129	S	0.015	0.000	USA BUREAU OF LAND MANAGEMENT
	N3279 E3641 SW 29 38S 23E SL							2370 SOUTH 2300 WEST
<u>09-2125</u>	Underground	<u>well info</u>	P	20030715	M	0.000	4.730	SAN JUAN COUNTY
	N1247 W433 SE 34 36S 22E SL							P.O. BOX 9
<u>09-2139</u>	Underground		T	20040126	DIS	0.000	4.730	MITCHELL H. BAILEY
	N95 E1830 SW 10 37S 22E SL							105-14 SHIRTAIL CORNER
<u>09-2140</u>	Underground	<u>well info</u>	T	20040217	DIS	0.000	4.730	TONY F. GUYMON
	N2565 E2680 SW 02 37S 22E SL							BROWN CANYON ROAD 104-7
<u>09-2152</u>	Underground		A	20041115	DIS	0.000	4.730	JAMES R. AND WENDY L. BUNTING
	S2520 E420 NW 36 36S 22E SL							905 EAST HARRIS LANE
<u>09-2162</u>	Underground		A	20050407	DIS	0.000	4.730	LEE R. & DENIECE A. MEYERS
	N1095 W725 E4 21 37S 22E SL							1051 WEST 4350 SOUTH 105-10
<u>09-2170</u>	Underground	<u>well</u>	P	20060103	DI	0.000	4.730	DANIEL AND

		<u>info</u>						MARILYN KARTCHNER
	S1285 E573 NW 06 37S 23E SL							1551 S. BOOTS & SPURS LANE
<u>09-2182</u>	Underground		A	20060814	DIS	0.000	4.730	GLENN & GLORIA PATTERSON
	N1390 E90 S4 02 37S 22E SL							P.O BOX 972
<u>09-2185</u>	Underground		T	20060908	DI	0.000	4.730	MARTHA A. LYMAN
	S100 W990 NE 21 37S 22E SL							90 WEST 100 SOUTH
<u>09-2187</u>	Underground	<u>well info</u>	A	20060920	DIS	0.000	4.730	RANDALL & MARILYN PEMBERTON
	N784 E278 W4 01 37S 22E SL							72 SOUTH 100 WEST 70-1
<u>09-226</u>	Underground	<u>well info</u>	P	19580110	D	0.015	0.000	WAUKESHA OF UTAH
	S1639 E1689 N4 03 37S 22E SL							BOX #714
<u>09-2263</u>	Underground		A	20070124	DIS	0.000	4.730	STAN & SANDRA PERKINS
	N2010 W235 SE 34 36S 22E SL							686 NORTH DAYBREAK
<u>09-2267</u>	Underground	<u>well info</u>	A	20070323	D	0.000	0.450	JEFF & SHERI MONTELLA
	S516 E2 E4 02 37S 22E SL							P.O. BOX 285
<u>09-2270</u>	Underground	<u>well info</u>	A	20070530	DIS	0.000	2.562	CRAIG B. AND JOANNE T BARLOW
	N2383 E1328 SW 35 36S 22E SL							P.O. BOX 625
<u>09-2276</u>	Underground	<u>well info</u>	A	20070829	DIS	0.000	2.478	GLENN T. AND GLORIA J. PATTERSON
	N348 W1021 E4 01 37S 22E SL							1981 KOKOPELLI LANE
<u>09-2286</u>	Underground		A	20071218	DIS	0.000	4.730	MITCHELL H. & JANA L. BAILEY
	N834 E1230 S4 16 37S 22E SL							210 N. SHIRTTAIL WAY

Denison Mines (USA) Corp.
White Mesa Mill Reclamation Plan

<u>09-2290</u>	Underground		A	20080221	DIS	0.000	4.730	LOIS SHUMWAY
	S284 W423 NE 03 37S 22E SL							PO BOX 447
<u>09-2296</u>	Underground		A	20080505	DIS	0.000	4.730	WENDELL & ELIZA FRY
	S1255 W814 E4 02 37S 22E SL							P.O. BOX 555
<u>09-2297</u>	Underground		A	20080516	DIS	0.000	4.728	NELLADEE AND JACK L. STREET
	S100 W650 E4 02 37S 22E SL							1004 EAST BROWNS CANYON ROAD
<u>09-2306</u>	Underground	<u>well info</u>	A	20081006	DS	0.000	0.534	ANDY & ALICIA BLACK
	S400 E738 W4 36 36S 22E SL							1312 HARRIS LANE
<u>09-2309</u>	Underground		A	20081103	DIS	0.000	4.470	KEVIN BLACK
	S955 E192 NW 01 37S 22E SL							41 EAST 300 SOUTH
<u>09-2311</u>	Underground		A	20081110	DIS	0.000	4.730	MARK & TERRI LYMAN
	S50 W990 NE 21 37S 22E SL							PO BOX 106
<u>09-2312</u>	Underground		A	20081230	DIS	0.000	4.730	JACK & NELLADEE STREET
	S72 W662 E4 02 37S 22E SL							1004 EAST BROWNS CANYON RD
<u>09-2316</u>	Underground		A	20090209	DIS	0.000	4.590	FRANKLIN P. HAWKINS
	S1095 W725 NE 21 37S 22E SL							4238 SOUTH 1000 WEST
<u>09-255</u>	Underground		P	19660304	S	0.015	0.000	USA BUREAU OF LAND MANAGEMENT
	S688 E128 W4 14 38S 21E SL							2370 SOUTH 2300 WEST
<u>09-275</u>	Underground		P	19600804	S	0.001	0.000	UTAH SCHOOL AND INSTITUTIONAL TRUST LANDS ADMIN.
	S943 W546 N4 32 38S 23E SL							675 EAST 500 SOUTH, 5TH FLOOR

<u>09-348</u>	Underground		P	19640513	S	0.011	0.000	KELLY G. & TERRI J. LAWS
	N2265 W900 S4 33 36S 23E SL							295 W. 400 N.
<u>09-365</u>	Underground		P	19641013	S	0.015	0.000	EUGENE GUYMON
	N747 W932 E4 02 37S 22E SL							P.O. BOX 117
<u>09-385</u>	Underground		T	19650715	I	0.500	0.000	HARRIS SHUMWAY
	S1320 E395 NW 33 37S 22E SL							BOX 172
<u>09-423</u>	Underground		P	19350522	DIS	0.022	5.580	FRED S. LYMAN
	N340 W750 S4 10 37S 22E SL							BLANDING UT 84511
<u>09-466</u>	Underground		P	19680308	S	0.007	0.000	LORENZO HAWKINS
	S152 W76 NE 32 37S 22E SL							P.O. BOX 182
<u>09-473</u>	Underground		P	19680927	D	0.015	0.000	USA UTAH LAUNCH COMPLEX WHITE SANDS MISSLE RANGE
	S608 W327 NE 27 37S 22E SL							C/O A. MURAY MAUGHN, SITE DIRECTOR
<u>09-474</u>	Underground		T	19690303		0.015	0.000	HARVEY J. KARTCHNER
	S3700 W2000 N4 35 36S 22E SL							BOX 232
<u>09-496</u>	Underground		T	19700325		0.100	0.000	MONTICELLO DISTRICT USA BUREAU OF LAND MANAGEMENT
	N1098 E1642 SW 11 38S 21E SL							P.O. BOX 1327
<u>09-504</u>	Underground		P	19700722	S	0.010	0.000	USA BUREAU OF LAND MANAGEMENT
	S3219 E3255 NW 08 37S 22E SL							2370 SOUTH 2300 WEST
<u>09-510</u>	Underground		T	19710318		2.000	0.000	WILLIAM B. REDD
	N200 E2750 SW 03 37S 21E SL							BOX 531

09-510	Underground		T	19710318		2.000	0.000	WILLIAM B. REDD
	N0 E3000 SW 03 37S 21E SL							BOX 531
09-528	Underground		P	19720315	DIS	0.015	0.000	J. PARLEY LAWS
	N3110 W1790 SE 02 37S 22E SL							P.O. BOX #315
09-541	Underground		T	19720731		0.100	0.000	BLANDING VACATIONS INCORPORATED
	S1550 E2500 NW 15 37S 22E SL							PO BOX 66
09-544	Underground		T	19720922		0.015	0.000	ROBERT E. HOSLER
	N1678 W953 SE 03 37S 22E SL							PO BOX 421
09-546	Underground		P	19721012	DI	0.030	0.000	WILLIAM W. AND ROSELINE M. SIMPSON
	S3273 E1687 N4 03 37S 22E SL							P.O. BOX #263
09-573	Underground		P	19730927	DIS	0.084	0.000	ERWIN OLIVER
	N1610 E1260 SW 35 36S 22E SL							P.O. BOX #285
09-581	Underground		P	19740502	I	0.300	0.000	DELORES HURST
	S70 W900 E4 35 36S 22E SL							516 WEST 100 SOUTH (50-5)
09-581	Underground		P	19740502	I	0.300	0.000	DELORES HURST
	S750 W430 E4 35 36S 22E SL							516 WEST 100 SOUTH (50-5)
09-581	Underground		P	19740502	I	0.300	0.000	DELORES HURST
	S20 W325 E4 35 36S 22E SL							516 WEST 100 SOUTH (50-5)
09-582	Underground		P	19740502	I	0.750	0.000	TODD MILTON HURST
	S75 W1185 E4 35 36S 22E SL							747 NORTH 300 WEST (34-2)
09-582	Underground		P	19740502	I	0.750	0.000	TRAVIS EVAN PEHRSON
	S60 W860 E4 35 36S 22E SL							747 NORTH 300 WEST (34-2)
09-584	Underground	well	P	19740503	O	0.015	0.000	LEONARD R. HOWE

		<u>info</u>						
	S619 W135 N4 03 37S 22E SL							P.O. BOX #1025
<u>09-597</u>	Underground		P	19740829	S	0.015	0.000	DOROTHY PERKINS
	S590 W810 E4 21 37S 22E SL							NORTH RESERVOIR ROAD (37-1)
<u>09-606</u>	Underground		T	19741127	DIS	0.100	0.000	JESS M. GROVER
	N2040 W350 S4 01 37S 22E SL							P.O. BOX #564
<u>09-618</u>	Underground	<u>well info</u>	P	19750421	DIS	0.010	0.000	MARK EUGENE SHUMWAY
	S1140 W220 N4 03 37S 22E SL							444 WEST 1600 SOUTH (79-2)
<u>09-619</u>	Underground		T	19750619	DIS	0.015	0.000	BOYD LAWS
	S2400 W210 N4 22 37S 22E SL							P.O. BOX #317
<u>09-631</u>	Underground		P	19751120	DIS	0.100	0.000	EUGENE GUYMON
	N747 W932 E4 02 37S 22E SL							P.O. BOX #117
<u>09-631</u>	Underground		P	19751120	DIS	0.100	0.000	EUGENE GUYMON
	N400 W350 E4 02 37S 22E SL							P.O. BOX #117
<u>09-631</u>	Underground		P	19751120	DIS	0.100	0.000	EUGENE GUYMON
	N275 W150 E4 02 37S 22E SL							P.O. BOX #117
<u>09-634</u>	Underground	<u>well info</u>	P	19751129	S	0.015	0.000	LORRAINE ROSE AND VERL J. ROSE
	S1326 W1205 E4 02 37S 22E SL							1166 SOUTH 100 EAST
<u>09-637</u>	Underground	<u>well info</u>	P	19760103	IS	0.200	0.000	HENRY CLYDE WATKINS
	S2722 E10 NW 01 37S 22E SL							EAST BROWN CANYON ROAD 103- 14
<u>09-663</u>	Underground		T	19760623	DIS	0.015	0.000	GRANT L. BAYLES
	N1155 E870 SW 22 37S 22E SL							P.O. BOX #275
<u>09-666</u>	Underground		T	19761021	O	1.000	0.000	HEMI WEST PROPERTIES

	N3200 W2600 SE 23 37S 21E SL							1325 SOUTH 800 EAST
09-666	Underground		T	19761021	O	1.000	0.000	HEMI WEST PROPERTIES
	N3000 W1300 SE 23 37S 21E SL							1325 SOUTH 800 EAST
09-666	Underground		T	19761021	O	1.000	0.000	HEMI WEST PROPERTIES
	N2100 W200 SE 23 37S 21E SL							1325 SOUTH 800 EAST
09-666	Underground		T	19761021	O	1.000	0.000	HEMI WEST PROPERTIES
	N2100 E1200 SW 24 37S 21E SL							1325 SOUTH 800 EAST
09-672	Underground	<u>well info</u>	P	19761210	OS	0.015	0.000	ENERGY FUELS LIMITED
	N640 W1650 SE 28 37S 22E SL							1200 17TH STREET, ONE TABOR CENTER SUITE 2500
09-689	Underground	<u>well info</u>	P	19770307	MOS	1.110	803.600	IUC WHITE MESA LLC
	N1400 W3000 SE 28 37S 22E SL							1050 17TH STREET SUITE 950
09-689	Underground	<u>well info</u>	P	19770307	MOS	1.110	803.600	IUC WHITE MESA LLC
	N1300 W2400 SE 28 37S 22E SL							1050 17TH STREET SUITE 950
09-689	Underground	<u>well info</u>	P	19770307	MOS	1.110	803.600	ENERGY FUELS LTD.
	N2100 W2200 SE 28 37S 22E SL							1200 17TH STREET, ONE TABOR CENTER SUITE 2500
09-689	Underground		P	19770307	MOS	1.110	803.600	IUC WHITE MESA LLC
	N1000 E650 SW 22 37S 22E SL							1050 17TH STREET SUITE 950
09-713	Underground	<u>well info</u>	P	19770407	DIS	0.015	0.000	DEAN W. GUYMON
	S360 W350 NE 03 37S 22E SL							P.O. BOX #194
09-740	Underground	<u>well</u>	P	19770419	I	0.015	0.000	WINSTON AND

		<u>info</u>						KATHRYN J. HURST BAYLISS
	N320 W1240 E4 27 38S 22E SL							259 NORTH 100 WEST
<u>09-743</u>	Underground		T	19851016	DI	0.015	0.000	O. FROST BLACK
	N150 E50 SW 36 36S 22E SL							208 SOUTH 200 WEST (65-5)
<u>09-771</u>	Underground		P	19770427	I	0.015	0.000	ELIZABETH ANN HURST PHILLIPS
	N670 E950 S4 34 36S 22E SL							P.O. BOX #389
<u>09-778</u>	Underground		T	19770504	O	0.015	0.000	REX D. ANDERSON
	S310 E1240 W4 15 37S 22E SL							P.O. BOX 569
<u>09-792</u>	Underground	<u>well info</u>	P	19770509	DIS	0.015	0.000	HENRY CLYDE WATKINS
	S80 E220 W4 01 37S 22E SL							1000 EAST BROWNS CANYON ROAD 103- 14
<u>09-805</u>	Underground		T	19770510	DIS	0.015	0.000	BAR M. K. RANCHES INCORPORATED
	N1540 E1340 W4 03 37S 22E SL							BOX 576
<u>09-806</u>	Underground		T	19770510	DIS	0.015	0.000	BAR M. K. RANCHES INCORPORATED
	N1200 E990 W4 14 37S 22E SL							BOX 576
<u>09-808</u>	Underground		T	19770510	DIS	0.015	0.000	BAR M. K. RANCHES INCORPORATED
	N990 W990 S4 11 37S 22E SL							BOX 576
<u>09-826</u>	Underground		U	19770523	DIS	0.500	0.000	CLISBEE LYMAN
	N665 W1015 S4 10 37S 22E SL							435 SOUTH 200 WEST 63-2
<u>09-826</u>	Underground		U	19770523	DIS	0.500	0.000	CLISBEE LYMAN
	N70 W790 S4 10 37S 22E SL							435 SOUTH 200 WEST 63-2
<u>09-826</u>	Underground		U	19770523	DIS	0.500	0.000	CLISBEE LYMAN
	N340 W750 S4 10 37S 22E SL							435 SOUTH 200 WEST 63-2

Denison Mines (USA) Corp.
White Mesa Mill Reclamation Plan

09-826	Underground		U	19770523	DIS	0.500	0.000	CLISBEE LYMAN
	N315 W450 S4 10 37S 22E SL							435 SOUTH 200 WEST 63-2
09-831	Underground		T	19800516	DIS	0.015	0.000	J. KEITH ROGERS
	N2306 E217 SW 35 36S 22E SL							3488 FOOTHILL DRIVE
09-832	Underground		T	19800516	DIS	0.015	0.000	J. KEITH ROGERS
	N1728 E215 SW 35 36S 22E SL							3488 FOOTHILL DRIVE
09-833	Underground		P	19800516	I	0.015	0.000	J. KEITH ROGERS
	N1265 W250 SE 34 36S 22E SL							3488 NORTH FOOTHILL DRIVE
09-834	Underground		T	19800516	DIS	0.015	0.000	J. KEITH ROGERS
	N2208 E2252 S4 34 36S 22E SL							3488 FOOTHILL DRIVE
09-843	Underground		P	19900308	DI	0.015	0.000	STAN AND SANDRA PERKINS
	N2220 E1930 S4 34 36S 22E SL							864 NORTH DAYBREAK DRIVE
09-860	Underground	<u>well info</u>	P	19770620	DI	0.015	0.000	STANLEY D. MARTINEAU
	S830 E1740 W4 01 37S 22E SL							P.O. BOX #822
09-871	Underground		P	19770606	S	0.015	0.000	JESS M. GROVER
	N270 E520 W4 36 36S 22E SL							BLANDING UT 84511
09-872	Underground	<u>well info</u>	P	19770606	S	0.015	0.000	JESS M. GROVER
	S420 E2080 W4 01 37S 22E SL							BLANDING UT 84511
09-875	Underground	<u>well info</u>	P	19770630	IS	0.015	2.512	AROE G. BROWN
	N1570 W1230 SE 01 37S 22E SL							BOX 213
09-876	Underground	<u>well info</u>	P	19770630	IS	0.015	1.400	PETER D. AND GEORGIA R. KARAMESINES
	N1150 W1900 SE 01 37S 22E SL							1527 LINCOLN STREET APT. #4
09-879	Underground		P	19770706	I	0.015	0.000	JAMES DEWEY AND

								SHIRLEY LOU B. BRADFORD
	N570 W700 SE 36 36S 22E SL							149 SOUTH 800 EAST
09-885	Underground		P	19770711	I	0.015	0.000	GEORGE H. BRADFORD
	N1280 W1050 SE 36 36S 22E SL							BOX 855
09-888	Underground	<u>well info</u>	P	19770711	IS	0.015	0.000	FRED E. HALLIDAY
	S1310 E585 NW 11 37S 22E SL							BOX 335
09-895	Underground		T	19800925	IS	0.015	0.000	NELDON E. HOLT
	S1340 E1300 N4 21 37S 22E SL							BOX 394
09-896	Underground	<u>well info</u>	P	19770713	S	0.007	0.000	NELDON E. HOLT
	N100 E680 SW 15 37S 22E SL							BOX 394
09-906	Underground		T	19770719	DIS	0.015	0.000	REED E. BAYLES
	N1520 E650 S4 35 36S 22E SL							P.O. BOX #203
09-914	Underground		P	19770726	IS	0.015	0.000	EUGENE GUYMON
	N275 W150 E4 02 37S 22E SL							P.O. BOX #117
09-915	Underground		U	19770726	IS	0.100	0.000	EUGENE GUYMON
	N300 W100 E4 02 37S 22E SL							P.O. BOX #117
09-925	Underground	<u>well info</u>	P	19770728	DIS	0.015	0.000	DOROTHY PERKINS
	S75 W25 E4 02 37S 22E SL							205 EAST 700 SOUTH
09-93	Underground		P	19440929	S	0.013	0.000	BARRY LEE AND LOREE A. WOOLLEY
	N644 W855 SE 10 37S 22E SL							191 BUTTERNUT DRIVE NORTH
09-949	Underground		T	19770816	DIS	0.015	0.000	BERTHA SNYDER
	S200 E800 W4 01 37S 22E SL							P.O. BOX 1318
09-954	Underground		P	19770907	DIS	0.015	0.000	PHYLLIS B. JONES

Denison Mines (USA) Corp.
White Mesa Mill Reclamation Plan

	N500 W1280 SE 36 36S 22E SL							P.O. BOX #472
<u>09-955</u>	Underground		P	19770907	I	0.015	0.000	O. FROST BLACK
	S175 E50 W4 36 36S 22E SL							P.O. BOX #71
<u>09-958</u>	Underground		T	19770915	IS	0.015	0.000	RICHARD & NORMAN NIELSON
	S2640 W400 NE 14 37S 22E SL							P.O. BOX #245
<u>09-959</u>	Underground		T	19840329	DIS	0.015	0.000	NORMAN AND RICHARD C. NIELSON
	N1700 W1100 SE 11 37S 22E SL							63 NORTH 100 WEST (17-2)
<u>09-960</u>	Underground		T	19880622	IS	0.015	0.000	NORMAN AND RICHARD NIELSON
	S585 E40 W4 01 37S 22E SL							63 NORTH 100 WEST (17-2)
<u>09-977</u>	Underground		T	19771005	DIS	0.015	0.000	KENNETH P. MCDONALD
	N559 0 S4 34 36S 22E SL							60 NORTH 100 WEST (16-5)
<u>09-983</u>	Underground		T	19771007	IS	0.500	0.000	PETER D. AND GEORGIA R. KARAMESINES
	N1270 W1980 SE 01 37S 22E SL							1527 LINCOLN STREET APT. #4
<u>09-984</u>	Underground	<u>well info</u>	P	19771013	DIO	0.015	0.000	FRANK A. MONTELLA
	S545 W505 E4 03 37S 22E SL							P.O. BOX #643, HIGHWAY 163 NORTH
<u>09-988</u>	Underground		A	19811117	DI	0.015	0.000	GARTH L. BRADFORD
	N700 W270 SE 36 36S 22E SL							P.O. BOX #1357
<u>09-989</u>	Underground		T	19771031	DO	0.015	0.000	REX D. ANDERSON
	N155 E1010 W4 15 37S 22E SL							P.O. BOX 569
<u>09-990</u>	Underground	<u>well info</u>	P	19771101	IS	0.015	1.280	EUGENE GUYMON


Denison Mines (USA) Corp.
White Mesa Mill Reclamation Plan

	N400 W350 E4 02 37S 22E SL							P.O. BOX #117
09-993	Underground		P	19771027	DI	0.015	0.000	BERNAL BRADFORD
	N1260 W200 SE 36 36S 22E SL							P.O. BOX #594
09-994	Underground		P	19771108	S	0.015	0.000	UTAH SCHOOL AND INSTITUTIONAL TRUST LANDS ADMIN.
	S660 W660 NE 32 38S 22E SL							675 EAST 500 SOUTH, 5TH FLOOR
a12177	Underground		A	19820223	DIS	0.015	0.000	NED J. AND MARILYN PALMER
	S551 E1540 W4 01 37S 22E SL							12 EAST 5TH SOUTH 107-5
a13054	Underground		T	19831205	IS	0.015	0.000	NORMAN AND RICHARD NIELSON
	S585 E40 W4 01 37S 22E SL							P.O. BOX #245
a20266	Underground		T	19770315	M	2.000	0.000	BLANDING CITY
	S2440 W1245 NE 35 36S 22E SL							50 WEST 100 SOUTH
a20266	Underground		T	19770315	M	2.000	0.000	BLANDING CITY
	S2440 W870 NE 35 36S 22E SL							50 WEST 100 SOUTH
a21545	Underground	<u>well info</u>	T	19970915	DI	0.000	4.730	JIM & MARY BOURNE
	N3055 W1059 SE 01 37S 22E SL							468 NORTH 500 WEST
a24139	Underground	<u>well info</u>	T	20000201	DIS	0.000	1.480	ANNA M. RAFFERTY
	S860 E315 NW 22 37S 22E SL							P.O. BOX 553
a35842	Underground		U	20090819	M	2.000	0.000	BLANDING CITY
	N938 E135 W4 01 37S 22E SL							50 WEST 100 SOUTH
a35842	Underground		U	20090819	M	2.000	0.000	BLANDING CITY
	S145 E133 N4 12 37S 22E SL							50 WEST 100 SOUTH
a35896	Underground		U	20090908	DIS	0.000	4.730	MITCHELL H. &

Denison Mines (USA) Corp.
White Mesa Mill Reclamation Plan

								JANA L. BAILEY
	N256 W943 SE 16 37S 22E SL							210 N. SHIRTTAIL WAY
<u>t89-09-01</u>	Underground		T	19890118	O	0.000	5.000	IVAN R. WATKINS
	S2722 E10 NW 01 37S 22E SL							BOX 938
<u>t89-09-02</u>	Underground		T	19890504	O	0.000	5.000	IVAN R. WATKINS
	S2722 E10 NW 01 37S 22E SL							BOX 938

W:\Legacy\USA\UTAH\Mill\DWGs\Reclamation\Plans\Rev_07-2011\Work01\Fig.1.5-9_GroundWaterApprop.dwg 11x17 G.Mossley



Denison Mines (USA) Corp	
REVISIONS Date By 09-11 GM	Project: White Mesa Mill County: San Juan State: UT Location:
GROUNDWATER APPROPRIATIONS WITHIN A 5-MILE RADIUS OF THE WHITE MESA MILL FIGURE 1.5-9	
Author: unknown	Date: May 2010
Drafted By: D.Siedd	

The well yield from wells completed in the Burro Canyon formation within the White Mesa site is generally lower than that obtained from wells in this formation upgradient of the site. For the most part, the documented pumping rates from on-site wells completed in the Burro Canyon formation are less than 0.7 cfs. Even at this low rate, the on-site wells completed in the Burro Canyon formation are typically pumped dry within a couple of hours.

This low productivity suggests that the Mill is located over a peripheral fringe of perched water; with saturated thickness in the perched zone discontinuous and generally decreasing beneath the site, and with conductivity of the formation being very low. These observations have been verified by studies performed for the U.S. Department of Energy's disposal site at Slick Rock, which noted that the Dakota Sandstone, Burro Canyon formation, and upper claystone of the Brushy Basin Member are not considered aquifers due to the low permeability, discontinuous nature, and limited thickness of these units (U.S. DOE, 1993).

1.6 Geology

The following text is copied, with minor revisions, from the 1978 ER (Dames and Moore, 1978b). The text has been duplicated herein for ease of reference and to provide background information concerning the site geology. 1978 ER Subsections used in the following text are shown in parentheses immediately following the subsection titles.

The site is near the western margin of the Blanding Basin in southeastern Utah and within the Monticello uranium-mining district. Thousands of feet of multi-colored marine and non-marine sedimentary rocks have been uplifted and warped, and subsequent erosion has carved a spectacular landscape for which the region is famous. Another unique feature of the region is the wide-spread presence of unusually large accumulations of uranium-bearing minerals.

1.6.1 Regional Geology


The following descriptions of regional physiography; rock units; and structure and tectonics are reproduced from the 1978 ER for ease of reference and as a review of regional geology.

1.6.1.1 Physiography (1978 ER Section 2.4.1.1)

The Mill site lies within the Canyon Lands section of the Colorado Plateau physiographic province. To the north, this section is distinctly bounded by the Book Cliffs and Grand Mesa of the Uinta Basin; western margins are defined by the tectonically controlled High Plateaus section, and the southern boundary is arbitrarily defined along the San Juan River. The eastern boundary is less distinct where the elevated surface of the Canyon Lands section merges with the Southern Rocky Mountain province.

Canyon Lands has undergone epeirogenic uplift and subsequent major erosion has produced the region's characteristic angular topography reflected by high plateaus, mesas, buttes, structural benches, and deep canyons incised into flat-laying sedimentary rocks of pre-Tertiary age. Elevations range from approximately 3,000 feet (914 meters) in the bottom of the deeper canyons along the southwestern margins of the section to more than 11,000 feet (3,353 meters) in the topographically anomalous laccolithic Henry, Abajo and La Sal Mountains to the northeast. Except for the deeper canyons and isolated mountain peaks, an average elevation in excess of 500 feet (1,524 meters) persists over most of the Canyon Lands section.

On a more localized regional basis, the Mill site is located near the western edge of the Blanding Basin, sometimes referred to as the Great Sage Plain (Eardly, 1958), lying east of the north-south trending Monument Uplift, south of the Abajo Mountains and adjacent to the northwesterly-trending Paradox Fold and Fault Belt (Figure 1.6-1). Topographically, the Abajo Mountains are the most prominent feature in the region, rising more than 4,000 feet (1,219 meters) above the broad, gently rolling surface of the Great Sage Plain.



LEGEND


-  **BOUNDARY OF TECTONIC DIVISION**
-  **MONOCLINE SHOWING TRACE OF AXIS AND DIRECTION OF DIP**
-  **ANTICLINE SHOWING TRACE OF AXIS AND DIRECTION OF PLUNGE**
-  **SYNCLINE SHOWING TRACE OF AXIS AND DIRECTION OF PLUNGE**

Figure 1.6-1

Colorado Plateau Geologic Map

The Great Sage Plain is a structural slope, capped by the resistant Burro Canyon formation and the Dakota Sandstone, almost horizontal in an east-west direction but descends to the south with a regional slope of about 2,000 feet (610 meters) over a distance of nearly 50 miles (80 kilometers). Though not as deeply or intricately dissected as other parts of the Canyon Lands, the plain is cut by numerous narrow and vertical-walled south-trending valleys 100 to more than 500 feet (30 to 152+ meters) deep. Water from the intermittent streams that drain the plain flow southward to the San Juan River, eventually joining the Colorado River and exiting the Canyon Lands section through the Grand Canyon.

1.6.1.2 Rock Units (1978 ER Section 2.4.1.1)

The sedimentary rocks exposed in southeastern Utah have an aggregate thickness of about 6,000 to 7,000 feet (1,829 to 2,134 meters) and range in age from Pennsylvanian to Late Cretaceous. Older unexposed rocks are known mainly from oil well drilling in the Blanding Basin and Monument Uplift. These wells have encountered correlative Cambrian to Permian rock units of markedly differing thicknesses but averaging over 5,000 feet (1,524 meters) in total thickness (Witkind, 1964). Most of the wells drilled in the region have bottomed in the Pennsylvanian Paradox Member of the Hermosa formation. A generalized stratigraphic section of rock units ranging in age from Cambrian through Jurassic and Triassic (?), as determined from oil-well logs, is shown in Table 1.6-1. Descriptions of the younger rocks, Jurassic through Cretaceous, are based on field mapping by various investigators and are shown in Table 1.6-2.

Paleozoic rocks of Cambrian, Devonian and Mississippian ages are not exposed in the southeastern Utah region. Most of the geologic knowledge regarding these rocks was learned from the deeper oil wells drilled in the region, and from exposures in the Grand Canyon to the

**Table 1.6-1
Generalized Stratigraphic Section of Subsurface Rocks Based on Oil-Well Logs (Table 2.6-1 UMETCO)**

Age	Stratigraphic Unit	Thickness* (ft.)	Description
MESOZOIC			
<u>Glen Canyon Group:</u>			
Jurassic and Triassic (?)	Navajo Sandstone	300 - 400	Buff to light gray, massive, cross-bedded, friable sandstone
Triassic (?)	Kayenta Formation	100 - 150	Reddish-brown sandstone and mudstone and occasional conglomerate lenses
Triassic	Wingate Sandstone	250 - 350	Reddish-brown, massive, cross-bedded, fine-grained sandstone
<u>Chinle Formation:</u>			
	Undivided	600 - 700	Variegated claystone with some thin beds of siltstone and limestone
	Moss Back Member	0 - 100	Light colored, conglomeratic sandstone and conglomerite
	Shinarump Member	0 - 20	Yellowish-gray, fine to coarse-grained sandstone; conglomeratic sandstone and conglomerate
----- Unconformity -----			
Middle (?) and Lower Triassic	Moenkopi Formation	50 - 100	Reddish-brown mudstone and fine-grained sandstone
----- Unconformity -----			
PALEOZOIC			
<u>Permian</u>			
<u>Cutler Formation:</u>			
	Organ Rock Member	0 - 800	Reddish-brown, sandy mudstone
	Cedar Mesa Sandstone Member	1100 - 1400	Reddish-brown, massive, fine to medium-grained sandstone
Pennsylvanian and Permian (?)	Rice Formation	450	Red and gray calcareous, sandy shale; gray limestone and sandstone
<u>Permian</u>			
<u>Hermosa Formation:</u>			
	Upper Member	1000 - 1200	Gray, massive limestone; some shale and sandstone
	Paradox Member	1200	Halls, anhydrite, gypsum, shale, and siltstone
	Lower Member	200	Limestone, siltstone, and shale
----- Unconformity -----			
Mississippian	Leadville Limestone	500	White to tan sucrose to crystalline limestone
Devonian	Ouray Limestone	100	Light gray and tan, thin-bedded limestone and dolomite
	Zilbert Formation	200	Gray and brown dolomite and limestone with thin beds green shale and sandstone
----- Unconformity -----			
Cambrian	Ophir Formation and Tintic Quartzite	600	Gray and brown limestone and dolomite, feldspathic sandstone and arkose

* To convert feet to meters, multiply by 0.3048. Average thickness given if range is not shown.

Table 1.6-2
Generalized Stratigraphic Section of Exposed Rocks in the Project Vicinity (Table 2.6-2 UMETCO)

ERA	SYSTEM	SERIES (Age)	STRATIGRAPHIC UNIT	THICKNESS* (ft.)	LITHOLOGY	
CENOZOIC	QUATERNARY	Holocene to Pleistocene	Alluvium	2 - 25+	Silt, sand and gravel in arroyos and stream valleys.	
			Colluvium and Talus	0 - 15+	Slope wash, talus and rock rubble ranging from cobbles and boulders to massive blocks fallen from cliffs and outcrops of resistant rock.	
			Loess	0 - 22+	Reddish-brown to light-brown, unconsolidated, well-sorted silt to medium-grained sand; partially cemented with caliche in some areas; reworked partly by water.	
			Unconformity			
MESOZOIC	CRETACEOUS	Upper Cretaceous	Mancoes Shale	0 - 11(7)	Gray to dark-gray, fissile, thin-bedded marine shale with fossiliferous sandy limestone in lower strata.	
			Dakota Sandstone	30 - 75	Light yellowish-brown to light gray-brown, thick bedded to cross-bedded sandstone, conglomeratic sandstone; interbedded thin lenticular gray carbonaceous claystone and impure coal; local coarse basal conglomerate.	
		Lower Cretaceous	Burro Canyon Formation	50 - 150	Light-gray and light-brown, massive and cross-bedded conglomeratic sandstone and interbedded green and gray-green mudstone; locally contains thin discontinuous beds of silicified sandstone and limestone near top.	
		Unconformity (7)				
	Jurassic	Upper Jurassic	Mashkin Formation	Brushy Basin Member	200 - 450	Variegated gray, pale-green, reddish-brown, and purple bentonitic mudstone and siltstone containing thin discontinuous sandstone and conglomerate lenses.
				Westwater Canyon Member	0 - 250	Interbedded yellowish- and greenish-gray to pinkish-gray, fine- to coarse-grained arkosic sandstone and greenish-gray to reddish-brown sandy shale and mudstone.
				Recapture Member	0 - 200	Interbedded reddish-gray to light brown fine- to medium-grained sandstone and reddish-gray silty and sandy claystone.
				Salt Wash Member	0 - 350	Interbedded yellowish-brown to pale reddish-brown fine-grained to conglomeratic sandstones and greenish- and reddish-gray mudstone.
			Unconformity			
			San Rafael Group	Bluff Sandstone	0 - 150+	White to grayish-brown, massive, cross-bedded, fine- to medium-grained eolian sandstone.
Summerville Formation	25 - 125	Thin-bedded, ripple-marked reddish-brown muddy sandstone and sandy shale.				
Middle Jurassic	San Rafael Group	Entrada Sandstone	150 - 180	Reddish-brown to grayish-white, massive, cross-bedded, fine- to medium-grained sandstone.		
		Carmel Formation	20 - 100+	Irregularly bedded reddish-brown muddy sandstone and sandy mudstone with local thin beds of brown to gray limestone and reddish- to greenish-gray shale.		
			Unconformity			

*To convert feet to meters, multiply feet by 0.3048.

southwest and in the Uinta and Wasatch Mountains to the north. A few patches of Devonian rocks are exposed in the San Juan Mountains in southwestern Colorado. These Paleozoic rocks are the result of periodic transgressions and regressions of epicontinental seas and their lithologies reflect a variety of depositional environments.

In general, the coarse-grained feldspathic rocks overlying the Precambrian basement rocks grade upward into shales, limestones and dolomites that dominate the upper part of the Cambrian. Devonian and Mississippian dolomites, limestones and interbedded shales unconformably overlay the Cambrian strata. The complete absence of Ordovician and Silurian rocks in the Grand Canyon, Uinta Mountains, southwest Utah region and adjacent portions of Colorado, New Mexico and Arizona indicate that the region was probably epeirogenically positive during these times.

The oldest stratigraphic unit that crops out in the region is the Hermosa formation of Middle and Late Pennsylvanian age. Only the uppermost strata of this formation are exposed, the best exposure being in the canyon of the San Juan River at the "Goosenecks" where the river traverses the crest of the Monument uplift. Other exposures are in the breached centers of the Lisbon Valley, Moab and Castle Valley anticlines. The Paradox Member of the Hermosa formation is sandwiched between a relatively thin lower unnamed member consisting of dark-gray shale siltstone, dolomite, anhydrite, and limestone, and an upper unnamed member of similar lithology but having a much greater thickness. Composition of the Paradox Member is dominantly a thick sequence of interbedded slate (halite), anhydrite, gypsum, and black shale. Surface exposures of the Paradox in the Moab and Castle Valley anticlines are limited to contorted residues of gypsum and black shale.

Conformably overlying the Hermosa is the Pennsylvanian and Permian (?) Rico formation, composed of interbedded reddish-brown arkosic sandstone and gray marine limestone. The Rico represents a transition zone between the predominantly marine Hermosa and the overlying continental Cutler formation of Permian age.

Two members of the Cutler probably underlying the region south of Blanding are, in ascending order, the Cedar Mesa Sandstone and the Organ Rock Tongue. The Cedar Mesa is a white to pale reddish-brown, massive, cross-bedded, fine-to medium-grained eolian sandstone. An irregular fluvial sequence of reddish-brown fine-grained sandstones, shaly siltstones and sandy shales comprise the Organ Rock Tongue.

The Moenkopi formation, of Middle (?) and Lower Triassic age, unconformably overlies the Cutler strata. It is composed of thin, evenly-bedded, reddish to chocolate-brown, ripple-marked, cross-laminated siltstone and sandy shales with irregular beds of massive medium-grained sandstone.

A thick sequence of complex continental sediments known as the Chinle formation unconformably overlies the Moenkopi. For the purpose of making lithology correlations in oil wells this formation is divided into three units: The basal Shinarump Member, the Moss Back Member and an upper undivided thick sequence of variegated reddish-brown, reddish- to greenish-gray, yellowish-brown to light-brown bentonitic claystones, mudstones, sandy siltstone, fine-grained sandstone, and limestones. The basal Shinarump is dominantly a yellowish-grey, fine- to coarse-grained sandstone, conglomeratic sandstone and conglomerate characteristically filling ancient stream channel scours eroded into the Moenkopi surface. Numerous uranium deposits have been located in this member in the White Canyon mining district to the west of Comb Ridge. The Moss Back is typically composed of yellowish- to greenish-grey, fine- to medium-grained sandstone, conglomeratic sandstone and conglomerate. It commonly comprises the basal unit of the Chinle where the Shinarump was not deposited, and in a like manner, fills ancient stream channels scoured into the underlying unit.

In the Blanding Basin the Glen Canyon Group consists of three formations which are, in ascending order, the Wingate Sandstone, the Kayenta and the Navajo Sandstone. All are conformable and their contacts are gradational. Commonly cropping out in sheer cliffs, the Late Triassic Wingate Sandstone is typically composed of buff to reddish-brown, massive, cross-

bedded, well-sorted, fine-grained quartzose sandstone of eolian origin. Late Triassic (?) Kayenta is fluvial in origin and consists of reddish-brown, irregularly to cross-bedded sandstone, shaly sandstone and, locally, thin beds of limestone and conglomerate. Light yellowish-brown to light-gray and white, massive, cross-bedded, friable, fine- to medium-grained quartzose sandstone typifies the predominantly eolian Jurassic and Triassic (?) Navajo Sandstone.

Four formations of the Middle to Late Jurassic San Rafael Group unconformably overly the Navajo Sandstone. These strata are composed of alternating marine and non-marine sandstones, shales and mudstones. In ascending order, the formations are the Carmel formation, Entrada Sandstone, Summerville formation, and Bluff Sandstone. The Carmel usually crops out as a bench between the Navajo and Entrada Sandstones. Typically reddish-brown muddy sandstone and sandy mudstone, the Carmel locally contains thin beds of brown to gray limestone and reddish- to greenish-gray shale. Predominantly eolian in origin, the Entrada is a massive cross-bedded fine- to medium-grained sandstone ranging in color from reddish-brown to grayish-white that crops out in cliffs or hummocky slopes. The Summerville is composed of regular thin-bedded, ripple-marked, reddish-brown muddy sandstone and sandy shale of marine origin and forms steep to gentle slopes above the Entrada. Cliff-forming Bluff Sandstone is present only in the southern part of the Monticello district thinning northward and pinching out near Blanding. It is a white to grayish-brown, massive, cross-bedded eolian sandstone.

In the southeastern Utah region the Late Jurassic Morrison formation has been divided in ascending order into the Salt Wash, Recapture, Westwater Canyon, and Brushy Basin Members. In general, these strata are dominantly fluvial in origin but do contain lacustrine sediments. Both the Salt Wash and Recapture consist of alternating mudstone and sandstone; the Westwater Canyon is chiefly sandstone with some sandy mudstone and claystone lenses, and the heterogeneous Brushy Basin consists of variegated bentonitic mudstone and siltstone containing scattered thin limestone, sandstone, and conglomerate lenses. As strata of the Morrison formation are the oldest rocks exposed in the Mill area vicinity and are one of the two principal

uranium-bearing formations in southeast Utah, the Morrison, as well as younger rocks, are described in more detail in Section 1.6.2.2.

The Early Cretaceous Burro Canyon formation rests unconformably (?) on the underlying Brushy Basin Member of the Morrison formation. Most of the Burro Canyon consists of light-colored, massive, cross-bedded fluvial conglomerate, conglomerate sandstone and sandstone. Most of the conglomerates are near the base. Thin, even-bedded, light-green mudstones are included in the formation and light-grey thin-bedded limestones are sometimes locally interbedded with the mudstones near the top of the formation.

Overlying the Burro Canyon is the Dakota Sandstone of Upper Cretaceous age. Typical Dakota is dominantly yellowish-brown to light-gray, thick-bedded, quartzitic sandstone and conglomeratic sandstone with subordinate thin lenticular beds of mudstone, gray carbonaceous shale and, locally, thin seams of impure coal. The contact with the underlying Burro Canyon is unconformable whereas the contact with the overlying Mancos Shale is gradational from the light-colored sandstones to dark-grey to black shaly siltstone and shale.

Upper Cretaceous Mancos Shale is exposed in the region surrounding the project vicinity but not within it. Where exposed and weathered, the shale is light-gray or yellowish-gray, but is dark, to olive-gray where fresh. Bedding is thin and well developed; much of it is laminated.

Quaternary alluvium within the project vicinity is of three types: alluvial silt, sand and gravels deposited in the stream channels; colluvium deposits of slope wash, talus, rock rubble and large displaced blocks on slopes below cliff faces and outcrops of resistant rock; and alluvial and windblown deposits of silt and sand, partially reworked by water, on benches and broad upland surfaces.

1.6.1.3 Structure and Tectonics (1978 ER Section 2.4.1.3)

According to Shoemaker (1954 and 1956), structural features within the Canyon Lands of southeastern Utah may be classified into three main categories on the basis of origin or mechanism of the stress that created the structure. These three categories are: (1) structures related to large-scale regional uplifting or downwarping (epeirogenic deformation) directly related to movements in the basement complex (Monument Uplift and the Blanding Basin); (2) structures resulting from the plastic deformation of thick sequences of evaporite deposits, salt plugs and salt anticlines, where the structural expression at the surface is not reflected in the basement complex (Paradox Fold and Fault Belt); and (3) structures that are formed in direct response to stresses induced by magmatic intrusion including local laccolithic domes, dikes and stocks (Abajo Mountains).

Each of the basins and uplifts within the Mill area region is an asymmetric fold usually separated by a steeply dipping sinuous monocline. Dips of the sedimentary beds in the basins and uplifts rarely exceed a few degrees except along the monocline (Shoemaker, 1956) where, in some instances, the beds are nearly vertical. Along the Comb Ridge monocline, the boundary between the Monument Uplift and the Blanding Basin, approximately eight miles (12.9 kilometers) west of the Mill area, dips in the Upper Triassic Wingate sandstone and in the Chinle formation are more than 40 degrees to the east.

Structures in the crystalline basement complex in the central Colorado Plateau are relatively unknown but where monoclines can be followed in Precambrian rocks they pass into steeply dipping faults. It is probable that the large monoclines in the Canyon Lands section are related to flexure of the layered sedimentary rocks under tangential compression over nearly vertical normal or high-angle reverse faults in the more rigid Precambrian basement rocks (Kelley, 1955; Shoemaker, 1956; Johnson and Thordarson, 1966).

The Monument Uplift is a north-trending, elongated, upwarped structure approximately 90 miles (145 kilometers) long and nearly 35 miles (56 kilometers) wide. Structural relief is about 3,000 feet (914 meters) (Kelley, 1955). Its broad crest is slightly convex to the east where the Comb Ridge monocline defines the eastern boundary. The uniform and gently descending western flank of the uplift crosses the White Canyon slope and merges into the Henry Basin (Figure 1.6-1).

East of the Monument Uplift, the relatively equidimensional Blanding Basin merges almost imperceptibly with the Paradox Fold and Fault Belt to the north, the Four Corners Platform to the southeast and the Defiance Uplift to the south. The basin is a shallow feature with approximately 700 feet (213 meters) of structural relief as estimated on top of the Upper Triassic Chinle formation by Kelley (1955), and is roughly 40 to 50 miles (64 to 80 kilometers) across. Gentle folds within the basin trend westerly to northwesterly in contrast to the distinct northerly orientation of the Monument Uplift.

Situated to the north of the Monument Uplift and Blanding Basin is the most unique structural feature of the Canyon Lands section, the Paradox Fold and Fault Belt. This tectonic unit is dominated by northwest trending anticlinal folds and associated normal faults covering an area about 150 miles (241 kilometers) long and 65 miles (104 kilometers) wide. These anticlinal structures are associated with salt flowage from the Pennsylvanian Paradox Member of the Hermosa formation and some show piercement of the overlying younger sedimentary beds by plug-like salt intrusions (Johnson and Thordarson, 1966). Prominent valleys have been eroded along the crests of the anticlines where salt piercements have occurred or collapses of the central parts have resulted in intricate systems of step-faults and grabens along the anticlinal crests and flanks.

The Abajo Mountains are located approximately 20 miles (32 kilometers) north of the Mill area on the more-or-less arbitrary border of the Blanding Basin and the Paradox Fold and Fault Belt (Figure 1.6-1). These mountains are laccolithic domes that have been intruded into and through

the sedimentary rocks by several stocks (Witkind, 1964). At least 31 laccoliths have been identified. The youngest sedimentary rocks that have been intruded are those of Mancos Shale of Late Cretaceous age. Based on this and other vague and inconclusive evidence, Witkind (1964), has assigned the age of these intrusions to the Late Cretaceous or early Eocene.

Nearly all known faults in the region of the Mill area are high-angle normal faults with displacements on the order of 300 feet (91 meters) or less (Johnson and Thordarson, 1966). The largest known faults within a 40-mile (64 kilometer) radius around Blanding are associated with the Shay graben on the north side of the Abajo Mountains and the Verdure graben on the south side. Respectively, these faults trend northeasterly and easterly and can be traced for approximate distances ranging from 21 to 34 miles (34 to 55 kilometers) according to Witkind (1964). Maximum displacements reported by Witkind on any of the faults are 320 feet (98 meters). Because of the extensions of Shay and Verdure fault systems beyond the Abajo Mountains and other geologic evidence, the age of these faults is Late Cretaceous or post-Cretaceous and antedate the laccolithic intrusions (Witkind, 1964).

A prominent group of faults is associated with the salt anticlines in the Paradox Fold and Fault Belt. These faults trend northwesterly parallel to the anticlines and are related to the salt emplacement. Quite likely, these faults are relief features due to salt intrusion or salt removal by solution (Thompson, 1967). Two faults in this region, the Lisbon Valley fault associated with the Lisbon Valley salt anticline and the Moab fault at the southeast end of the Moab anticline have maximum vertical displacements of at least 5,000 feet (1,524 meters) and 2,000 feet (609 meters), respectively, and are probably associated with breaks in the Precambrian basement crystalline complex. It is possible that zones of weakness in the basement rocks represented by faults of this magnitude may be responsible for the beginning of salt flowage in the salt anticlines, and subsequent solution and removal of the salt by groundwater caused collapse within the salt anticlines resulting in the formation of grabens and local complex block faults (Johnson and Thordarson, 1966).

The longest faults in the Colorado Plateau are located some 155 to 210 miles (249 to 338 kilometers) west of the Mill area along the western margin of the High Plateau section. These faults have a north to northeast echelon trend, are nearly vertical and downthrown on the west in most places. Major faults included in this group are the Hurrigan, Toroweap-Sevier, Paunsaugunt, and Paradise faults. The longest fault, the Toroweap-Sevier, can be traced for about 240 miles (386 kilometers) and may have as much as 3,000 feet (914 meters) of displacement (Kelley, 1955).

From the later part of the Precambrian until the middle Paleozoic the Colorado Plateau was a relatively stable tectonic unit undergoing gentle epeirogenic uplifting and downwarping during which seas transgressed and regressed, depositing and then partially removing layers of sedimentary materials. This period of stability was interrupted by northeast-southwest tangential compression that began sometime during late Mississippian or early Pennsylvanian and continued intermittently into the Triassic. Buckling along the northeast margins of the shelf produced northwest-trending uplifts, the most prominent of which are the Uncompahgre and San Juan Uplifts, sometimes referred to as the Ancestral Rocky Mountains. Clearly, these positive features are the earliest marked tectonic controls that may have guided many of the later Laramide structures (Kelley, 1955).

Subsidence of the area southwest of the Uncompahgre Uplift throughout most of the Pennsylvanian led to the filling of the newly formed basin with an extremely thick sequence of evaporites and associated interbeds which comprise the Paradox Member of the Hermosa formation (Kelley, 1956). Following Paradox deposition, continental and marine sediments buried the evaporite sequence as epeirogenic movements shifted shallow seas across the region during the Jurassic, Triassic and much of the Cretaceous. The area underlain by the Paradox Member in eastern Utah and western Colorado is commonly referred to as the Paradox Basin (Figure 1.6-1). Renewed compression during the Permian initiated the salt anticlines and piercements, and salt flowage continued through the Triassic.

The Laramide orogeny, lasting from Late Cretaceous through Eocene time, consisted of deep-seated compressional and local vertical stresses. The orogeny is responsible for a north-south to northwest trend in the tectonic fabric of the region and created most of the principal basins and uplifts in the eastern-half of the Colorado Plateau (Grose, 1972; Kelley, 1955).

Post-Laramide epirogenic deformation has occurred throughout the Tertiary; Eocene strata are flexed sharply in the Grand Hogback monocline, fine-grained Pliocene deposits are tilted on the flanks of the Defiance Uplift, and Pleistocene deposits in Fisher Valley contain three angular unconformities (Shoemaker, 1956).


1.6.2 Blanding Site Geology

The following descriptions of physiography and topography; rock units; structure; relationship of earthquakes to tectonic structure; and potential earthquake hazards to the Mill area are reproduced from the 1978 ER for ease of reference and as a review of the Mill site geology. (See Figure 1.6-2)

1.6.2.1 Physiography and Topography (1978 ER Section 2.4.2.1)

The Mill site is located near the center of White Mesa, one of the many finger-like north-south trending mesas that make up the Great Sage Plain. The nearly flat upland surface of White Mesa is underlain by resistant sandstone caprock which forms steep prominent cliffs separating the upland from deeply entrenched intermittent stream courses on the east, south and west.

Surface elevations across the Mill site range from about 5,550 to 5,650 feet (1,692 to 1,722 meters) and the gently rolling surface slopes to the south at a rate of approximately 60 feet per mile (18 meters per 1.6 kilometer).



REFERENCES: GEOLOGY, IN PART, AFTER HAYNES ET AL., 1962. BASE MAP PREPARED FROM PORTIONS OF THE BLANDING, BRUSHY BASIN WASH, BLUFF, AND MONTEZUMA CREEK U.S.G.S. 15-MINUTE TOPOGRAPHIC QUADRANGLES.

EXPLANATION

- Qae** LOESS
- Km** MANCOS SHALE
- Kdb** DAKOTA AND BURRO CANYON FORMATIONS (UNDIFFERENTIATED)
- Jmb** MORRISON FORMATION: BRUSHY BASIN MEMBER
- Jmw** WESTWATER CANYON MEMBER
- Jmr** RECAPTURE MEMBER

CONTACT, DASHED WHERE APPROXIMATE



Denison Mines (USA) Corp.		
Project: WHITE MESA MILL		
County: San Juan	State: Utah	
FIGURE 1.6-2 WHITE MESA MILLSITE GEOLOGY OF SURROUNDING AREA		
Date: Nov. 2009	Design:	Drafted By: RAH

After Umetco. 1988

Maximum relief between the mesa's surface and Cottonwood Canyon on the west is about 750 feet (229 meters) where Westwater Creek joins Cottonwood Wash. These two streams and their tributaries drain the west and south sides of White Mesa. Drainage on the east is provided by Recapture Creek and its tributaries. Both Cottonwood Wash and Recapture Creeks are normally intermittent streams and flow south to the San Juan River. However, Cottonwood Wash has been known to flow perennially in the project vicinity during wet years.

1.6.2.2 Rock Units (1978 ER Section 2.4.2.2)

Only rocks of Jurassic and Cretaceous ages are exposed in the vicinity of the Mill site. These include, in ascending order, the Upper Jurassic Salt Wash, Recapture, Westwater Canyon, and Brushy Basin Members of the Morrison formation; the Lower Cretaceous Burro Canyon formation; and the Upper Cretaceous Dakota Sandstone. The Upper Cretaceous Mancos Shale is exposed as isolated remnants along the rim of Recapture Creek valley several miles southeast of the Mill site and on the eastern flanks of the Abajo Mountains some 20 miles (32 kilometers) north but is not exposed at the Mill site. However, patches of Mancos Shale may be present within the Mill site boundaries as isolated buried remnants that are obscured by a mantle of alluvial windblown silt and sand.

The Morrison formation is of particular economic importance in southeast Utah since several hundred uranium deposits have been discovered in the basal Salt Wash Member (Stokes, 1967).

In most of eastern Utah, the Salt Wash Member underlies the Brushy Basin. However, just south of Blanding in the project vicinity the Recapture Member replaces an upper portion of the Salt Wash and the Westwater Canyon Member replaces a lower part of the Brushy Basin. A southern limit of Salt Wash deposition and a northern limit of Westwater Canyon deposition has been recognized by Haynes et al. (1972) in Westwater Canyon approximately three to six miles (4.8 to 9.7 kilometers), respectively, northwest of the Mill site. However, good exposures of Salt Wash are found throughout the Montezuma Canyon area 13 miles (21 kilometers) to the east.

The Salt Wash Member is composed dominantly of fluvial fine-grained to conglomeratic sandstones, and interbedded mudstones. Sandstone intervals are usually yellowish-brown to pale reddish-brown while the mudstones are greenish- and reddish-gray. Carbonaceous materials ("trash") vary from sparse to abundant. Cliff-forming massive sandstone and conglomeratic sandstone in discontinuous beds make up to 50 percent or more of the member. According to Craig et al. (1955), the Salt Wash was deposited by a system of braided streams flowing generally east and northeast. Most of the uranium-vanadium deposits are located in the basal sandstones and conglomeratic sandstones that fill stream-cut scour channels in the underlying Bluff Sandstone, or where the Bluff Sandstone has been removed by pre-Morrison erosion, in similar channels cut in the Summerville formation. Mapped thicknesses of this member range from zero to approximately 350 feet (0-107 meters) in southeast Utah. Because the Salt Wash pinches out in a southerly direction in Recapture Creek three miles (4.8 kilometers) northwest of the Mill site and does not reappear until exposed in Montezuma Canyon, it is not known for certain that the Salt Wash actually underlies the site.

The Recapture Member is typically composed of interbedded reddish-gray, white, and light-brown fine- to medium-grained sandstone and reddish-gray, silty and sandy claystone. Bedding is gently to sharply lenticular. Just north of the Mill site, the Recapture intertongues with and grades into the Salt Wash and the contact between the two cannot be easily recognized. A few spotty occurrences of uriferous mineralization are found in sandstone lenses in the southern part of the Monticello district and larger deposits are known in a conglomeratic sandstone facies some 75 to 100 miles (121 to 161 kilometers) southeast of the Monticello district. Since significant ore deposits have not been found in extensive outcrops in more favorable areas, the Recapture is believed not to contain potential resources in the Mill site (Johnson and Thordarson, 1966).

Just north of the Mill site, the Westwater Canyon Member intertongues with and grades into the lower part of the overlying Brushy Basin Member. Exposures of the Westwater Canyon in Cottonwood Wash are typically composed of interbedded yellowish- and greenish-gray to

pinkish-gray, lenticular, fine- to coarse-grained arkosic sandstone and minor amounts of greenish-gray to reddish-brown sandy shale and mudstone. Like the Salt Wash, the Westwater Canyon Member is fluvial in origin, having been deposited by streams flowing north and northwest, coalescing with streams from the southwest depositing the upper part of the Salt Wash and the lower part of the Brushy Basin (Huff and Lesure, 1965). Several small and scattered uranium deposits in the Westwater Canyon are located in the extreme southern end of the Monticello district. Both the Recapture Member and the Westwater Canyon contain only traces of carbonaceous materials, are believed to be less favorable host rocks for uranium deposition (Johnson and Thordarson, 1966) and have very little potential for producing uranium reserves.

The lower part of the Brushy Basin is replaced by the Westwater Canyon Member in the Blanding area but the upper part of the Brushy Basin overlies this member. Composition of the Brushy Basin is dominantly variegated bentonitic mudstone and siltstone. Bedding is thin and regular and usually distinguished by color variations of gray, pale-green, reddish-brown, pale purple, and maroon. Scattered lenticular thin beds of distinctive green and red chert-pebble conglomeratic sandstone are found near the base of the member, some of which contain uranium-vanadium mineralization in the southernmost part of the Monticello district (Haynes et al., 1972). Thin discontinuous beds of limestone and beds of grayish-red to greenish-black siltstone of local extent suggest that much of the Brushy Basin is probably lacustrine in origin.

For the most part, the Great Sage Plain owes its existence to the erosion of resistant sandstones and conglomerates of the Lower Cretaceous Burro Canyon formation. This formation unconformably(?) overlies the Brushy Basin and the contact is concealed over most of the Mill area by talus blocks and slope wash. Massive, light-gray to light yellowish-brown sandstone, conglomeratic sandstone and conglomerate comprise more than two-thirds of the formation's thickness. The conglomerate and sandstone are interbedded and usually grade from one to the other. However, most of the conglomerate is near the base. These rocks are massive cross-bedded units formed by a series of interbedded lenses, each lens representing a scour filled with

stream-deposited sediments. In places the formation contains greenish-gray lenticular beds of mudstone and claystone. Most of the Burro Canyon is exposed in the vertical cliffs separating the relatively flat surface of White Mesa from the canyons to the west and east. In some places the resistant basal sandstone beds of the overlying Dakota Sandstone are exposed at the top of the cliffs, but entire cliffs of Burro Canyon are most common. Where the sandstones of the Dakota rest on sandstones and conglomerates of the Burro Canyon, the contact between the two is very difficult to identify and most investigators map the two formations as a single unit (Figure 1.6-2). At best, the contact can be defined as the top of a silicified zone in the upper part of the Burro Canyon that appears to be remnants of an ancient soil that formed during a long period of weathering prior to Dakota deposition (Huff and Lesure, 1965).

The Upper Cretaceous Dakota Sandstone disconformably overlies the Burro Canyon formation. Locally, the disconformity is marked by shallow depressions in the top of the Burro Canyon filled with Dakota sediments containing angular to sub-rounded rock fragments probably derived from Burro Canyon strata (Witkind, 1964) but the contact is concealed at the Mill site. The Dakota is composed predominantly of pale yellowish-brown to light gray, massive, intricately cross-bedded, fine- to coarse-grained quartzose sandstone locally well-cemented with silica and calcite; elsewhere it is weakly cemented and friable. Scattered throughout the sandstone are lenses of conglomerate, dark-gray carbonaceous mudstones and shale and, in some instances, impure coal. In general, the lower part of the Dakota is more conglomeratic and contains more cross-bedded sandstone than the upper part which is normally more thinly bedded and marine-like in appearance. The basal sandstones and conglomerates are fluvial in origin, whereas the carbonaceous mudstones and shales were probably deposited in back water areas behind beach ridges in front of the advancing Late Cretaceous sea (Huff and Lesure, 1965). The upper sandstones probably represent littoral marine deposits since they grade upward into the dark-gray siltstones and marine shales of the Mancos Shale.

The Mancos shale is not exposed in the project vicinity. The nearest exposures are small isolated remnants resting conformably on Dakota Sandstone along the western rim above Recapture

Creek 4.3 to 5.5 miles (6.9 to 8.9 kilometers) southeast of the Mill site. Additional exposures are found on the eastern and southern flanks of the Abajo Mountains approximately 16 to 20 miles (26 to 32 kilometers) to the north. It is possible that thin patches of Mancos may be buried at the Mill site but are obscured by the mantle of alluvial windblown silt and sand covering the upland surface. The Upper Cretaceous Mancos shale is of marine origin and consists of dark- to olive-gray shale with minor amounts of gray, fine-grained, thin-bedded to blocky limestone and siltstone in the lower part of the formation. Bedding in the Mancos is thin and well developed, and much of the shale is laminated. Where fresh, the shale is brittle and fissile and weathers to chips that are light- to yellowish-gray. Topographic features formed by the Mancos are usually subdued and commonly displayed by low rounded hills and gentle slopes.


A layer of Quaternary to Recent reddish-brown eolian silt and fine sand is spread over the surface of the Mill site. Most of the loess consists of subangular to rounded frosted quartz grains that are coated with iron oxide. Basically, the loess is massive and homogeneous, ranges in thickness from a dust coating on the rocks that form the rim cliffs to more than 20 feet (6 meters), and is partially cemented with calcium carbonate (caliche) in light-colored mottled and veined accumulations which probably represent ancient immature soil horizons.

1.6.2.3 Structure (1978 ER Section 2.4.2.3)


The geologic structure at the Mill site is comparatively simple. Strata of the underlying Mesozoic sedimentary rocks are nearly horizontal; only slight undulations along the caprock rims of the upland are perceptible and faulting is absent. In much of the area surrounding the Mill site the dips are less than one degree. The prevailing regional dip is about one degree to the south. The low dips and simple structure are in sharp contrast to the pronounced structural features of the Comb Ridge Monocline to the west and the Abajo Mountains to the north.

The Mill area is within a relatively tectonically stable portion of the Colorado Plateau noted for its scarcity of historical seismic events. The epicenters of historical earthquakes from 1853

through 1986 within a 200-mile (320 km) radius of the site are shown in Figure 1.6-3. More than 1,146 events have occurred in the area, of which at least 45 were damaging; that is, having an intensity of VI or greater on the Modified Mercalli Scale. A description of the Modified Mercalli Scale is given in Table 1.6-3. All intensities mentioned herein refer to this table. Table 1.6-3 also shows a generalized relationship between Mercalli intensities and other parameters to which this review will refer. Since these relationships are frequently site specific, the table values should be used only for approximation and understanding. Conversely, the border between the Colorado Plateau and the Basin and Range Province and Middle Rocky Mountain



1146 EARTHQUAKES PLOTTED



NATIONAL GEOPHYSICAL DATA CENTER / NOAA BOULDER, CO 80303

After Umetco, 1988

Denison Mines (USA) Corp.		
Project: WHITE MESA MILL		
County: San Juan	State: Utah	
FIGURE 1.6-3 SEISMICITY WITHIN 320 KM OF THE WHITE MESA MILL		
Date: Nov. 2009	Design:	Drafted By: RAH

Table 1.6-3
Modified Mercalli Scale

Modified Mercalli Scale, 1956 Version ^a			v. † cm/s	g ‡
Intensity	Effects			
M	I.	Not felt. Marginal and long-period effects of large earthquakes (for details see text).		
	3	II. Felt by persons at rest on upper floors, or favorably placed.		
4	III.	Felt indoors. Hanging objects swing. Vibration like passing of light trucks. Duration estimated. May not be recognized as an earthquake.		0.0035-0.007
	IV.	Hanging objects swing. Vibration like passing of heavy trucks or sensation of a jolt like a heavy ball striking the walls. Standing motor cars rock. Windows, dishes, doors rattle. Glasses clink. Crockery clashes. In the upper range of IV wooden walls and frame creak.		0.007-0.015
	V.	Felt outdoors: direction estimated. Sleepers wakened. Liquids disturbed. Some spilled. Small unstable objects displaced or upset. Doors swing close, open. Shutters, pictures move. Pendulum clocks stop, start, change rate.	1-3	0.015-0.035
5	VI.	Felt by all. Many frightened and run outdoors. Persons walk unsteadily. Windows, dishes, glassware broken. Knickknacks, books, etc. off shelves. Pictures off walls. Furniture moved or overturned. Weak plaster and masonry D cracked. Small bells ring (church, school). Trees, bushes shaken (visibly, or heard to rustle - CFR).	3-7	0.035-0.07
	6	VII. Difficult to stand. Noticed by drivers of motor cars. Hanging objects quiver. Furniture broken. Damage to masonry D including cracks. Weak chimneys broken at roof line. Fall of plaster, loose bricks, stones, tiles, cornices (also unbraced parapets and architectural ornaments - CFR). Some cracks in masonry C. Waves on ponds: water turbid with mud. Small slides and caving in along sand or gravel banks. Large bells ring. Concrete irrigation ditches damaged.	7-20	0.07-0.15
7	8	VIII. Steering of motor cars affected. Damage to masonry C; partial collapse. Some damage to masonry B; none is masonry A. Fall of stucco and some masonry walls. Twisting, fall of chimneys, factory stacks, monuments, towers, elevated tanks. Frame houses moved on foundations if not bolted down; loose panel walls thrown out. Decayed piling broken off. Branches broken from trees. Changes in flow or temperature of springs and wells. Cracks in wet ground and on steep slopes.	20-80	0.15-0.35
	9	IX. General panic. Masonry D destroyed, masonry C heavily damaged. Sometimes with complete collapse, masonry B seriously damaged. (General damage to foundations - CFR). Frame structures, if not bolted, shifted off foundations. Frames rocked. Serious damage to reservoirs. Underground pipes broken. Conspicuous cracks in ground. In alluviated areas sand and mud ejected, earthquake fountains, sand craters.	.80-200	0.35-0.7
	10	X. Most masonry and frame structures destroyed with their foundations. Some well-built wooden structures and bridges destroyed. Serious damage to dams, dikes, embankments. Large landslides. Water thrown on banks of canals, rivers, lakes, etc. Sand and mud shifted horizontally on beaches and flat land. Rails bent slightly.	200-500	0.7-1.2
8	11	XI. Rails bent greatly. Underground pipelines completely out of service.		>1.2
	12	XII. Damage nearly total. Large rock masses displaced. Lines of sight and level distorted. Objects thrown into the air.	From Fig. 11.14	

Note: Masonry A, B, C, D. To avoid ambiguity of language, the quality of masonry, brick or otherwise, is specified by the following lettering (which has no connection with the conventional Class A, B, C construction).


- Masonry A : Good workmanship, mortar, and design reinforced, especially laterally, and bound together by using steel, concrete, etc.; designed to resist lateral forces.
- Masonry B: Good workmanship and mortar; reinforced, but not designed to resist lateral forces.
- Masonry C: Ordinary workmanship and mortar; no extreme weaknesses such as non-ded-ia corners, but masonry is neither reinforced nor designed against horizontal forces.
- Masonry D : Weak materials such as adobe, poor mortar, low standards of workmanship, weak horizontally.

^aFrom Richter (1958). ¹Adapted with permission of W. H. Freeman and Company by Hunt (1984).
†Average peak ground velocity, cm/s.
‡Average peak acceleration (away from source).
§Magnitude correlation.


Province some 155 to 240 miles (249 to 386 km) west and northwest, respectively, from the site is one of the most active seismic belts in the western United States.

Only 63 non-duplicative epicenters have been recorded within a 120 mile (200 km) radius of the Mill area (Figure 1.6-4). Of these, 50 had an intensity IV or less (or unrecorded) and two were recorded as intensity VI. The nearest event occurred in the Glen Canyon National Recreation Area approximately 38 miles (63 km) west-northwest of the Mill area. The next closest event occurred approximately 53 miles (88 km) to the northeast. Just east of Durango, Colorado, approximately 99 miles (159 km) due east of the Mill area, an event having local intensity of V was recorded on August 29, 1941 (Hadsell, 1968). It is very doubtful that these events would have been felt in the vicinity of Blanding.

Three of the most damaging earthquakes associated with the seismic belt along the Colorado Plateau's western border have occurred in the Elsinore-Richfield area about 168 miles (270 km) northwest of the Mill site. All were of intensity VIII. On November 13, 1901, a strong shock caused extensive damage from Richfield to Parowan. Many brick structures were damaged; rockslides were reported near Beaver. Earthquakes with the ejection of sand and water were reported, and some creeks increased their flow. Aftershocks continued for several weeks (von Hake, 1977). Following several weeks of small foreshocks, a strong earthquake caused major damage in the Monroe-Elsinore-Richfield area on September 29, 1921. Scores of chimneys were thrown down, plaster fell from ceilings, and a section of a new two-story brick wall collapsed at Elsinore's schoolhouse. Two days later, on October 1, 1921, another strong tremor caused additional damage to the area's structures. Large rockfalls occurred along both sides of the Sevier Valley and hot springs were discolored by iron oxides (von Hake, 1977). It is probable that these shocks may have been perceptible at the Mill site but they certainly would not have caused any damage.



103 EARTHQUAKES PLOTTED



NATIONAL GEOPHYSICAL DATA CENTER / NOAA BOULDER, CO 80303


Denison Mines (USA) Corp.		
Project: WHITE MESA MILL		
County: San Juan	State: Utah	
FIGURE 1.6-4 SEISMICITY WITHIN 200 KM OF THE WHITE MESA MILL		
Date: Nov. 2009	Design:	Drafted By: RAH

After Umetco, 1988

Seven events of intensity VII have been reported within 320 kilometers (km) around Blanding, Utah, which is the area shown in Figure 1.6-3. Of these, only two are considered to have any significance with respect to the Mill site. On August 18, 1912, an intensity VII shock damaged houses in northern Arizona and was felt in Gallup, New Mexico, and southern Utah. Rock slides occurred near the epicenter in the San Francisco Mountains and a 50-mile (80 km) earth crack was reported north of the San Francisco Range (Cater, 1970). Nearly every building in Dulce, New Mexico, was damaged to some degree when shook by a strong earthquake on January 22, 1966. Rockfalls and landslides occurred 10 to 15 miles (16 to 24 km) west of Dulce along Highway 17 where cracks in the pavement were reported (Hermann et al., 1980). Both of these events may have been felt at the Mill site but, again, would certainly not have caused any damage. Figure 1.6-4 shows the occurrence of seismic events within 200 km of Blanding.

1.6.2.4 Relationship of Earthquakes to Tectonic Structures

The majority of recorded earthquakes in Utah have occurred along an active belt of seismicity that extends from the Gulf of California, through western Arizona, central Utah, and northward into western British Columbia. The seismic belt is possibly a branch of the active rift system associated with the landward extension of the East Pacific Rise (Cook and Smith, 1967). This belt is the Intermountain Seismic Belt shown in Figure 1.6-5 (Smith, 1978).



Modified from Smith, 1978

SHOWS RELATIONSHIP OF THE COLORADO PLATEAU PROVINCE TO MARCANAL BELTS

After Umetco, 1988

Denison Mines (USA) Corp.		DENISON MINES	
Project:		WHITE MESA MILL	
County:	San Juan	State:	Utah
FIGURE 1.6-5 SEISMICITY OF THE WESTERN UNITED STATES 1950 TO 1976			
Date:	Nov. 2009	Design:	Drafted By: RAH

It is significant to note that the seismic belt forms the boundary zone between the Basin and Range - Great Basin Provinces and the Colorado Plateau - Middle Rocky Mountain Provinces. This block-faulted zone is about 47 to 62 miles (75 to 100 km) wide and forms a tectonic transition zone between the relatively simple structures of the Colorado Plateau and the complex fault-controlled structures of the Basin and Range Province (Cook and Smith, 1967).


Another zone of seismic activity is in the vicinity of Dulce, New Mexico, near the Colorado border. This zone, which coincides with an extensive series of tertiary intrusives, may also be related to the northern end of the Rio Grande Rift. This rift is a series of fault-controlled structural depressions extending southward from southern Colorado through central New Mexico and into Mexico. The rift is shown on Figure 1.6-5 trending north-south to the east of the Mill area.

Most of the events south of the Utah border of intensity V and greater are located within 50 miles (80 km) of post-Oligocene extrusives. This relationship is not surprising because it has been observed in many other parts of the world (Hadsell, 1968).

In Colorado, the Rio Grande Rift zone is one of three siesmotectonic provinces that may contribute energy to the study area. Prominent physiographic expression of the rift includes the San Luis Valley in southern Colorado. The valley is a half-graben structure with major faulting on the eastern flank. Extensional tectonics is dominant in the area and very large earthquakes with recurrence intervals of several thousand years have been projected (Kirkham and Rodgers, 1981). Mountainous areas to the west of the Rio Grande rift province include the San Juan Mountains. These mountains are a complex domicil uplift with extensive Oligocene and Miocene volcanic cover. Many faults are associated with the collapse of the calderas and apparently have not moved since. Faults of Neogene age exist in the eastern San Juan Mountains that may be related to the extension of the Rio Grande rift. Numerous small earthquakes have been felt or recorded in the western mountainous province despite an absence of major Neogene tectonic faults (Kirkham and Rodgers, 1981).

The third seismotectonic province in Colorado, that of the Colorado Plateau, extends into the surrounding states to the west and south. In Colorado, the major tectonic element that has been recurrently active in the Quaternary is the Uncompahgre uplift. Both flanks are faulted and earthquakes have been felt in the area. The faults associated with the Salt Anticlines are collapsed features produced by evaporite solution and flowage (Cater, 1970). Their non-tectonic origin and the plastic deformation of the salt reduce their potential for generating even moderate-sized earthquakes (Kirkham and Rodgers, 1981).

Case and Joesting (1972) have called attention to the fact that regional seismicity of the Colorado Plateau includes a component added by basement faulting. They inferred a basement fault trending northeast along the axis of the Colorado River through Canyonlands. This basement faulting may be part of the much larger structure that Hite (1975) examined and Warner (1978) named the Colorado lineament (Figure 1.6-6). This 1,300-mile (2,100 km) long lineament that extends from northern Arizona to Minnesota is suggested to be a Precambrian wrench-fault system formed some 2.0 to 1.7 billion years before present. While it has been suggested that the Colorado lineament is a source zone for larger earthquakes ($m = 4$ to 6) in the west-central United States, the observed spatial relationship between epicenters and the trace of the lineament does not prove a casual relation (Brill and Nuttli, 1983). In terms of contemporary seismicity, the lineament does not act as a uniform earthquake generator. Only specific portions of the proposed structure can presently be considered seismic source zones and each segment exhibits seismicity of distinctive activity and character (Wong, 1981). This is a reflection of the different orientations and magnitudes of the stress fields along the lineament. The interior of the Colorado Plateau forms a tectonic stress province, as defined by Zoback and Zoback (1980), that is characterized by generally east-west tectonic compression. Only where extensional stresses from the Basin and Range province of the Rio Grande rift extend into the Colorado Plateau would the Colorado lineament in the local area be suspected of having the capability of generating a large magnitude earthquake (Wong, 1984). At the present time, the well-defined surface expression of regional extension is far to the west and far to the east of the Mill area.



SOURCE: WARNER, 1978

After Umetco, 1988

Denison Mines (USA) Corp.			
Project:		WHITE MESA MILL	
County:	San Juan	State:	Utah
FIGURE 1.6-6 COLORADO LINEAMENT			
Date:	Nov. 2009	Design:	
		Drafted By:	RAH

Work by Wong (1984) has helped define the seismicity of the whole Colorado Plateau. He called attention to the low level (less than $ML = 3.6$) but high number (30) of earthquakes in the Capitol Reef Area from 1978 to 1980 that were associated with the Waterpocket fold and the Cainville monocline, two other major tectonic features of the Colorado Plateau. Only five earthquakes in the sequence were of ML greater than three, and fault plane solutions suggest the swarm was produced by normal faulting along northwest-trending Precambrian basement structures (Wong, 1984). The significance of the Capitol Reef seismicity is its relatively isolated occurrence within the Colorado Plateau and its location at a geometric barrier in the regional stress field (Aki, 1979). Stress concentration that produces earthquakes at bends or junctures of basement faults as indicated by this swarm may be expected to occur at other locations in the Colorado Plateau Province. No inference that earthquakes such as those at Capitol Reef are precursors for larger subsequent events is implied.

1.6.2.5 Potential Earthquake Hazards to Mill Area

The Mill site is located in a region known for its scarcity of recorded seismic events. Although the seismic history for this region is barely 135 years old, the epicentral pattern, or fabric, is basically set and appreciable changes are not expected to occur. Most of the larger seismic events in the Colorado Plateau have occurred along its margins rather than in the interior central region. Based on the region's seismic history, the probability of a major damaging earthquake occurring at or near the Mill site is very remote. Studies by Algermissen and Perkins (1976) indicate that southeastern Utah, including the site, is in an area where there is a 90 percent probability that a horizontal acceleration of four percent gravity ($0.04g$) would not be exceeded within 50 years. In 2002, the USGS updated the National Seismic Hazard Maps (NSHM), which show peak ground and spectral accelerations at 2 percent and 10 percent probability of exceedance in 50 years. From these maps, it is determined that there is a 98 percent probability that a horizontal acceleration of $0.09g$ would not be exceeded within 50 years (Tetra Tech, 2006). Furthermore, an updated seismic hazard analysis performed by Tetra Tech (2010) for the site determined that there is a 98 percent probability that a horizontal acceleration of $0.15g$ would

not be exceeded within a 200-year design life of the tailings cells. The Tetra Tech (2010) report is included in Appendix D.

1.6.3 Seismic Risk Assessment

Static and pseudostatic analyses were performed to establish the stability of the side slopes of the tailings cells. These analyses, together with analyses of radon flux attenuation, infiltration, freeze/thaw effects, biointrusion, settlement, liquefaction, dewatering, and erosion protection, are summarized below, and are detailed in Appendix D.

The side slopes are designed at an angle of 5H:1V. Because the side slope along the southern section of Cell 4A is the longest and the ground elevation drops rapidly at its base, this slope was determined to be critical and is thus the focus of the stability analyses.

Slope stability analyses were performed for both static and pseudostatic loading conditions, as discussed further in Section 3.3. These data and results are included in Appendix E of the Updated Tailings Cover Design Report (MWH, 2011b), attached to the Reclamation Plan as Appendix D.

1.6.3.1 Static Analysis

For the static analysis, a Factor of Safety ("FOS") of 1.5 or more was used to indicate an acceptable level of stability. The calculated FOS is 4.30, which indicates that the slope should be stable under static conditions. Results of the computer model simulations are included in Appendix E of the Updated Tailings Cover Design Report, included as Appendix D to this report.

1.6.3.2 Pseudostatic Analysis (Seismicity)

The slope stability analysis described above was repeated under pseudostatic conditions in order to estimate a FOS for the slope when a seismic coefficient of 0.10g is applied. This seismic coefficient corresponds to a peak ground acceleration of 0.15g at the site (Tetra Tech, 2010), a more conservative value than was used in previous analyses by Titan (1996). The slope geometry and material properties used in the pseudostatic analysis are identical to those used in the static stability analysis. A FOS of 1.1 or more was used to indicate an acceptable level of stability under pseudostatic conditions. The calculated FOS is 2.82, which indicates that the slope should be stable under dynamic conditions. Details of the analysis and the simulation results are included in Appendix E of the Updated Tailings Cover Design Report, attached to the Reclamation Plan as Appendix D.

1.7 Biota (1978 ER Section 2.9)

1.7.1 Terrestrial (1978 ER Section 2.9.1)

1.7.1.1 Flora (1978 ER Section 2.9.1.1)

The natural vegetation presently occurring within a 25-mile (40-km) radius of the site is very similar to that of the potential, being characterized by pinyon-juniper woodland intergrading with big sagebrush (*Artemisia tridentata*) communities. The pinyon-juniper community is dominated by Utah juniper (*Juniperus osteosperma*) with occurrences of pinyon pine (*Pinus edulis*) as a codominant or subdominant tree species. The understory of this community, which is usually quite open, is composed of grasses, forbs, and shrubs that are also found in the big sagebrush communities. Common associates include galleta grass (*Hilaria jamesii*), green ephedra (*Ephedra viridis*), and broom snakewood (*Gutierrezia sarothrae*). The big sagebrush communities occur in deep, well-drained soils on flat terrain, whereas the pinyon-juniper woodland is usually found on shallow rocky soil of exposed canyon ridges and slopes.

Seven community types are present on the Mill site (Table 1.7-1 and Figure 1.7-1). Except for the small portions of pinyon-juniper woodland and the big sagebrush community types, the majority of the plant communities within the site boundary have been disturbed by past grazing and/or treatments designed to improve the site for rangeland. These past treatments include chaining, plowing, and reseeding with crested wheatgrass (*Agropyron desertorum*). Controlled big sagebrush communities are those lands containing big sagebrush that have been chained to stimulate grass production. In addition, these areas have been seeded with crested wheatgrass. Both grassland communities I and II are the result of chaining and/or plowing and seeding with crested wheatgrass. The reseeded grassland II community is in an earlier stage of recovery from disturbance than the reseeded grassland I community. The relative frequency, relative cover, relative density, and importance values of species sampled in each community are presented in Dames and Moore (1978b), Table 2.8-2. The percentage of vegetative cover in 1977 was lowest on the reseeded grassland II community (10.7 percent) and highest on the big sagebrush community (33 percent) (Table 1.7-2).

Based upon dry weight composition, most communities on the site were in poor range condition in 1977 (Dames & Moore (1978b), Tables 2.8-3 and 2.8-4). Pinyon-juniper, big sagebrush, and controlled big sagebrush communities were in fair condition. However, precipitation for 1977 at the Mill site was classed as drought conditions (Dames & Moore (1978b), Section 2.8.2.1). Until July, no production was evident on the site.

Based on the work completed by Dames & Moore in the 1978 ER, no designated or proposed endangered plant species occur on or near the Mill site (Dames & Moore (1978b), Section 2.8.2.1). Of the 65 proposed endangered species in Utah at that time, six have documented distributions on San Juan County. A careful review of the habitat requirements and known distributions of these species by Dames & Moore in the 1978 ER indicated that, because of the disturbed environment, these species would probably not occur on the Mill site. The Navajo Sedge has been added to the list as a threatened species since the 1978 ER.

**Table 1.7-1
Community Types and Expanse Within the Project site
Boundary**


Community Type	Expanse	
	Ha	Acres
Pinyon-juniper Woodland	5	13
Big Sagebrush	113	278
Reseeded Grassland I	177	438
Reseeded Grassland II	121	299
Tamarisk-salix	3	7
Controlled Big Sagebrush	230	569
Disturbed	17	41

**Table 1.7-2
Ground Cover For Each Community Within the Project Site Boundary**


Community Type	Percentage of Each Type of Cover		
	Vegetative Cover	Litter	Bare Ground
Pinyon-juniper Woodland ^a	25.9	15.6	55.6
Big Sagebrush	33.3	16.9	49.9
Reseeded Grassland I	15.2	24.2	61.0
Reseeded Grassland II	10.7	9.5	79.7
Tamarisk-salix	12.0	20.1	67.9
Controlled Big Sagebrush	17.3	15.3	67.4
Disturbed	13.2	7.0	80.0

^aRock covered 4.4% of the ground.

\\dmcrfs01\MASTER DRAWINGS\USA\Utah\Mill\dwgs\Reclamation Plans\Rev_07-2011\Work01_Harold\Fig.1.7-1_Vegetation.dwg Layout1 G.Moseley



- Pinyon - Juniper
- Reseeded Grassland I
- Reseeded Grassland II
- Big Sagebrush
- Controlled Big Sagebrush
- Disturbed



Denison Mines (USA) Corp

Project: White Mesa Mill	
Date: 11-09	By: DLS
Location: County: San Juan State: UT	
VEGETATION COMMUNITY TYPES ON THE WHITE MESA MILL SITE	
FIGURE 1.7-1	
Author:	Drafted By: RAH
Date: May 1999	

In completing the 2002 EA, NRC staff contacted wildlife biologists from the BLM and the Utah Wildlife Service to gather local information on the occurrences of additional species surrounding the Mill. In the 2002 EA, NRC staff concluded that the Navajo Sedge has not been observed in the area surrounding Blanding, and is typically found in areas of moisture (2002 EA at 4).

1.7.1.2 Fauna (1978 ER Section 2.9.1.2)

Wildlife data have been collected through four seasons at several locations on the site. The presence of a species was based on direct observations, trappings and signs such as the occurrence of scat, tracks, or burrows. A total of 174 vertebrate species potentially occur within the vicinity of the mill (Dames & Moore (1978b), Appendix D, previously submitted), 78 of which were confirmed (Dames & Moore (1978b), Section 2.8.2.2).

Although seven species of amphibians are thought to occur in the area, the scarcity of surface water limits the use of the site by amphibians. The tiger salamander (*Ambystoma tigrinum*) was the only species observed. It appeared in the pinyon-juniper woodland west of the Mill site (Dames & Moore (1978b), Section 2.8.2.2).

Eleven species of lizards and five snakes potentially occur in the area. Three species of lizards were observed: the sagebrush lizard (*Sceloporus graciosus*), western whiptail (*Cnemidophorus tigris*), and the short-horned lizard (*Phrynosoma douglassi*) (Dames & Moore (1978b), Section 2.8.2.2). The sagebrush and western whiptail lizard were found in sagebrush habitat, and the short-horned lizard was observed in the grassland. No snakes were observed during the field work.

Fifty-six species of birds were observed in the vicinity of the Mill site (Table 1.7-3). The abundance of each species was estimated by using modified Emlen transects and roadside bird counts in various habitats and seasons. Only four species were observed during the February

**Table 1.7-3
Birds Observed in the Vicinity of the White Mesa Project**

Species	Relative Abundance and Status ^a	Species	Relative Abundance and Status ^a
Mallard	CP	Pinyon Jay	CP
Pintail	CP	Bushtit	CP
Turkey Vulture	US	Bewick's Wren	CP
Red-tailed Hawk	CP	Mockingbird	US
Golden Eagle	CP	Mountain Bluebird	CS
Marsh Hawk	CP	Black-tailed Gnatcatcher	H
Merlin	UW	Ruby-crowned Kinglet	CP
American Kestrel	CP	Loggerhead Shrike	CS
Sage Grouse	UP	Starling	CP
Scaled Quail	Not Listed	Yellow-rumped Warbler	CS
American Coot	CS	Western Meadowlark	CP
Killdeer	CP	Red-winged Blackbird	CP
Spotted Sandpiper	CS	Brewer's Blackbird	CP
Mourning Dove	CS	Brown-headed Cowbird	CS
Common Nighthawk	CS	Blue Grosbeak	CS
White-throated Swift	CS	House Finch	CP
Yellow-bellied Sapsucker	CP	American Goldfinch	CP
Western Kingbird	CS	Green-tailed Towhee	CS
Ash-throated Flycatcher	CS	Rufous-sided Towhee	CP
Say's Phoebe	CS	Lark Sparrow	CS
Horned Lark	CP	Black-throated Sparrow	CS
Violet-green Swallow	CS	Sage Sparrow	UC

Barn Swallow	CS	Dark-eyed Junco	CW
Cliff Swallow	CS	Chipping Sparrow	CS

Table 1.7-3

Birds Observed in the Vicinity of the White Mesa Project (continued)

Species	Relative Abundance and Status ^a	Species	Relative Abundance and Status ^a
Scrub Jay	CP	Brewer's Sparrow	CS
Black-billed Magpie	CP	White-crowned Sparrow	CS
Common Raven	CP	Song Sparrow	CP
Common Crow	CW	Vesper Sparrow	CS

^aW. H. Behle and M. L. Perry, *Utah Birds*, Utah Museum of Natural History, University of Utah, Salt Lake City, 1975.

Relative Abundance

C = Common

U = Uncommon

H = Hypothetical

Status

P = Permanent

S = Summer Resident

W = Winter Visitant

Source: Dames & Moore (1978b), Table 2.8-5

sampling. The most abundant species was the horned lark (*Eremophila aepestis*) followed by the common raven (*Corvus corax*), which were both concentrated in the grassland. Avian counts increased drastically in May. Based on extrapolation of the Emlen transect data, the avian density on grassland of the Mill site during spring was about 123 per 100 acres (305 per square kilometer). Of these individuals, 94 percent were horned larks and western meadowlarks (*Sturnella neglecta*). This density and species composition are typical of rangeland habitats. In late June the species diversity declined somewhat in grassland but peaked in all other habitats. By October the overall diversity decreased but again remained the highest in grassland.

Raptors are prominent in the western United States. Five species were observed in the vicinity of the site (Table 1.7-3). Although no nests of these species were located, all (except the golden eagle, *Aquila chrysaetos*) have suitable nesting habitat in the vicinity of the site. The nest of a prairie falcon (*Falco mexicanus*) was found about 3/4 mile (1.2 km) east of the site. Although no sightings were made of this species, members tend to return to the same nests for several years if undisturbed (Dames & Moore (1978b), Section 2.8.2.2).

Of several mammals that occupy the site, mule deer (*Odocoileus hemionus*) is the largest species. The deer inhabit the project vicinity and adjacent canyons during winter to feed on the sagebrush and have been observed migrating through the site to Murphy Point (Dames & Moore (1978b), Section 2.8.2.2). Winter deer use of the project vicinity, as measured by browse utilization, is among the heaviest in southeastern Utah [25 days of use per acre (61 days of use per hectare) in the pinyon-juniper-sagebrush habitats in the vicinity of the Mill site]. In addition, this area is heavily used as a migration route by deer traveling to Murphy Point to winter. Daily movement during winter periods by deer inhabiting the area has also been observed between Westwater Creek and Murphy Point. The present size of the local deer herd is not known.

Other mammals present at the site include the coyote (*Canis latrans*), red fox (*Vulpes vulpes*), gray fox (*Urocyon cinereoargenteus*), striped skunk (*Mephitis mephitis*), badger (*taxidea taxus*), longtail weasel (*Mustela frenata*), and bobcat (*Lynx rufus*). Nine species of rodents were trapped

or observed on the site, the deer mouse (*Peromyscus maniculatus*) having the greatest distribution and abundance. Although desert cottontails (*Sylvilagus auduboni*) were uncommon in 1977, black-tailed jackrabbits (*Lepus californicus*) were seen during all seasons.

In the 2002 EA, NRC staff noted that, in the vicinity of the site, the U.S. Fish and Wildlife Service had provided the list set out in Table 3.12-1, of the endangered, threatened, and candidate species that may occur in the area around the site.

**Table 1.7-4
Endangered, Threatened and Candidate Species in the Mill Area**

Common Name	Scientific Name	Status
Navajo Sedge	<i>Carex specuicola</i>	Threatened
Bonytail Chub	<i>Gila elegans</i>	Endangered
Colorado Pikeminnow	<i>Ptychocheilus Lucius</i>	Endangered
Humpback Chub	<i>Gila cypha</i>	Endangered
Razorback Sucker	<i>Xyrauchen texanus</i>	Endangered
Bald Eagle	<i>Haliaeetus leucocephalus</i>	Threatened
California Condor	<i>Gymnogyps californianus</i>	Endangered
Gunnison Sage Grouse	<i>Centrocercus minimus</i>	Candidate
Mexican Spotted Owl	<i>Strix occidentalis lucida</i>	Threatened
Southwestern Willow Flycatcher	<i>Empidonax traillii extimus</i>	Endangered
Western Yellow-billed Cuckoo	<i>Coccyzus americanus occidentalis</i>	Candidate
Black-footed Ferret	<i>Mustela nigripes</i>	Endangered

Source: 2002 EA

The 2002 EA also noted that, in addition, the species listed on Table 3.12-2 may occur within the Mill area that are managed under Conservation Agreements/Strategies.

Table 1.7-5
Species Managed Under Conservation Agreements/Strategies at the Mill Area

Common Name	Scientific Name
Colorado River Cutthroat Trout	<i>Oncorhynchus clarki pleuriticus</i>
Gunnison Sage Grouse	<i>Centrocercus minimus</i>

Source: 2002 EA

For the 2002 EA, NRC staff contacted wildlife biologists from the BLM and the Utah Wildlife Service to gather local information on the occurrences of these additional species surrounding the Mill. NRC staff made the following conclusions (2002 EA p. 4):

While the ranges of the bald eagle, peregrine falcon, and willow flycatcher encompass the project area, their likelihood of utilizing the site is extremely low. The black-footed ferret has not been seen in Utah since 1952, and is not expected to occur any longer in the area. The California Condor has only rarely been spotted in the area of Moab, Utah, (70 miles north) and around Lake Powell (approximately 50 miles south). The Mexican Spotted Owl is only found in the mountains in Utah, and is not expected to be on the Mesa. The Southwestern Willow Flycatcher, Western Yellow-billed Cuckoo, and Gunnison Sage Grouse are also not expected to be found in the immediate area around the Mill site.

1.7.2 Aquatic Biota (1978 ER Section 2.9.2)

Aquatic habitat at the Mill site ranges temporally from extremely limited to nonexistent due to the aridity, topography and soil characteristics of the region and consequent dearth of perennial surface water. Two small stock watering ponds, are located on the Mill site a few hundred yards from the ore pad area (See Figure 1.5-3 above). One additional small “wildlife pond”, east of Cell 4A, was completed in 1994 to serve as a diversionary feature for migrating waterfowl (see Figure 1.5-3 above). Although more properly considered features of the terrestrial environment,

they essentially represent the total aquatic habitat on the Mill site. These ponds probably harbor algae, insects, other invertebrate forms, and amphibians.

They also provide a water source for small mammals and birds. Similar ephemeral catch and seepage basins are typical and numerous to the northeast of the Mill site and south of Blanding.

Aquatic habitat in the project vicinity is similarly limited. The three adjacent streams (Corral Creek, Westwater Creek, and an unnamed arm of Cottonwood Wash) are only intermittently active, carrying water primarily in the spring during increased rainfall and snowmelt runoff, in the autumn, and briefly during localized but intense electrical storms. Intermittent water flow most typically occurs in April, August, and October in those streams. Again, due to the temporary nature of these streams, their contribution to the aquatic habitat of the region is probably limited to providing a water source for wildlife and a temporary habitat for insect and amphibian species.

In the 2002 EA, NRC staff concluded that (p. 4) no populations of fish are present on the project site, nor are any known to exist in the immediate area of the site. Four species of fish designated as endangered or threatened (the Bonytail Chub, Colorado Pikeminnow, Humpback Chub and Razorback Sucker) occur in the San Juan River 18 miles south of the site, which Dames & Moore noted in the 1978 ER (Section 2.8.2) is the closest habitat suitable for these species. NRC staff further concluded that there are no discharges of Mill effluents to surface waters, and therefore, no impacts are expected for the San Juan River due to operations of the Mill.

1.7.3 Background Radiation (2007 ER, Section 3.13.1)

All living things are continuously exposed to ionizing radiation from a variety of sources including cosmic and cosmogenic radiation from space and external radiation from terrestrial radionuclides such as uranium, thorium and potassium-40 that occur in the earth's crust, in building materials, in the air we breathe, the food we eat, the water we drink and in our bodies.

Some exposures, such as that from potassium-40, are controlled by our body's metabolism and are relatively constant throughout the world, but exposures from sources such as uranium and thorium in soils and especially from radon in homes can vary greatly, by more than a factor of ten, depending on location.

In order to provide a context for exposures potentially attributable to radioactive emissions from processing ores and alternate feed materials at the Mill, this section provides some general background information on exposures to natural background radiation worldwide, in the United States and in the Colorado Plateau region where the Mill is located.

1.7.3.1 The World

In general terms, the worldwide breakdown of natural background radiation sources can be summarized as follows (UNSCEAR, 2000):

Cosmic and Cosmogenic	39 mrem/yr
Terrestrial	48 mrem/yr
Inhaled (Radon)	126 mrem/yr
Ingested	29 mrem /yr
Total (Average)	242 mrem/yr (116 mrem/yr excluding radon)

According to the United Nations Scientific Committee on the Effects of Atomic Radiation ("UNSCEAR"), the actual doses can vary considerably from the nominal values listed above, and around the world vary from this value by more than a factor of 10. For example, the dose from cosmic and cosmogenic radiation varies with altitude. The higher the altitude, the less is the protection offered by the earth's atmosphere. The dose from external gamma radiation can vary greatly depending on the levels of uranium and thorium series radionuclides in the local soil. One example is the elevated gamma fields seen on natural sands containing heavy minerals as for example in regions around the Indian Ocean, in Brazil, and New Jersey. The high

variability in indoor radon concentrations is a major source of the variation in natural background dose. The variability in the dose from radon arises from many factors, including: variability in soil radium concentrations from place to place; variation both over time and location in housing stock, heating and ventilating systems; and variations in individual habits. The worldwide average ambient (i.e. outdoor) radon concentration is about 10 Bq/m³ (UNSCEAR, 2000) and the world average concentration of U-238 and Th-232 in soils is about 0.7 pCi/g (25 Bq/kg) (NRC, 1994).

The definition of “background radiation” in 10 CFR 20.1003 specifically includes global fallout as it exists in the environment from the testing of nuclear explosive devices or from past nuclear accidents such as Chernobyl that contribute to background radiation and are not under the control of the licensee. The calculation of background radiation in this Section 3.13.1 is conservative because it does not include such fallout in background radiation for the Mill site.

1.7.3.2 United States

In the United States, nominal average levels of natural background radiation are as follows (National Council of Radiation Protection and Measurements (“NCRP”), 1987):

Cosmic and Cosmogenic	28 mrem/yr
Terrestrial	28 mrem/yr
Inhaled (Radon)	200 mrem/yr
Ingested	40 mrem /yr
Total (Average)	296 mrem/yr (96 mrem/yr excluding radon)

As shown above, in the United States, the average annual dose from natural background radiation is about 296 mrem/yr (including radon). The actual annual dose from natural background varies by region within the United States. For example, the average dose from external terrestrial radiation for a person living on the Colorado Plateau is in the order of 63

mrem/yr, which is considerably higher than the average dose from terrestrial radiation for a person living in Florida, where the average annual dose from external terrestrial radiation is only about 16 mrem/yr. (NRC, 1994; NCRP, 1987). No comparison made. In the United States, outdoor radon levels vary widely from about 0.1 pCi/l in New York City to about 1.2 pCi/L in Colorado Springs (NCRP, 1987), generally consistent with nominal worldwide values noted in the previous section.

1.7.4 Mill Site Background (1978 ER Section 2.10)

Radiation exposure in the natural environment is due to cosmic and terrestrial radiation and to the inhalation of radon and its daughters. Measurements of the background environmental radioactivity were made at the Mill site using thermoluminescent dosimeters (“TLDs”). The results indicate an average total body dose of 142 millirems per year, of which 68 millirems is attributable to cosmic radiation and 74 millirems to terrestrial sources. The cosmogenic radiation dose is estimated to be about 1 millirem per year. Terrestrial radiation originates from the radionuclides potassium-40, rubidium-87, and daughter isotopes from the decay of uranium-238, thorium-232, and, to a lesser extent, uranium-235. The dose from ingested radionuclides is estimated at 18 millirems per year to the total body. The dose to the total body from all sources of environmental radioactivity is estimated to be about 161 millirems per year.

The concentration of radon in the area is estimated to be in the range of 500 to 1,000 pCi/m³, based on the concentration of radium-226 in the local soil. Exposure to this concentration on a continuous basis would result in a dose of up to 625 millirems per year to the bronchial epithelium. As ventilation decreases, the dose increases; for example, in unventilated enclosures, the comparable dose might reach 1,200 millirems per year.

The medical total body dose for Utah is about 75 millirems per year per person. The total dose in the area of the mill from natural background and medical exposure is estimated to be 236 millirems per year.

1.7.5 Current Monitoring Data

The most recent data for gamma, vegetation, air and stack sampling, groundwater, surface water, meteorological monitoring, and soil sampling discussed in the following sections are found in the Semi-Annual Effluent Report for January through June 2011, included as Appendix A. See Section 2.3.2.1 below for a more detailed discussion of the environmental monitoring programs at the Mill.

1.7.5.1 Environmental Radon

Until 10 CFR 20 standards were reduced to 0.1 pCi/l, environmental radon concentrations were determined by using Track Etch detectors. There was one detector at each of five environmental monitoring stations with a duplicate at BHV-2, the nearest residence. See the Semi-Annual Effluent reports, for maps showing these locations. After 1995, with concurrence of the NRC, environmental radon concentrations are no longer measured at these locations due to the lack of sensitivity of available monitoring methods to meet the new 10 CFR 20 standard of 0.1 pCi/l.

1.7.5.2 Environmental Gamma

Gamma radiation levels are determined by optically stimulated luminescence dosimeters (“OSLs”). The OLDs are placed at the five environmental stations located around the perimeter boundary of the mill site discussed above. The badges are exchanged quarterly. The data are presented in Appendix A.

1.7.5.3 Vegetation Samples

Vegetation samples are collected at three locations around the Mill periphery. The sampling locations are northeast, northwest, and southwest of the Mill facility. Vegetation samples are collected three times per year. Vegetation results are included in Appendix A. No trends are

apparent, as the Ra-226 and Pb-210 concentrations at each sampling location have remained consistent.

1.7.5.4 Environmental Air Monitoring and Stack Sampling

Air monitoring at the Mill is conducted at five high volume (40 standard cubic feet per minute) stations located around the periphery of the Mill. These locations are shown in Appendix A and on Figure 2.3-1. BHV-1 is located at the northern Mill boundary at the meteorological station site. BHV-2 is further north at the nearest residence. BHV-4 is south of Cell 3, BHV-5 is just south of the ore storage pad and BHV-6 is located on a vector between the Mill site and the White Mesa Ute Community. The Semi-Annual Effluent reports contain air monitoring data. The results of the quarterly stack samples are also presented in Appendix A.

Pursuant to NRC License Amendment No. 41 for the Mill's Source Material License No. SUA-1358, air particulate radionuclide monitoring at BHV-3 was discontinued at the end of the third quarter of 1995. Appendix A tables show the radionuclide concentrations at each location. No apparent trends are evident.

1.7.5.5 Surface Water

The results of surface water monitoring are presented in the Semi-Annual Effluent Reports. Cottonwood Creek is sampled Semi-annually and Westwater Creek is sampled on an annual basis. No trends are apparent.

1.7.5.6 Meteorological Monitoring

The Semi-Annual Air Quality and Meteorology Monitoring Report for January 1, 2011 through June 30, 2011 was provided by McVehil-Monnett and is included as Appendix F.

2 EXISTING FACILITY

The following sections describe the construction history of the Mill; the Mill and Mill tailings management facilities; Mill operations including the Mill circuit and tailings management; and both operational and environmental monitoring.

2.1 Facility Construction History

The Mill is a uranium/vanadium mill that was developed in the late 1970s by Energy Fuels Nuclear, Inc. (“EFN”) as an outlet for the many small mines that are located in the Colorado Plateau and for the possibility of Milling Arizona Strip ores. At the time of its construction, it was anticipated that high uranium prices would stimulate ore production. However, prices started to decline about the same time as Mill operations commenced.

As uranium prices fell, producers in the region were affected and mine output declined. After about two and one-half years, the Mill ceased ore processing operations altogether, began solution recycle, and entered a total shutdown phase. In 1984, a majority ownership interest was acquired by Union Carbide Corporation's (“UCC”) Metals Division which later became Umetco Minerals Corporation (“Umetco”), a wholly-owned subsidiary of UCC. This partnership continued until May 26, 1994 when EFN reassumed complete ownership. In May 1997, Denison (then named International Uranium (USA) Corporation) and its affiliates purchased the assets of EFN and is the current owner of the facility.

2.1.1 Mill and Tailings Management Facility

The Source Materials License Application for the Mill was submitted to the NRC on February 8, 1978. Between that date and the date the first ore was fed to the Mill grizzly on May 6, 1980, several actions were taken including: increasing Mill design capacity, permit issuance from the

United States Environmental Protection Agency (“EPA”) and the State of Utah, archeological clearance for the Mill and tailings areas, and an NRC pre-operational inspection on May 5, 1980.

Construction on the tailings area began on August 1, 1978 with the movement of earth from the area of Cell 2. Cell 2 was completed on May 4, 1980, Cell 1 on June 29, 1981, and Cell 3 on September 2, 1982. In January of 1990 an additional cell, designated Cell 4A, was completed and initially used solely for solution storage and evaporation. Cell 4A was only used for a short period of time and then taken out of service because of concerns about the synthetic lining system. In 2007, Cell 4A was retrofitted with a new State of Utah approved lining system and was authorized to begin accepting process solutions in September, 2008. Cell 4A was put back into service in October of 2008. Cell 4B was constructed in 2010 and authorized to begin accepting process solutions in February 2011.

2.2 Facility Operations

In the following subsections, an overview of Mill operations and operating periods are followed by descriptions of the operations of the Mill circuit and tailings management facilities.

2.2.1 Operating Periods

The Mill was operated by EFN from the initial start-up date of May 6, 1980 until the cessation of operations in 1983. Umetco, as per agreement between the parties, became the operator of record on January 1, 1984. The Mill was shut down during all of 1984. The Mill operated at least part of each year from 1985 through 1990. Mill operations again ceased during the years of 1991 through 1994. EFN reacquired sole ownership on May 26, 1994, and the Mill operated again during 1995 and 1996. After acquisition of the Mill by Denison and its affiliates several local mines were restarted and the Mill processed conventional ore during 1999 and early 2000. With the resurgence in uranium and vanadium prices in 2003, Denison reopened several area mines and again began processing uranium and vanadium ores in April of 2008. Mill operations

were suspended in May of 2009, and resumed in March of 2010. Typical employment figures for the Mill are 110 during uranium-only operations and 140 during uranium/vanadium operations.

Commencing in the early 1990s through today, the Mill has processed alternate feed materials from time to time when the Mill has not been processing conventional ores. Alternate feed materials are uranium-bearing materials other than conventionally mined uranium ores. The Mill installed an alternate feed circuit in 2009 that will allow the Mill to process certain alternate feed materials simultaneously with conventional ores.

2.2.2 Mill Circuit

While originally designed for a capacity of 1,500 dry tons per day (dtpd.), the Mill capacity was boosted to the present rated design of 1980 dtpd prior to commissioning.

The Mill uses an atmospheric hot acid leach followed by counter current decantation (CCD). This in turn is followed by a clarification stage which precedes the solvent extraction (SX) circuit. Kerosene containing iso-decanol and tertiary amines extracts the uranium and vanadium from the aqueous solution in the SX circuit. Salt and soda ash are then used to strip the uranium and vanadium from the organic phase.

After extraction of the uranium values from the aqueous solution in SX, uranium is precipitated with anhydrous ammonia, dissolved, and re-precipitated to improve product quality. The resulting precipitate is then washed and dewatered using centrifuges to produce a final product called "yellowcake." The yellowcake is dried in a multiple hearth dryer and packaged in drums weighing approximately 800 to 1,000 lbs. for shipping to converters.

After the uranium values are stripped from the pregnant solution in SX, the vanadium values are transferred to tertiary amines contained in kerosene and concentrated into an intermediate

product called vanadium product liquor (VPL). An intermediate product, ammonium metavanadate (AMV), is precipitated from the VPL using ammonium sulfate in batch precipitators. The AMV is then filtered on a belt filter and, if necessary, dried. Normally, the AMV cake is fed to fusion furnaces where it is converted to the Mill's primary vanadium product, V₂O₅ tech flake, commonly called "black flake."

The same basic process steps used for the recovery of uranium from conventional ores are used for the recovery of uranium from alternate feed materials, with some variations depending on the particular alternate feed material.

The Mill processed 1,511,544 tons of conventional ore and other materials from May 6, 1980 to February 4, 1983. During the second operational period from October 1, 1985 through December 7, 1987, 1,023,393 tons of conventional ore were processed. During the third operational period from July 1988 through November 1990, 1,015,032 tons of conventional ore were processed. During the fourth operational period from August 1995 through January 1996, 203,317 tons of conventional ore were processed. In the fifth operational period, from May 1996 through September 1996, the Mill processed 3,868 tons of calcium fluoride alternate feed material. From 1997 to early 1999, the Mill processed 58,403 tons from several additional alternate feed stocks.

With rising uranium prices in the late 1990s, company mines were reopened in 1997, and 87,250 tons of conventional ore were processed in 1999 and early 2000. In 2002 and 2003, the Mill processed 266,690 tons of alternate feed material from government cleanup projects. An additional 40,866 tons of alternate feed materials were processed in 2007. An additional 1,401 tons of alternate feed materials were processed in 2008 through July of 2011. From April 2008 through July 2011 the Mill processed an additional 722,843 tons of conventional ore.

Inception to date material processed through July, 2011 totals 4,934,607 tons. This total is for all processing periods and feeds combined.

2.2.3 Tailings Management Facilities

Tailings produced by the Mill from conventional ores typically contain 30 percent moisture by weight, have an in-place dry density of 86.3 pounds per cubic foot (calculated from Cell 2 volume and tons placed), have a size distribution with a significant -200 to -325 mesh size fraction, and have a high acid and flocculent content. Tailings from alternate feed materials that are similar physically to conventional ores, which comprise most of the tons of alternate feed materials processed to date at the Mill, are similar to the tailings for conventional ores. Tailings from some of the higher grade, lower volume alternate feed materials may vary somewhat from the tailings from conventional ores, primarily in moisture and density content.

The tailings facilities at the Mill currently consist of four cells as follows:

- Cell 1, constructed with a 30-Millimeter (ml) PVC earthen-covered liner, is used for the evaporation of process solution (Cell 1 was previously referred to as Cell 1-I, but is now referred to as Cell 1);
- Cell 2, constructed with a 30-Millimeter (ml) PVC earthen-covered liner, is used for the storage of barren tailings sands. This Cell is full and has been partially reclaimed;
- Cell 3, constructed with a 30-Millimeter (ml) PVC earthen-covered liner, is used for the storage of barren tailings sands and solutions. This cell is partially filled and has been partially reclaimed; and
- Cell 4A, constructed with a geosynthetic clay liner, a 60 Millimeter (mil) HDPE liner, a 300 mil HDPE geonet drainage layer, a second 60 mil HDPE liner, and a slimes drain network over the entire cell bottom. This cell was placed into service in October of 2008.
- Cell 4B, constructed with a geosynthetic clay liner, a 60 Millimeter (mil) HDPE liner, a 300 mil HDPE geonet drainage layer, a second 60 mil HDPE liner, and a slimes drain network over the entire cell bottom. This cell was placed into service in February of 2011.

Total estimated design capacity of Cells 2, 3, 4A, and 4B is approximately eight million (mm) tons. Figures 1.5-4 and 1.5-5 show the locations of the tailings cells.

2.2.3.1 Tailings Management

Constructed in shallow valleys or swale areas, the lined tailings facilities provide storage below the existing grade and reduce potential exposure. Because the cells are separate and distinct, individual tailings cells may be reclaimed as they are filled to capacity. This phased reclamation approach minimizes the amount of tailings exposed at any given time and reduces potential exposure to a minimum.

Slurry disposal has taken place in Cells 2, 3 and 4A. Tailings placement in Cell 2 and Cell 3 was accomplished by means of the final grade method, described below.

The final grade method used in Cell 2 and Cell 3 calls for the slurry to be discharged until the tailings surface comes up to near final grade. The discharge points are set up in the east end of the cell, and the final grade surface is advanced to the slimes pool area. Coarse tailings sand from the discharge points is graded into low areas to reach the final disposal elevation. When the slimes pool is reached, the discharge points are then moved to the west end of the cell and worked back to the middle. An advantage to using the final grade method is that maximum beach stability is achieved by (1) allowing water to drain from the sands to the maximum extent, and (2) allowing coarse sand deposition to help provide stable beaches. Another advantage is that radon release and dust prevention measures (through the placement of the initial layer of the final cover) are applied as expeditiously as possible.

Slurry disposal in Cell 4A is from several pre-determined discharge points located around the north and east sides of the cell. Slurry discharge is only allowed on skid pads, or protective HDPE sheets, to prevent damage to the synthetic lining system. Once tailings solids have reach the maximum elevation around the perimeter of the cell, discharge points can be moved toward

the interior of the cell. Slurry disposal in Cell 4B will be conducted in the same manner as Cell 4A. Cell 4B is currently only accepting process solutions.

2.2.3.2 Liquid Management

As a zero-discharge facility, the Mill must evaporate all of the liquids utilized during processing. This evaporation currently takes place in four (4) areas:

- Cell 1, which is used for solutions only;
- Cell 3, in which tailings and solutions exist;
- Cell 4A, in which tailings and solutions exist; and
- Cell 4B, presently used for solutions only.

The original engineering design indicated a net water gain into the cells would occur during Mill operations. As anticipated, this has been proven to be the case. In addition to natural evaporation, spray systems have been used at various times to enhance evaporative rates and for dust control. To minimize the net water gain, solutions are recycled back for use in the Mill circuit from the active tailings cells to the maximum extent possible. Solutions from Cells 1, 3, 4A, and 4B are brought back to the CCD circuit where metallurgical benefit can be realized. Recycle to other parts of the Mill circuit are not feasible due to the acidic condition of the solution.

2.3 Monitoring Programs

2.3.1 Monitoring and Reporting Under the Mill's GWDP

2.3.1.1 *Groundwater Monitoring*

a) Plugged and Excluded Wells

Wells MW-6, MW-7, and MW-8 were plugged because they were in the area of Cell 3, as was MW-13, in the Cell 4A area. Wells MW-9 and MW-10 are dry and have been excluded from the monitoring program. MW-16 is dry and has been plugged as part of the tailings Cell 4B construction.

b) Groundwater Monitoring at the Mill Prior to Issuance of the GWDP

At the time of renewal of the License by NRC in March, 1997 and up until issuance of the GWDP in March 2005, the Mill implemented a groundwater detection monitoring program to ensure compliance to 10 CFR Part 40, Appendix A, in accordance with the provisions of the License. The detection monitoring program was in accordance with the report entitled, *Points of Compliance, White Mesa Uranium Mill*, prepared by Titan Environmental Corporation, submitted by letter to the NRC dated October 5, 1994 (Titan, 1994b). Under that program, the Mill sampled monitoring wells MW-5, MW-11, MW-12, MW-14, MW-15 and MW-17, on a quarterly basis. Samples were analyzed for chloride, potassium, nickel and uranium, and the results of such sampling were included in the Mill's Semi-Annual Effluent Monitoring Reports that were filed with the NRC up until August 2004 and with the DRC subsequent thereto.

Between 1979 and 1997, the Mill monitored up to 20 constituents in up to 13 wells. That program was changed to the Points of Compliance Program in 1997 because NRC had concluded that:

- The Mill and tailings system had produced no impacts to the perched zone or deep aquifer; and
- The most dependable indicators of water quality and potential cell failure were considered to be chloride, nickel, potassium and natural uranium.

c) Issuance of the GWDP

On March 8, 2005, the Executive Secretary issued the GWDP, which includes a groundwater monitoring program that supersedes and replaces the groundwater monitoring requirements set out in the License. Groundwater monitoring under the GWDP commenced in March 2005, the results of which are included in the Mill's *Quarterly Groundwater Monitoring Reports* that are filed with the Executive Secretary.

d) Current Ground Water Monitoring Program at the Mill Under the GWDP


The current groundwater monitoring program at the Mill under the GWDP consists of monitoring at 25 point of compliance monitoring wells: MW-1, MW-2, MW-3, MW-3A, MW-5, MW-11, MW-12, MW-14, MW-15, MW-17, MW-18, MW-19, MW-23, MW-24, MW-25, MW-26, MW-27, MW-28, MW-29, MW-30, MW-31, MW-32, MW-35, MW-36, and MW-37. The locations of these wells are indicated on Figure 2.3-1.

PROPERTY
BOUNDARY


WESTWATER CREEK

US 191
TO BLANDING

US 191
TO WHITEMESA



- EXPLANATION**
- MW-20 ● perched monitoring well
 - TW4-19 ○ temporary perched monitoring well
 - PIEZ-1 ◐ perched piezometer
 - TWN-1 ◆ temporary perched nitrate monitoring well
 - MW-34 ◐ perched monitoring well installed August/September, 2010
 - MW-36 ⚙ perched monitoring well installed April, 2011



HYDRO
GEO
CHEM, INC.

**SITE PLAN
AND PERCHED WELL LOCATIONS
WHITE MESA SITE**

APPROVED	DATE	REFERENCE	FIGURE
SJS		H:/718000/aug11/welloc11.srf	A-1

Part I.E.1.(c) of the GWDP requires that each point of compliance well must be sampled for the constituents listed in Table 2.3-1.

**Table 2.3-1
Groundwater Monitoring Constituents Listed in Table 2 of the GWDP**

Nutrients:

Ammonia (as N)

Nitrate & Nitrite (as N)

Heavy Metals:

Arsenic

Lead

Thallium

Beryllium

Manganese

Tin

Cadmium

Mercury

Uranium

Chromium

Molybdenum

Vanadium

Cobalt

Nickel

Zinc

Copper

Selenium

Iron

Silver

Radiologics:

Gross Alpha

Volatile Organic Compounds:

Acetone

Chloroform

Tetrahydrofuran

Benzene

Chloromethane

Toluene

2-Butanone (MEK)

Dichloromethane

Xylenes (total)

Carbon Tetrachloride

Naphthalene

Others:

Field pH (S.U.)

Chloride

TDS

Fluoride

Sulfate

Further, Part I.E.1.(d) of the GWDP, requires that, in addition to pH, the following field parameters must also be monitored:

- Depth to groundwater
- Temperature
- Specific conductance

and that, in addition to chloride and sulfate, the following general organics must also be monitored:

- Carbonate, bicarbonate, sodium, potassium, magnesium, calcium, and total anions and cations.

Sample frequency depends on the speed of ground water flow in the vicinity of each well. Parts I.E.1(b) and (c) of the GWDP provide that quarterly monitoring is required for all wells where local groundwater average linear velocity has been found by the Executive Secretary to be equal to or greater than 10 feet/year, and semi-annual monitoring is required where the local groundwater average linear velocity has been found by the Executive Secretary to be less than 10 feet/year.

Based on these criteria, MW-11, MW-14, MW-25, MW-26, MW-30, MW-31, MW-35, MW-36 and MW-37 are monitored quarterly to collect background water quality data for the establishment of GWCLs. Semi-annual monitoring is required at MW-1, MW-2, MW-3, MW-3A, MW-5, MW-12, MW-15, MW-17, MW-18, MW-19, MW-23, MW-24, MW-27, MW-28, MW-29 and MW-32.

In addition MW-20 and MW-22, which have been classified as general monitoring wells are sampled semi-annually.

2.3.1.2 Deep Aquifer

The culinary well (one of the supply wells) is completed in the Navajo aquifer, at a depth of approximately 1,800 feet below the ground surface. Due to the fact that the deep confined aquifer at the site is hydraulically isolated from the shallow perched aquifer (see the discussion in Sections 1.5.1.1 and 1.5.1.2) no monitoring of the deep aquifer is required under the GWDP.

2.3.1.3 Seeps and Springs

Pursuant to Part I.E.6 of the GWDP, Denison has a *Sampling Plan for Seeps and Springs in the Vicinity of the White Mesa Uranium Mill*, Revision: 0, March 17, 2009 (the “SSSP”) (and as modified on June 10, 2011, Revision 1 – submitted to UDEQ for review) that requires the Mill to perform groundwater sampling and analysis of all seeps and springs found downgradient or lateral gradient from the tailings cells.

Under the SSSP, seeps and springs sampling is conducted on an annual basis between May 1 and July 15 of each year, to the extent sufficient water is available for sampling, at five identified seeps and springs near the Mill. The sampling locations were selected to correspond with those seeps and springs sampled for the initial Mill site characterization performed in the 1978 ER, plus additional sites located by Denison, the BLM and Ute Mountain Ute Indian Tribe representatives.

Samples are analyzed for all groundwater monitoring parameters found in Table 2.3-1 above. The laboratory procedures utilized to conduct the analyses of the sampled parameters are those utilized for groundwater sampling. In addition to these laboratory parameters, the pH, temperature and conductivity of each sample will be measured and recorded in the field. Laboratories selected by Denison to perform analyses of seeps and springs samples will be required to be certified by the State of Utah in accordance with UAC R317-6-6.12.A.

The seeps and springs sampling events will be subject to the Mill's QAP, unless otherwise specifically modified by the SSSP to meet the specific needs of this type of sampling.

2.3.1.4 Discharge Minimization Technology and Best Available Technology Standards and Monitoring

a) General

Part I.D. of the GWDP sets out a number of Discharge Minimization Technology (“DMT”) and Best Available Technology (“BAT”) standards that must be followed. Part I.E. of the GWDP sets out the Ground Water Compliance and Technology Performance Monitoring requirements, to ensure that the DMT and BAT standards are met. These provisions of the GWDP, along with the *White Mesa Mill Tailings Management System and Discharge Minimization (DMT) Monitoring Plan*, 1/11 Revision: Denison-11.1 (the “DMT Plan”) (Section 3.1 of Denison, 2011b), the Cell 4A and 4B BAT Monitoring, Operations and Maintenance Plan and other plans and programs developed pursuant to such Parts of the GWDP, set out the methods and procedures for inspections of the facility operations and for detecting failure of the system.

In addition to the programs discussed above, the following additional DMT and BAT performance standards and associated monitoring are required under Parts I.D and I.E. of the GWDP.

b) Tailings Cell Operation

Part I.D.2 of the GWDP provides that authorized operation and maximum disposal capacity in each of the existing tailings cells. Cells 1 and 4B shall not exceed the levels authorized by the License and that under no circumstances shall the freeboard be less than three feet, as measured from the top of the flexible membrane liner (“FML”). Part I.E.7(a) of the GWDP requires that the wastewater pool elevations in Cells 1, 3, 4A and 4B must be monitored weekly to ensure

compliance with the maximum wastewater elevation criteria mandated by Condition 10.3 of the License, and in the case of Cell 4A to provided head information used in determining the allowable leakage rate through the FML

Part I.D.2 further provides that any modifications by Denison to any approved engineering design parameter at these existing tailings cells requires prior Executive Secretary approval, modification of the GWDP and issuance of a construction permit.

c) Slimes Drain Monitoring

Part I.D.3(b)(1) of the GWDP requires that Denison must at all times maintain the average wastewater head in the slimes drain access pipe to be as low as reasonably achievable (ALARA) in each tailings disposal cell, in accordance with the approved DMT Plan. Compliance will be achieved when the average annual wastewater recovery elevation in the slimes drain access pipe, determined pursuant to the currently approved DMT Plan meets the conditions in Equation 1 specified in Part I.D.3(b)(1) of the GWDP.

Part I.E.7(b) of the GWDP requires that Denison must monitor and record quarterly the depth to wastewater in the slimes drain access pipes as described in the currently approved DMT Plan at Cell 2, and upon commencement of de-watering activities, at Cell 3, in order to ensure compliance with Part I.D.3(b)(1) of the GWDP.

d) Maximum Tailings Waste Solids Elevation

Part I.D.3(c) of the GWDP requires that upon closure of any tailings cell, Denison must ensure that the maximum elevation of the tailings waste solids does not exceed the top of the FML.

e) Wastewater Elevation in Roberts Pond

Part I.D.3(e) of the GWDP requires that Roberts Pond be operated so as to provide a minimum 2-foot freeboard at all times, and that under no circumstances will the water level in the pond exceed an elevation of 5,624 feet above mean sea level. Part I.D.3(e) also provides that in the event the wastewater elevation exceeds this maximum level, Denison must remove the excess wastewater and place it into containment in Cell 1 within 72 hours of discovery.

Part I.E.7(c) of the GWDP requires that the wastewater level in Roberts Pond must be monitored and recorded weekly, in accordance with the currently approved DMT Plan, to determine compliance with the DMT operations standard in Part I.D.3(e) of the GWDP;

f) Inspection of Feedstock Storage Area

Part I.D.3(f) of the GWDP requires that open-air or bulk storage of all feedstock materials at the Mill facility awaiting Mill processing must be limited to the eastern portion of the Mill site (the “ore pad”) described by the coordinates set out in that Part of the GWDP, and that storage of feedstock materials at the facility outside of this defined area, must meet the requirements of Part I.D.11 of the GWDP. Part I.D.11 requires that Denison must store and manage feedstock materials outside the defined ore storage pad in accordance with the following minimum performance requirements:

- (i) Feedstock materials will be stored at all times in water-tight containers, and
- (ii) Aisle ways will be provided at all times to allow visual inspection of each and every feedstock container, or
- (iii) Each and every feedstock container will be placed inside a water-tight overpack prior to storage, or

- (iv) Feedstock containers shall be stored on a hardened surface to prevent spillage onto subsurface soils, and that conforms with the following minimum physical requirements:
 - A. A storage area composed of a hardened engineered surface of asphalt or concrete, and
 - B. A storage area designed, constructed, and operated in accordance with engineering plans and specifications approved in advance by the Executive Secretary. All such engineering plans or specifications submitted shall demonstrate compliance with Part I.D.4 of the GWDP, and
 - C. A storage area that provides containment berms to control stormwater run-on and run-off, and
 - D. Stormwater drainage works approved in advance by the Executive Secretary, or
- (v) Other storage facilities and means approved in advance by the Executive Secretary.

Part I.E.7(d) of the GWDP requires that Denison conduct weekly inspections of all feedstock storage areas to:

- (i) Confirm that the bulk feedstock materials are maintained within the approved feedstock storage area specified by Part I.D.3(f) of the GWDP; and
- (ii) Verify that all alternate feedstock materials located outside the approved feedstock storage area are stored in accordance with the requirements found in Part I.D.11 of the GWDP.

Part I.E.7(e) further provides that Denison must conduct weekly inspections to verify that each feed material container complies with the requirements of Part I.D.11 of the GWDP.

The Mill's Standard Operating Procedure under the License for inspection of the Mill's ore pad is contained in Section 3.3 of the DMT Plan.

g) Monitor and Maintain Inventory of Chemicals

Part I.D.3(g) of the GWDP requires that for all chemical reagents stored at existing storage facilities and held for use in the milling process, Denison must provide secondary containment to capture and contain all volumes of reagent(s) that might be released at any individual storage area. Response to spills, cleanup thereof, and required reporting must comply with the provisions of the Mill's *Emergency Response Plan* (a copy of which is included as Appendix C), as stipulated by Part I.D.10 of the GWDP. Part I.D.3(g) further provides that for any new construction of reagent storage facilities, such secondary containment and control must prevent any contact of the spilled or otherwise released reagent or product with the ground surface.

Part I.E.9 of the GWDP requires that Denison must monitor and maintain a current inventory of all chemicals used at the facility at rates equal to or greater than 100 kg/yr. This inventory must be maintained on-site, and must include:

- (iii) Identification of chemicals used in the milling process and the on-site laboratory;
and
- (iv) Determination of volume and mass of each raw chemical currently held in storage at the facility.

2.3.1.5 BAT Performance Standards for Cell 4A

a) BAT Operations and Maintenance Plan

Part I.D.6 and I.D.13 of the GWDP provides that Denison must operate and maintain Cell 4A and Cell 4B respectively so as to prevent release of wastewater to groundwater and the

environment in accordance with the Mill's Cell 4A BAT Monitoring, Operations and Maintenance Plan, pursuant to Part I.H.19 of the GWDP. The Mill's *Cell 4A and 4B BAT Monitoring, Operations and Maintenance Plan*, 01/11 Revision: Denison 2.2 includes the following performance standards:

- (i) The fluid head in the leak detection system shall not exceed 1 foot above the lowest point in the lower membrane liner;
- (ii) The leak detection system maximum allowable daily leak rate shall not exceed 24,160 gallons/day for Cell 4A and 26, 145 gallons/day for Cell 4B;
- (iii) After Denison initiates pumping conditions in the slimes drain layer in Cell 4A or Cell 4B, Denison will provide continuous declining fluid heads in the slimes drain layer, in a manner equivalent to the requirements found in Part I.D.3(b) for Cells 2 and 3; and
- (iv) Under no circumstances shall the freeboard be less than 3-feet in Cell 4B, as measured from the top of the FML.

b) Implementation of Monitoring Requirements Under the BAT Operations and Maintenance Plan

The *Cell 4A and 4B BAT Monitoring, Operations and Maintenance Plan* also requires Denison to perform the following monitoring and recordkeeping requirements:

- (i) Weekly Leak Detection System (LDS) Monitoring - including:
 - A. Denison must provide continuous operation of the leak detection system pumping and monitoring equipment, including, but not limited to, the submersible pump, pump controller, head monitoring, and flow meter equipment approved by the Executive Secretary. Failure of any pumping or monitoring equipment not repaired and made fully operational within

24-hours of discovery shall constitute failure of BAT and a violation of the GWDP;

- B. Denison must measure the fluid head above the lowest point on the secondary FML by the use of procedures and equipment approved by the Executive Secretary. Under no circumstance shall fluid head in the leak detection system sump exceed a 1-foot level above the lowest point in the lower FML, not including the sump;
- C. Denison must measure the volume of all fluids pumped from the leak detection system. Under no circumstances shall the average daily leak detection system flow volume exceed 24,160 gallons/day for Cell 4A or 26, 145 for Cell 4B; and
- D. Denison must operate and maintain wastewater levels to provide a 3-foot Minimum of vertical freeboard in tailings Cell 4B. Such measurement must be made to the nearest 0.1 foot.

(ii) Slimes Drain Recovery Head Monitoring

Immediately after the Mill initiates pumping conditions in the Cell 4A or Cell 4B slimes drain system, quarterly recovery head tests and fluid level measurements will be made in accordance with the requirements of Parts I.D.3(b) and I.E.7(b) of the GWDP and any plan approved by the Executive Secretary.

2.3.1.6 Stormwater Management and Spill Control Requirements

Part I.D.10 of the GWDP requires that Denison will manage all contact and non-contact stormwater and control contaminant spills at the facility in accordance with the Mill's

stormwater best management practices plan. The Mill's *Stormwater Best Management Practices Plan, Revision 1.3*: June 12, 2008 (a copy of which is included as Appendix C) includes the following provisions:

- a) Protect groundwater quality or other waters of the state by design, construction, and/or active operational measures that meet the requirements of the Ground Water Quality Protection Regulations found in UAC R317-6-6.3(G) and R317-6-6.4(C);
- b) Prevent, control and contain spills of stored reagents or other chemicals at the Mill site;
- c) Cleanup spills of stored reagents or other chemicals at the Mill site immediately upon discovery; and
- d) Report reagent spills or other releases at the Mill site to the Executive Secretary in accordance with UAC 19-5-114.

2.3.1.7 Tailings and Slimes Drain Sampling

Part I.E.10 of the GWDP requires that, on an annual basis, Denison must collect wastewater quality samples from each wastewater source at each tailings cell at the facility, including surface impounded wastewaters, and slimes drain wastewaters, pursuant to the Mill's *Tailings and Slimes Drain Sampling Program*, Revision 0, November 20, 2008 (the "WQSP"). All such sampling must be conducted in August of each calendar year.

The purpose of the WQSP is to characterize the source term quality of all tailings cell wastewaters, including impounded wastewaters or process waters in the tailings cells, and wastewater or leachates collected by internal slimes drains. The WQSP requires:

- Collection of samples from the pond area of each active cell and the slimes drain of each cell that has commenced de-watering activities;

- Samples of tailings and slimes drain material will be analyzed at an offsite contract laboratory and subjected to the analytical parameters included in Table 2 of the GWDP (see Table 2.3-1 above) and general inorganics listed in Part I.E.1(d)(2)(ii) of the GWDP, as well as semi-volatile organic compounds;
- A detailed description of all sampling methods and sample preservation techniques to be employed;
- The procedures utilized to conduct these analyses will be standard analytical methods utilized for groundwater sampling and as shown in Section 8.2 of the Mill's QAP;
- The contracted laboratory will be certified by the State of Utah in accordance with UAC R317-6-6.12A; and
- 30-day advance notice of each annual sampling event must be given, to allow the Executive Secretary to collect split samples of all tailings cell wastewater sources.

The tailings and slimes drain sampling events are subject to the Mill's QAP, unless otherwise specifically modified by the WQSP to meet the specific needs of this type of sampling.

2.3.2 Monitoring and Inspections Required Under the License

2.3.2.1 Environmental Monitoring


The environmental monitoring program is designed to assess the effect of Mill process and disposal operations on the unrestricted environment. Delineation of specific equipment and procedures is presented in the Mill's *Environmental Protection Manual*, included as Appendix A to the 2007 License Renewal Application.

c) Ambient Air Monitoring


(i) Ambient Particulate

Airborne radionuclide particulate sampling is performed at five locations, termed BHV-1, BHV-2, BHV-4, BHV-5 and BHV-6. With the approval of the NRC and effective November, 1995, BHV-3 was removed from the active air particulate monitoring program. At that time, the Mill proposed (and NRC determined) that a sufficient air monitoring data base had been compiled at station BHV-3 to establish a representative airborne particulate radionuclide background for the Mill. BHV-6 was installed by the Mill at the request of the White Mesa Ute Community. This station began operation in July of 1999 and provides airborne particulate information in the southerly direction between the Mill and the White Mesa Ute Community. Figure 2.3-2 shows the locations of these air particulate monitoring stations.

W:\Legacy\USA\UTAH\Mill\DWGs\Reclamation\Plans\Rev_07-2011\Work01\Fig.2.3-2_AirMonitoring.dwg Layout1 G.Moseley



- PROPERTY BOUNDARY
- RESERVATION BOUNDARY
- CANYON RIM
- SURFACE WATER SAMPLING LOCATION



Denison Mines (USA) Corp **DENISON MINES**

Project: White Mesa Mill	
Date: 11-09	County: San Juan State: UT
By: dls	Location:
Date: 09-11	HIGH VOLUME AIR MONITORING STATIONS FIGURE 2.3-2
Author: HRR	Date: Feb 2007
	Drafted By: BM

UT83-SF

The present sampling system consists of high volume particulate samplers utilizing mass flow controllers to maintain an air flow rate of approximately 32 standard cubic feet per minute. Samplers are operated continuously with a goal for on-stream operating period at ninety percent. Filter rotation is weekly with quarterly site compositing for particulate radionuclide analysis. Analysis is done for U-natural, Th-230, Ra-226, and Pb-210.

See Section 3.13.1.7(a) of the 2007 ER for a summary of historic monitoring results for airborne particulate.

(ii) Ambient Radon

With the approval of the NRC, Radon-222 monitoring at the BHV stations was discontinued in 1995, due to the unreliability of monitoring equipment available at that time to detect the new 10 CFR standard of 0.1 pCi/l. From that time until the present, the Mill demonstrated compliance with the requirements of R313-15-301 by calculation authorized by the NRC in September 1995 and as contemplated by R313-15-302 (2) (a).

This calculation was performed by use of the MILDOS code for estimating environmental radiation doses for uranium recovery operations (Streng and Bender 1981) in 1991 in support of the Mill's 1997 license renewal and more recently in 2007 in support of the 2007 License Renewal Application, by use of the updated MILDOS AREA code (Yuan et al., 1998). The analysis under both the MILDOS and MILDOS AREA codes assumed the Mill to be processing high grade Arizona Strip ores at full capacity, and calculated the concentrations of radioactive dust and radon at individual receptor locations around the Mill. Specifically, the modeling under these codes assumed the following conditions:

- 730,000 tons of ore per year
- Average grade of 0.53 percent U₃O₈

- Yellowcake production of 4,380 tons of U_3O_8 per year (8.8 million pounds U_3O_8 per year).

Based on these conditions, the MILDOS and MILDOS AREA codes calculated the combined total effective dose equivalent from both air particulate and radon at the current nearest residence (approximately 1.2 miles north of the Mill), i.e., the individual member of the public likely to receive the highest dose from Mill operations, as well as at all other receptor locations, to be below the ALARA goal of 10 mrem/yr for air particulate alone as set out in R313-15-101(4). Mill operations are constantly monitored to ensure that operating conditions do not exceed the conditions assumed in the above calculations. If conditions are within those assumed above, radon has been calculated to be within regulatory limits. If conditions exceed those assumed above, then further evaluation will be performed in order to ensure that doses to the public continue to be within regulatory limits. Mill operations to date have never exceeded the License conditions assumed above.

In order to determine if detection equipment has improved since 1995, the Mill has, commencing with the first quarter of 2007, re-instituted direct measurements of radon at the five air particulate monitoring locations currently utilized for air particulate sampling. The reliability of this data is currently under review by Denison.

d) External Radiation

TLD badges, as supplied by Landauer, Inc., or equivalent, are utilized at BHV-1, BHV-2, BHV-3, BHV-4, BHV-5 and BHV-6 to determine ambient external gamma exposures (see Figure 2.3-1). System quality assurances are determined by placing a duplicate monitor at one site continuously. Exchanges of TLD badges are on a quarterly basis. Badges consist of a minimum of five TLD chips. Measurements obtained from location BHV-3 have been designated as background due to BHV-3's remoteness from the Mill site (BHV-3 is located approximately 3.5

miles west of the Mill site). For further procedural information see Section 4.3 of the Mill's *Environmental Protection Manual*, included as Appendix A to the 2007 License Renewal Application. See Section 3.13.1.7(c) of the 2007 ER for a summary of historic monitoring results for external radiation.

e) Soil and Vegetation

(i) Soil Monitoring

Soil samples from the top one centimeter of surface soils are collected annually at each of BHV-1, BHV-2, BHV-3, BHV-4 and BHV-5 (see Figure 2.3-1). A minimum of two kilograms of soil is collected per site and analyzed for U-natural and Ra-226. For further procedural information see Section 4.1 of the Mill's *Environmental Protection Manual* included as Appendix A to the 2007 License Renewal Application. See Section 3.13.1.7.1 of the 2007 ER for a summary of the historic results for soil monitoring. The 2007 ER concludes that the results of sampling are low, less than the unrestricted release limits.

(ii) Vegetation Monitoring

Forage vegetation samples are collected three times per year from animal grazing locations to the northeast (near BHV-1 (the meteorological station)), northwest (to the immediate west of the site) and southwest (by BHV-4) of the Mill site. Samples are obtained during the grazing season, in the late fall, early spring, and in late spring. A minimum of three kilograms of vegetation are submitted from each site for analysis of Ra-226 and Pb-210. For further procedure information see Section 4.2 of the Mill's *Environmental Protection Manual* included as Appendix A to the 2007 License Renewal Application. See Section 3.13.7(d) of the 2007 ER for a summary of the historic results for vegetation monitoring. The 2007 ER concludes that the most recent results indicate no increase in uptake of Ra-226 and Pb-210 in vegetation.

d) Meteorological

Meteorological monitoring is done at a site near BHV-1. The sensor and recording equipment are capable of monitoring wind velocity and direction, from which the stability classification is calculated. Data integration duration is one-hour with hourly recording of mean speed, mean wind direction, and mean wind stability (as degrees sigma theta).

The data from the meteorological station is retrieved monthly by down loading onto a Campbell Scientific data module, or the equivalent. The data module is sent to an independent meteorological contractor where the module is downloaded to a computer record, and the data is correlated and presented in a Semi-Annual Meteorological Report.

Monitoring for precipitation consists of a daily log of precipitation using a standard NOAA rain gauge, or the equivalent, installed near the administrative office, consistent with NOAA specifications.

Windrose data is summarized in a format compatible with MILDOS and UDAD specifications for 40 CFR 190 compliance. For further procedural information see Section 1.3 of the Mill's *Environmental Protection Manual* included as Appendix A to the 2007 License Renewal Application. A windrose for the site is set out in Figure 1.1-1.

e) Point Emissions

Stack emission monitoring from yellowcake facilities follows EPA Method 5 procedures and occurs on a quarterly basis, during operation of the facility. Particulate sampling is analyzed for Unat on a quarterly basis and for Th-230, Ra-226, and Pb-210 on a semi-annual basis. Demister and ore stack emission monitoring follows EPA Method 5 procedure on a semi-annual basis, during operation of the facility. Particulate samples are analyzed for Unat, Th-230, Ra-226, and Pb-210. Monitored data includes scrubber system operation levels, process feed levels,

particulate emission concentrations, isokinetic conditions, and radionuclide emission concentrations. For further procedure information see Section 1.4 of the Mill's *Environmental Protection Manual* included as Appendix A to the 2007 License Renewal Application. Historic stack emission data are summarized in Section 3.13.1.7(e) of the 2007 ER.

f) Surface Water Monitoring

Surface water monitoring is conducted at two locations adjacent to the Mill facility known as Westwater Canyon and Cottonwood Creek. Samples are obtained annually from Westwater and quarterly from Cottonwood using grab sampling. For Westwater Creek, samples will be of sediments if a water sample is not available. Field monitored parameters and laboratory monitored parameters are listed in Table 2.3-2. For further procedural information see Section 2.1 of the Mill's *Environmental Protection Manual* included as Appendix A to the 2007 License Renewal Application. See Section 3.7.4 of the 2007 ER for a summary of the historic results for surface water monitoring.

**Table 2.3-2
Operational Phase Surface Water Monitoring Program**

Monitoring Sites
Westwater Creek and Cottonwood Creek

Field Requirements

1. temperature C;
2. Specific Conductivity umhos at 25 C;
3. pH at 25 C;
4. Sample date;
5. Sample ID Code;

Vendor Laboratory Requirements

<u>Semiannual*</u>	<u>Quarterly</u>
One gallon Unfiltered and Raw	One gallon Unfiltered and Raw
One gallon Unfiltered, Raw and preserved to pH <2 with HNO ₃	One gallon Unfiltered, Raw and Preserved to pH <2 with HNO ₃
Total Dissolved Solids	Total Dissolved Solids
Total Suspended Solids	Total Suspended Solids
Gross Alpha	
Suspended Unat	
Dissolved Unat	
Suspended Ra-226	
Dissolved Ra-226	
Suspended Th-230	
Dissolved Th-230	

*Semiannual sample must be taken a minimum of four months apart.
**Annual Westwater Creek sample is analyzed for semi-annual parameters.
Radionuclides and LLDs reported in µCi/ml

2.3.2.2 Additional Monitoring and Inspections Required Under the License

Under the License daily, weekly, and monthly inspection reporting and monitoring are required by NRC Regulatory Guide 8.31, *Information Relevant to Ensuring that Occupational Radiation Exposures at Uranium Recovery Facilities will be As Low As is Reasonable Achievable*,

Revision 1, May 2002 (“Reg Guide 8.31”), by Section 2.3 of the Mill’s ALARA Program and by the DMT Plan, over and above the inspections described above that are required under the GWDP. A copy of the Mill’s ALARA Program is included as Appendix I to the 2007 License Renewal Application.

a) Daily Inspections

Three types of daily inspections are performed at the Mill under the License:

(i) Radiation Staff Inspections

Paragraph 2.3.1 of Reg. Guide 8.31 provides that the Mill’s Radiation Safety Officer (“RSO”) or designated health physics technician should conduct a daily walk-through (visual) inspection of all work and storage areas of the Mill to ensure proper implementation of good radiation safety procedures, including good housekeeping that would minimize unnecessary contamination. These inspections are required by Section 2.3.1 of the Mill’s ALARA Program, and are documented and on file in the Mill’s Radiation Protection Office.

(ii) Operating Foreman Inspections

30 CFR Section 56.18002 of the Mine Safety and Health Administration regulations requires that a competent person designated by the operator must examine each working place at least once each shift for conditions which may adversely affect safety or health. These daily inspections are documented and on file in the Mill’s Radiation Protection Office.

(iii) Daily Tailings Inspection

Paragraph 2.2 of the DMT Plan requires that during Mill operation, the Shift Foreman, or other person with the training specified in paragraph 2.4 of the DMT Plan, designated by the RSO, will perform an inspection of the tailings line and tailings area at least once per shift, paying close attention for potential leaks and to the discharges from the pipelines. Observations by the Inspector are recorded on the appropriate line on the Mill's Daily Inspection Data form.

b) Weekly Inspections

Three types of weekly inspections are performed at the Mill under the License:

(i) Weekly Inspection of the Mill Forms

Paragraph 2.3.1 of Reg. Guide 8.31 provides that the RSO and the Mill foreman should, and Section 2.3.2 of the Mill's ALARA Program provides that the RSO and Mill foreman, or their respective designees, shall conduct a weekly inspection of all Mill areas to observe general radiation control practices and review required changes in procedures and equipment. Particular attention is to be focused on areas where potential exposures to personnel might exist and in areas of operation or locations where contamination is evident.

(ii) Weekly Ore Storage Pad Inspection Forms

Paragraph 3.3 of the DMT Plan requires that weekly feedstock storage area inspections will be performed by the Radiation Safety Department, to confirm that the bulk feedstock materials are stored and maintained within the defined area of the ore pad and that all alternate feed materials located outside the defined ore pad area are maintained within water tight containers. The results of these inspections are recorded on the Mill's Ore Storage/Sample Plant Weekly Inspection Report.

(iii) Weekly Tailings and DMT Inspection

Paragraphs 3.1 and 3.2 of the DMT Plan require that weekly inspections of the tailings area and DMT requirements be performed by the radiation safety department.

c) Monthly Reports

Two types of monthly reports are prepared by Mill staff:

(i) Monthly Radiation Safety Reports

At least monthly, the RSO reviews the results of daily and weekly inspections, including a review of all monitoring and exposure data for the month and provides to the Mill Manager a monthly report containing a written summary of the month's significant worker protection activities (Section 2.3.4 of the Mill's ALARA Program).

(ii) Monthly Tailings Inspection Reports

Paragraph 4 of the DMT Plan requires that a Monthly Inspection Data form be completed for the monthly tailings inspection. This inspection is typically performed in the fourth week of each month and is in lieu of the weekly tailings inspection for that week.

Mill staff also prepares a monthly summary of all daily, weekly, monthly and quarterly tailings inspections.

d) Quarterly Tailings Inspections

Paragraph 5 of the DMT Plan requires that the RSO or his designee perform a quarterly tailings inspection.

e) Annual Evaluations

The following annual evaluations are performed under the License, as set out in Section 6 of the DMT Plan.

(i) Annual Technical Evaluation

An annual technical evaluation of the tailings management system must be performed by a registered professional engineer (PE), who has experience and training in the area of geotechnical aspects of retention structures. The technical evaluation includes an on-site inspection of the tailings management system and a thorough review of all tailings records for the past year. The Technical Evaluation also includes a review and summary of the annual movement monitor survey (see paragraph (ii) below).

All tailings cells and corresponding dikes are inspected for signs of erosion, subsidence, shrinkage, and seepage. The drainage ditches are inspected to evaluate surface water control structures.

In the event tailings capacity evaluations were performed for the receipt of alternate feed material during the year, the capacity evaluation forms and associated calculation sheets will be reviewed to ensure that the maximum tailings capacity estimate is accurate. The amount of tailings added to the system since the last evaluation will also be calculated to determine the estimated capacity at the time of the evaluation.

As discussed above, tailings inspection records consist of daily, weekly, monthly, and quarterly tailings inspections. These inspection records are evaluated to determine if any freeboard limits are being approached. Records will also be reviewed to summarize observations of potential concern. The evaluation also involves discussion with the Environmental and/or Radiation Technician and the RSO regarding activities around the tailings area for the past year. During

the annual inspection, photographs of the tailings area are taken. The training of individuals is also reviewed as a part of the Annual Technical Evaluation.

The registered engineer obtains copies of selected tailings inspections, along with the monthly and quarterly summaries of observations of concern and the corrective actions taken. These copies are then included in the *Annual Technical Evaluation Report*.

The *Annual Technical Evaluation Report* must be submitted by November 15th of every year to the Executive Secretary and to the Directing Dam Safety Engineer, State of Utah, Natural Resources.

(ii) Annual Movement Monitor Survey

A movement monitor survey is conducted by a licensed surveyor semi-annually for the first three (3) years, and annually thereafter during the second quarter of each year. The movement monitor survey consists of surveying monitors along dikes 4A-W, 4A-S and 4B-S to detect any possible settlement or movement of the dikes. The data generated from this survey is reviewed and incorporated into the *Annual Technical Evaluation Report* of the tailings management system.

(iii) Annual Leak Detection Fluid Samples

In the event solution has been detected in a leak detection system in Cells 1, 2 or 3, a sample will be collected on an annual basis. This sample will be analyzed according to the conditions set forth in License Condition 11.3.C. The results of the analysis will be reviewed to determine the origin of the solution.

3 TAILINGS RECLAMATION PLAN


This section provides an overview of the Mill location and property; details the facilities to be reclaimed; and describes the design criteria applied in this Plan. Reclamation plans and technical specifications are presented in Attachment A. Attachment B presents the quality assurance and quality control plan for construction activities. Attachment C presents cost estimates for reclamation. Attachment D presents the Radiation Protection Manual for Reclamation.

3.1 Location and Property Description

The Mill is located approximately six miles south of Blanding, Utah on US Highway 191 on a parcel of land encompassing all or part of Sections 21, 22, 27, 28, 29, 32, and 33 of T37S, R22E, and Sections 4, 5, 6, 8, 9, and 16 of T38S, R22E, Salt Lake Base and Meridian described as follows (Figure 3.1-1):

The south half of the south half of Section 21; the southeast quarter of the southeast quarter of Section 22; the northwest quarter of the northwest quarter and lots 1 and 4 of Section 27 all that part of the southwest quarter of the northwest quarter and the northwest quarter southwest quarter of Section 27 lying west of Utah State Highway 163; the northeast quarter of the northwest quarter, the south half of the northwest quarter, the northeast quarter and the south half of Section 28; the southeast quarter of the southeast quarter of Section 29; the east half of Section 32 and all of Section 33, Township 37 South, Range 22 East, Salt Lake Base and Meridian. Lots 1 through 4, inclusive, the south half of the north half, the southwest quarter, the west half of the southeast quarter, the west half of the east half of the southeast quarter and the west half of the east half of the east half of the southeast quarter of Section 4; Lots 1 through 4, inclusive, the south half of the north half and the south half of Section 5 (all); Lots 1 and 2, the south half of

W:\USA\Utah\Mill\Drawings\Reclamation Plans\RecPlan4.0\Land Location Maps.dwg Figure 3.1-1 03/11/2008 dsledd



Denison Mines (USA) Corp.		DENISON MINES	
REVISIONS		Project: White Mesa Mill	
Date	By	County: San Juan	State: Utah
		Location:	
FIGURE 3.1-1			
REGIONAL MAP SHOWING LAND POSITION			
Date	Nov. 2008	Scale	1"=6000'
Author:		Drawn by:	RAH

the northeast quarter and the south half of Section 6 (E1/2); the northeast quarter of Section 8; all of Section 9 and all of Section 16, Township 38 South, Range 22 East, Salt Lake Base and Meridian. Additional land is controlled by 46 Mill site claims. Total land holdings are approximately 5,415 acres.

3.2 Facilities to be Reclaimed

See the Drawings (Attachment A) for a general layout of the Mill yard and related facilities and the restricted area boundary.

3.2.1 Summary of Facilities to be Reclaimed

The facilities to be reclaimed include the following:

- Cell 1 (evaporation). Cell 1 was previously referred to as Cell 1-I. It is now referred to Cell 1;
- Cells 2, 3, 4A, and 4B (tailings);
- Mill buildings and equipment;
- On-site contaminated areas; and
- Off-site contaminated areas (i.e., potential areas affected by windblown tailings).

The reclamation of the above facilities will include the following:

- Placement of contaminated soils, crystals, and synthetic liner material and any contaminated underlying soils from Cell 1 into the last active tailings cell;
- Placement of a compacted clay liner on a portion of the Cell 1 impoundment area to be used for disposal of contaminated materials and debris from the Mill site;
- Decommissioning (the Cell 1 Tailings Area);

- Placement of materials and debris from Mill decommissioning into the last active tailings cell or Cell 1 Tailings Area cells;
- Placement of an engineered multi-layer cover over the entire area of Cells 2, 3, 4A, 4B, and the Cell 1 Tailings Area;
- Construction of runoff control and diversion channels as necessary;
- Reclamation of Mill and ancillary areas; and
- Reclamation of borrow sources.

3.2.2 Tailings and Evaporative Cells

The following subsections describe the cover design and reclamation procedures for Cells 1, 2, 3, 4A, and 4B. Complete engineering details and text are presented in the Updated Tailings Cover Design Report (MWH, 2011b) included as Appendix D to this Reclamation Plan.

3.2.2.1 Soil Cover Design

An ET cover was proposed by Denison for the White Mesa Mill disposal cells in the Infiltration and Contaminant Transport Modeling (ICTM) reports (MWH 2007 and 2010) submitted to the DRC to fulfill the White Mesa Mill's Ground Water Discharge Permit No. UGW370004. A conceptual design of the ET cover, to be placed over the uranium tailings and Mill decommissioning materials in the Cell 1, Cell 2, Cell 3, Cell 4A and Cell 4B tailings area, was provided in these reports. Denison stated their intent to submit an ET cover design as part of their license renewal in a meeting with DRC on October 5, 2010 after review of the DRC Reclamation Plan, Version 4.0 Interrogatories – Round 1 (DRC, 2010). The proposed conceptual ET cover design was provided to DRC on October 7, 2010 and was essentially the same as presented in the 2010 Infiltration and Contaminant Transport Model report (MWH, 2010). The ET cover proposed and evaluated as described in this report consists of the following materials outlined below by individual layers and thicknesses from top to bottom:

- 0.5 ft (15 cm) Erosion Protection Layer (gravel-admixture)
- 3.5 ft (107 cm) Water Storage/Biointrusion/Frost Protection/Radon Attenuation Layer (random fill composed of loam to sandy clay)
- 2.5 ft (75 cm) Radon Attenuation Layer (highly compacted random fill composed of loam to sandy clay)
- 2.5 ft (75 cm) Radon Attenuation and Grading Layer (random fill composed of loam to sandy clay)

The 0.5-foot thick erosion protection layer is planned to be rock mulch consisting of topsoil mixed with 25 percent gravel. The uppermost 3.5 feet of random fill will be placed at 85 percent of standard Proctor compaction in order to optimize water storage and rooting characteristics for plant growth. The middle layer (2.5 feet) of random fill will be compacted to 95 percent of standard Proctor. The lower layer of random fill consists of 2.5 feet of random fill that is assumed to be dumped and minimally compacted by construction equipment to approximately 80 percent standard Proctor. In Cell 2 and parts of Cell 3, the lower layer of random fill is already placed and is approximately 3 feet thick. The upper 6 inches of this fill will be compacted to 95 percent of standard Proctor compaction and will thus comprise the bottom portion of the Radon Attenuation Layer.

The majority of the cover will be constructed from materials available from within the site boundaries. As a part of the soil cover, erosion protection will be placed as the top layer of the cover to stabilize slopes and provide long-term erosion resistance (see Appendix D for characterization of cover materials). The erosion protection materials will be obtained from off-site sources.

Uranium tailings soil cover design requirements for regulatory compliance include:

- Attenuate radon flux to an acceptable level (20 picoCuries-per meter squared-per second [pCi/m²/sec]) (NRC, 1989) and 40 CFR 61.250-61.256;
- Minimize infiltration into the reclaimed tailings cells;
- Maintain a design life of up to 1,000 years to the extent reasonably achievable, and in any case for at least 200 years; and
- Provide long-term slope stability and geomorphic durability to withstand erosional forces of wind, the probable maximum flood event, and a horizontal ground acceleration of 0.1g due to seismic events.

Several models/analyses were utilized in simulating the soil cover effectiveness: radon flux attenuation, hydrologic evaluation of infiltration, freeze/thaw effects, soil cover erosion protection, static and pseudostatic slope stability analyses, biointrusion, tailings dewatering, liquefaction, and settlement. These analyses and results are discussed in detail in Sections 3.3.2 through 3.3.10, and calculations are also shown in the Updated Tailings Cover Design Report (Appendix D).

The final grading plans are presented in the Drawings (Attachment A). As indicated in the Drawings, the drainage on the top surface of the ET cover at Cells 1, 2, and 3 is planned at a 0.5 percent slope, with portions of Cell 2 top surface at a one percent slope and portions of Cells 4A and 4B top surfaces at 0.8 percent slope. The side slopes, as well as transitional areas between cells, will be graded to five horizontal to one vertical (5H:1V).

3.2.2.2 Cell 1

Cell 1, used during Mill operations solely for evaporation of process liquids, is the northernmost existing cell and is located immediately west of the Mill. It is also the highest cell in elevation,

as the natural topography slopes to the south. The drainage area above and including the cell is 216 acres. This includes drainage from the Mill site.

Cell 1 will be evaporated to dryness. The synthetic liner and raffinate crystals will then be removed and placed in the tailings cells. Any contaminated soils below the liner will be removed and also placed in the tailings cells. Based on current regulatory criteria, the current plan calls for excavation of the residual radioactive materials to be designed to ensure that the concentration of radium-226 in land averaged over any area of 100 square meters does not exceed the background level by more than:

- 5 pCi/g, averaged over the first 15 cm of soil below the surface, and
- 15 pCi/g, averaged over a 15 cm thick layer of soil more than 15 cm below the surface.

A portion of Cell 1 (i.e., the Cell 1 Tailings Area), adjacent to and running parallel to the downstream cell dike, may be used for permanent disposal of contaminated materials and debris from the Mill site decommissioning and windblown cleanup. The actual area of the Cell 1 Tailings Area needed for storage of additional material will depend on the status of Cells 3, 4A, and 4B at the time of final Mill decommissioning. A portion of the Mill area decommissioning material may be placed in Cells 3, 4A or 4B if space is available, but for purposes of the reclamation design the entire quantity of contaminated materials from the Mill site decommissioning is assumed to be placed in the Cell 1 Tailings Area, which will subsequently be covered with the ET cover. This results in approximately 10 acres of the Cell 1 area constituting the Cell 1 Tailings Area and being utilized for permanent tailings storage. The remaining area of Cell 1 will then be breached and converted to a sedimentation basin. All runoff from the Cell 1 Tailings Area, the Mill area and the area immediately north of Cell 1 will be routed into the sedimentation basin and will discharge onto the natural ground via the channel located at the southwest corner of the basin. The channel is designed to accommodate the PMF flood. Hydraulic and erosional analyses are provided in Appendix D. The channel will be a

bedrock channel with a 0.1 percent channel slope, 150-foot bottom width, and 3 horizontal: 1 vertical sideslopes.

3.2.2.3 Cell 2

Cell 2 will be filled with tailings and covered with the ET cover to a minimum cover thickness of nine feet. The final cover will drain to the south at a 0.5 percent gradient.

The cover will be as described in Section 3.2.2.1 above and will consist of a 2.5 feet of loam to sandy clay, followed by 2.5 feet of highly compacted loam to sandy clay, overlain by 3.5 feet of loam to sandy clay. 0.5 feet of rock mulch will be utilized as armor against erosion at the surface of the cover. External side slopes or internal transition slopes will be graded to a 5:1 slope will have 12 inches of angular riprap at the cover surface for erosion protection. A rock apron with a thickness of 2 feet will be constructed at the transition areas of the toes of the side slopes of Cell 2.

3.2.2.4 Cell 3

Cell 3 will be filled with tailings, debris and contaminated soils and covered with the same ET cover system and erosion protection as Cell 2.

3.2.2.5 Cell 4A

Cell 4A will be filled with tailings, debris and contaminated soils and will be covered with the same ET cover system as Cell 2 and Cell 3. A rock apron with a thickness of 3.75 feet will be constructed at the south and east side slopes of Cell 4A.

3.2.2.6 Cell 4B

Cell 4B will be filled with tailings, debris, and contaminated soils and covered with the same ET cover system as Cells 2, 3, and 4A.

3.3 Design Criteria

As required by Part I.H.11 of the GWDP, Denison has completed an infiltration and contaminant transport model of the final tailings cover system to demonstrate the long-term ability of the ET cover to protect nearby groundwater quality. The ET cover design and basis presented in Appendix D (MWH, 2011b) will be used for this version of the Plan.

The design criteria summaries in this section are adapted from the Updated Tailings Cover Design Report (MWH, 2011b). A copy of the Tailings Cover Design Report is included as Appendix D. It contains all of the calculations used in design and summarized in this section.

3.3.1 Regulatory Criteria

Information contained in 10 CFR Part 20, 10 CFR Part 40 and Appendix A to 10 CFR Part 40 (which are incorporated by reference into UAC R313-24-4), and 40 CFR Part 192 were used as criteria in final designs under this Plan. In addition, the following documents also provided guidance:

- EPA, 1994, The Hydrologic Evaluation of Landfill Performance (HELP) Model, Version 3, EPA/600/R-94/168b, September
- NRC, 1989, Regulatory Guide 3.64 (Task WM-503-4) Calculation of Radon Flux Attenuation by Earthen Uranium Mill Tailings Covers, March

- NRC, 1984. Radon Attenuation Handbook for Uranium Mill Tailings Cover Design, NUREG/CR-3533
- NRC, 1990, Final Staff Technical Position, Design of Erosion Protection Covers for Stabilization of Uranium Mill Tailings Sites, August
- NUREG/CR-4620, Nelson, J. D., Abt, S. R., et al., 1986, Methodologies for Evaluating Long-Term Stabilization Designs of Uranium Mill Tailings Impoundments, June
- Johnson, T.L., 2002. *Design of Erosion Protection for Long-Term Stabilization*. U.S. Nuclear Regulatory Commission (NRC), *NUREG-1623*. September
- U. S. Department of Energy, 1988, *Effect of Freezing and Thawing on UMTRA Covers*, Albuquerque, New Mexico, October
- NUREG 1620, 2003, Standard Review Plan for the Review of a Reclamation Plan for Mill Tailings Sites Under Title II of the Uranium Mill Tailings Radiation Control Act of 1978; and
- U.S. Department of Energy, 1989. *Technical Approach Document, Revision II, UMTRA-DOE/AL 050425.0002*, Uranium Mill Tailings Remedial Action Project, Albuquerque, New Mexico

As mentioned above, the requirements set out in Part I.D.8 of the GWDP require that the cover system for each tailings cell will be designed and constructed to meet the following minimum performance requirements for a period of not less than 200 years:

- Minimize the infiltration of precipitation or other surface water into the tailings, including, but not limited to the radon barrier;
- Prevent the accumulation of leachate head within the tailings waste layer that could rise above or over-top the maximum FML elevation internal to any disposal cell, i.e. create a “bathtub” effect; and
- Ensure that groundwater quality at the compliance monitoring wells does not exceed the GWQs or GWCLs specified in Part I.C.1 and Table 2 of the GWDP.

3.3.2 Radon Flux Attenuation

Analyses of radon attenuation through the monolithic ET cover have been performed, and incorporate the new cover design, changes to the final grading plan, and results of additional geotechnical testing of material properties. The thickness of the ET cover necessary to limit radon emanation from the disposal areas was analyzed using the NRC RADON model (NRC, 1989). The model was used to calculate the cover thickness required to achieve the State of Utah's long-term radon emanation standard for uranium mill tailings (Utah Administrative Code, Rule 313-24), 20 picocuries per square meter per second ($\text{pCi}/\text{m}^2\text{-s}$). The analyses were conducted following the guidance presented in NRC publications NUREG/CR-3533 (NRC, 1984) and Regulatory Guide 3.64 (NRC, 1989).

The input parameters used in the model are based on engineering experience with similar projects, recent laboratory testing results for samples of random fill (included in Appendix A.2), and available data from previous work by others. Results of the RADON analyses show that the proposed cover system reduces the rate of radon-222 emanation to less than 20 $\text{pCi}/\text{m}^2\text{-s}$, averaged over the entire area of the tailings impoundments. A complete description of the radon attenuation analyses conducted for the ET cover system is included in Appendix D.

3.3.2.1 Empirical Data

Radon gas flux measurements have been made at the Mill tailings piles over Cells 2 and 3. Currently Cell 2 is fully covered and Cell 3 is partially covered with three to four feet of random fill. During the period 2004 through 2007, Cell 2 was only partially covered with such random fill. Radon flux measurements, averaged over the covered areas, were as follows (Denison 2004-2010):

Table 3.3-1
Average Radon Flux From Tailings Cells 2004-2010
(pCi/m²/sec)

	2004	2005	2006	2007	2008	2009	2010
Cell 2	13.9	7.1	7.9	13.5	3.9	3.9	3.9
Cell 3	10.8	6.2	10.0	8.9	3.1	3.1	3.1

Empirical data suggest that the random fill cover, alone, is currently providing an effective barrier to radon flux. Thus, the proposed tailings cover configuration, which is thicker and contains a highly compacted radon attenuation layer is expected to attenuate the radon flux to a level below that predicted by the RADON model. The field radon flux measurements confirm the conservatism of the cover design. This conservatism is useful, however, to guarantee compliance with applicable regulations under long term climatic conditions over the required design life of 200 to 1,000 years.

3.3.3 Infiltration Analysis

Infiltration modeling for the monolithic ET cover was completed by MWH and summarized in the Infiltration and Contaminant Transport Modeling Report (MWH, 2010). These analyses included the soil properties for materials proposed for use in the monolithic ET cover. The evaluation of infiltration of precipitation through the cover system was evaluated with the computer program HYDRUS-1D (Simunek et al., 2009). The modeling used historic values of daily precipitation and evapotranspiration over a 57-year climate period, as well as assumptions that were either conservative or based on anticipated conditions. Given the flat nature of the cover (less than 1 percent slope), no runoff- or runoff-based processes were assumed to occur. As a result, precipitation applied to the cover surface was removed through evaporation or transpiration, retained in the soil profile as storage, or transmitted downward as infiltration.

The model-predicted water flux rate varies during the 57-year period from a minimum rate of 0.17 millimeters per year (mm/yr) to a maximum rate of 1.1 mm/yr, with an average long-term flux rate through the cover system of 0.45 mm/yr. This average long-term water flux rate corresponds to approximately 0.1 percent of the average annual amount of precipitation recorded at the Blanding, Utah weather station.

The model-predicted water flux rate through the monolithic ET cover indicates that the available storage capacity of the cover should be sufficient to significantly reduce infiltration, and the ET cover should function properly as designed. A complete description of the infiltration analyses conducted for the monolithic ET cover is provided in MWH (2010), and is included as a portion of Appendix D to this Reclamation Plan.

3.3.4 Freeze/Thaw Evaluation

A freeze/thaw analysis was performed for the monolithic ET cover system, utilizing geotechnical properties of materials specified for use in construction of the cover. The calculation of frost penetration at the site was performed with the computer program ModBerg (CRREL), which uses a built-in weather database, as well as user-defined soil parameters.

In summary, the freeze/thaw calculations show the total depth of frost penetration in the area of the Mill site to be 27.1 inches (2.26 ft). This frost depth could potentially be exceeded in a given year during the long-term design life of the cover, but the characteristics of the cover materials are such that detrimental effects to the cover because of freezing and thawing are not expected. Furthermore, because the cover has a total thickness of 9 feet, the impacts of freeze and thaw will not have significant impacts to the overall integrity of the cover. A complete description of the freeze/thaw analyses conducted for the proposed cover system is presented in the Updated Tailings Cover Design Report (MWH, 2011b), attached as Appendix D to this Reclamation Plan.

3.3.5 Soil Cover Erosion Protection

The erosional stability of the reclaimed tailings cells was evaluated in terms of long-term water erosion under extreme storm conditions. An updated evaluation of erosional stability of the new ET cover surface and reclaimed embankment slopes has been performed. The updated analyses also include an evaluation of sheet erosion of the top slope of the cells, a rock apron at the toe of the embankment slopes, and the need for filter material between riprap and the underlying soil. The analyses have been conducted in general accordance with NRC guidelines (NRC, 1990; Johnson, 2002). A detailed description of the analyses performed is presented in Appendix D.

The components of erosion protection for the reclaimed tailings cells consist of the following:

- The cover on the top surface of Cells 1, 2, and 3, with slopes of 0.5 percent, should be constructed as a vegetated slope, with 6 inches of topsoil vegetated with a grass mixture.
- The portions of Cell 2 with a top surface of 1 percent slope, and the portions of Cells 4A and 4B with 0.8 percent slope, should be constructed with 6 inches of topsoil mixed with 25 percent (by weight) gravel (maximum diameter of 1-inch).
- External side slopes or internal transition slopes graded to 5:1 (horizontal: vertical) should be constructed with 12 inches of angular riprap with a median rock size of 7.4 inches.
- A rock apron is recommended for the south side slopes of the reclaimed surfaces of Cells 4A and 4B and the east side of Cell 4A. The rock apron should be constructed with 3.75 feet of angular riprap with a median rock size of 15 inches.
- A rock apron is recommended for the transition areas of the toes of the north and west side slope and the east side slope of Cells 2 and 3. The rock apron should be constructed with 2 feet of angular riprap with a median rock size of 7.4 inches.

- A filter is recommended between the soil and rock protection, due to the size of riprap required for the embankment slopes and the fine-grained nature of the underlying topsoil.

3.3.6 Slope Stability Analysis

Slope stability analyses have been performed for the new monolithic ET cover system, and include updated geotechnical properties and seismic information, and an updated critical cross section. The slope stability analyses were performed for both static (long-term) and pseudo-static loading conditions, to meet NRC (2003) criteria. The analyses were performed using limit equilibrium methods with the computer program SLOPE/W (Geo-Slope, 2007).

A complete description of the input parameters and assumptions used in the analyses are included in Appendix D. The results of the stability analyses are provided in Table 3.3-2 below. The minimum factors of safety required in design and presented in Table 3.3-2 meet the criteria of NRC (2003). As shown in Table 3.3-2, the calculated factors of safety for both the long-term static condition and the pseudo-static condition exceed the required values.

**Table 3.3-2
Results of Slope Stability Analyses**

Loading Condition	Required Factor of Safety	Calculated Factor of Safety
Static Long-Term	1.5	4.30
Pseudo-static	1.1	2.82

3.3.7 Tailings Dewatering

An evaluation of the effects of dewatering in tailings Cells 2, 3, 4A and 4B was conducted to estimate the time required to dewater the tailings, as well as to calculate the residual saturated thickness of tailings after dewatering operations cease. Dewatering analyses for Cells 2 and 3 were conducted by MWH and are presented in Appendix J of MWH (2010). Dewatering

analyses for Cells 4A and 4B were conducted by Geosyntec (2007a, 2007b). The pertinent excerpts from MWH (2010), Geosyntec (2007a, 2007b), and DRC (2008) are included in Appendix D.

3.3.7.1 Tailings Cells 2 and 3

Dewatering of Cells 2 and 3 will be performed via the drain network consisting of perforated PVC pipe located across the base of the cells. The pipes drain to an extraction sump on the southern side of each cell. Tailings water gravity drains to the sump and is then pumped to Cell 1 for evaporation. The design for the drains is the same for both cells, and each drain system covers an approximate area of 400-feet by 600-feet in each cell. The drain pipes are covered by an envelope of sand over the drains, in contrast to a continuous layer of sand across the bottom of the tailing cells.

The analyses of dewatering of Cells 2 and 3 were performed with the computer code MODFLOW (McDonald and Harbaugh, 1988; Harbaugh et al., 2000) with the Department of Defense Groundwater Modeling System (GMS) pre- and post-processor. The slimes drains were simulated with the Drain package in MODFLOW, and values of hydraulic conductivity were based on measured values reported for uranium mill tailings at a similar facility (MWH, 2010).

The MODFLOW dewatering model completed for Cells 2 and 3 predicted that the tailings would draindown nonlinearly through time reaching an average saturated thickness of 3.5 feet (1.07 m) after 10 years of dewatering (MWH, 2010). The model also predicted that dewatering rates would decline to approximately 2 gallons per minute (gpm) after 10 years of pumping. A complete description of the dewatering modeling conducted for tailings Cells 2 and 3 is provided in Appendix J of MWH (2010), and is attached as a portion of Appendix D of this Reclamation Plan.

3.3.7.2 Tailings Cells 4A and 4B

The drain network design in Cells 4A and 4B is the same for each cell, and is different from that constructed in Cells 2 and 3. The drain network in Cells 4A and 4B consists of a series of 12-inch wide HDPE strip drains wrapped in geotextile, and covered by sand bags. The drain spacing is 50 feet across the entirety of both cells. The HDPE drains are connected to a perforated 4-inch diameter PVC pipe bedded in drain aggregate and wrapped in geotextile. The PVC pipe gravity drains the tailings water to the sump for extraction.

A tailings cell dewatering model was not constructed for Cells 4A and 4B because analytical solutions presented by Geosyntec Consultants (2007a, 2007b) were deemed adequate given the uniform distribution of the drain system in those cells. Material properties for tailings in Cells 4A and 4B were estimated based on results of laboratory tests. Results of the analyses indicated the areas of Cells 4A and 4B with the maximum thickness of tailings will be drained within approximately 5.5 years (Geosyntec Consultants, 2007a; 2007b). Cells 4A and 4B are estimated to be dewatered significantly faster than Cells 2 and 3 due to the more extensive drain network.

3.3.8 Liquefaction

Liquefaction analyses were performed to evaluate the risk of earthquake-induced liquefaction of the tailings. The analyses performed for the monolithic ET cover are an update to modeling presented in the previous Reclamation Plan, Revision 4.0 (Denison, 2009a). These analyses have been updated to incorporate the proposed monolithic ET cover system and a more recent reference for liquefaction analyses (Youd et al., 2001). Material properties used in the analyses were obtained from results of laboratory tests on tailings samples, or were estimated where site-specific data was not available. Site-specific seismic hazard information from Tetra Tech (2010) was used in the analysis and includes a peak ground acceleration of 0.15g for an approximate

10,000 year return period, with the mean seismic source being a magnitude (Mw) 5.81 event occurring 51.5 km from the site.

Based on the results of the liquefaction analysis, including assumed geotechnical material properties and site-specific estimations of ground acceleration, the tailings are not susceptible to earthquake-induced liquefaction. Computed factors of safety for an approximate 10,000 year return period range from 1.3 to 1.9. A detailed discussion of the liquefaction analyses performed is included in Appendix D.

3.3.9 Settlement

Settlement analyses were performed to evaluate the amount of tailings settlement expected to occur due to placement of the interim cover, dewatering, and subsequent construction of the final cover. Settlement of the tailings was modeled by applying loads corresponding to these loading conditions. Historic monitoring data from monitoring points in Cells 2 and 3 were used to estimate settlement parameters for calculation of future settlement. Material properties used in the analyses were obtained from laboratory test results or estimated based on historic monitoring data.

Settlement due to dewatering and placement of the interim cover is estimated to be approximately 2 inches in Cell 2, and approximately 10 inches in Cells 3, 4A and 4B. After placement of the interim cover, settlement monuments will be installed within Cells 3, 4A, and 4B. Monuments will be monitored on a regular basis in order to verify that most (90 percent) of the settlement due to dewatering and interim cover placement has occurred prior to construction of the final cover. The time required to reach 90 percent of total anticipated settlement ranges from approximately 2.5 to 4 years. Additional settlement due to placement of the final cover is estimated to be approximately 5 to 6 inches. The results of the analyses are summarized in Table 3.3-3. A detailed discussion of the settlement analyses performed for the ET cover is provided in Appendix D.

**Table 3.3-3
Estimate of Future Settlement in Tailings Cells**

Description	Cell 2	Cell 3	Cells 4A/4B
Total Settlement due to Interim Cover Placement and Dewatering	0.14 ft	0.83 ft	0.87 ft
Total Settlement due to Final Cover Placement	0.42 ft	0.38 ft	0.38 ft
Time to Reach 90% Consolidation	2.6 yrs	3.8 yrs	4.1 yrs

Note: Values presented in table are based on average consolidation parameters (C_c and c_v)

3.3.10 Soil Cover-Animal Intrusion

Based on a review of the wildlife survey data from the 1978 Environmental Report produced for the White Mesa site (Dames & Moore, 1978b), and a thorough literature review of burrowing depths and biointrusion studies, the maximum depth of on-site burrowing would be approximately one meter or slightly over three feet. Wildlife survey data for the site identify burrowing mammals as deer mice, kangaroo rats, chipmunks, desert cottontails, blacktailed jackrabbits, and prairie dogs. Other burrowing mammals, such as pocket gophers and badgers have not been observed in the area of the White Mesa site (Dames & Moore, 1978b). Of the list of burrowing mammals that may occur on the site, the prairie dog is the species capable of burrowing to the greatest depth. Studies by Shuman and Whicker (1986) and Cline et al. (1982) conducted in southeast Wyoming, Grand Junction, Colorado and Hanford, Washington, document maximum burrowing depths of prairie dogs between 60 and 100 cm. Based on this empirical data and the potential species that may use the site as habitat, any burrowing activity that may occur would be limited to about one meter below ground surface. In addition, prairie dog habitat is characterized by low plant cover and vegetation that is short in vertical stature (Holechek et al. 1998). The potential for prairie dogs colonizing the tailing cells is very low because plant cover and stature will not match their habitat preferences. A complete discussion of the evaluation of Biointrusion through the ET cover is presented in Appendix D.

3.3.11 Soil Cover Vegetation

The plant species proposed for the cover system consist of native perennial grasses and forbs. The use of these species in reclamation of the tailing cells should provide a permanent or sustainable plant cover because of the highly adapted nature of these species to existing site conditions, their tolerance to environmental stresses such as drought, fire, and herbivory, and their ability to effectively reproduce over time. These species can coexist and fully utilize plant resources to keep invasive weeds and deep rooted woody species from colonizing the site. Once established, the proposed seed mixture should produce a grass-forb community of highly adapted and productive species that can effectively compete with undesirable species, including shrubs and trees native to the area.

The proposed ET cover does not contain a biobarrier (e.g. cobble layer) to minimize potential intrusion by plant roots or burrowing animals. The proposed cover system is designed to minimize both plant root and burrowing animal intrusion through the use of thick layers of soil cover in combination with a highly compacted layer placed at a depth that is below the expected rooting and burrowing depths among species that may inhabit the site. Root growth into the highly compacted radon attenuation layer that begins at a depth of 122 cm will be restricted because of the high density of this material (compaction to 95 percent Standard Proctor). In addition, both root density and the size of roots decrease at a rapid rate with rooting depth, further decreasing the potential for root growth into the compacted radon attenuation layer of the cover system. Appendix D provides a complete discussion of cover vegetation.

3.3.12 Cover Material/Cover Material Volumes

The volume of materials required for construction of the interim cover, final cover, and erosion protection are provided in Table 3.3-4. The quantities of materials available for construction of the cover are also provided in Table 3.3-4. A summary of the volumes of borrow stockpiles is

provided in Appendix D. Sufficient quantities are available from on-site sources for the topsoil and random fill materials. The bedding and gravel materials would be obtained from off-site commercial sources. Three commercial sources have been identified as potential sources for the bedding and gravel materials, and these sources are described in further detail in Appendix D. Sufficient quantities of material are available from the off-site sources identified. Samples from each source were tested for durability in general accordance with guidelines for long-term performance outlined by the US Nuclear Regulatory Commission (NRC). These guidelines are for rock to be used for erosion protection material on exposed surfaces and utilize a rock scoring value (Johnson, 2002). Results of the durability testing are provided in Appendix D and were previously presented as Attachment H of the previous Reclamation Plan, Revision 4.0 (Denison, 2009a).

**Table 3.3-4
Reclamation Cover Material Quantity Summary**

Material	Quantity Required for Reclamation (cy)	Quantity Available (Identified Sources) (cy)
Topsoil (for Erosion Protection Layer)	226,000	284,100 (on-site stockpiles)
Gravel (1-inch minus for Erosion Protection Layer)	25,000	Sufficient quantity available (off-site commercial source)
Random Fill (total for water storage and radon attenuation cover layers)	3,398,000	3,522,000 (on-site stockpiles)
Riprap ($D_{50} = 7.4$ and 15 inch for side slopes and rock aprons)	54,000	Sufficient quantity available (off-site commercial source)
Riprap Bedding/Filter Layer	21,000 ¹	Sufficient quantity available (off-site commercial source)

Note:

1. Based on 6-inch thick medium sand bedding/filter layer beneath riprap.

4 MILL DECOMMISSIONING PLAN

The preliminary plans for decommissioning of the Mill are presented in MWH (2011a), and included as Appendix G to this Reclamation Plan. This information has been updated since the previous Reclamation Plan, Revision 4.0 (Denison, 2009a). The Decommissioning Plan attached as Appendix G includes a description of the following activities to be performed during the decommissioning process:

- development and implementation of health and safety procedures;
- execution of pre-decommissioning activities;
- demolition of above-ground and under-ground facilities, and placement of these materials in disposal Cell 1 or the last active tailings cell;
- excavation of contaminated subsoils from the process area and placement in disposal Cell 1 or the last active tailings cell;
- clean-up of windblown contamination and placement in disposal Cell 1 or the last active tailings cell; and
- regrading and revegetation.

The Plan further describes the requirements prior to demolition and the procedures to be used for specific locations within the process area, as well as requirements for personnel training, environmental monitoring, and management of water and contaminants. The work should be conducted under the Denison Radiation Protection Manual, as directed by the site Radiation Safety Officer.

The Denison Radiation Protection Manual for Reclamation is included as Attachment D to this Reclamation Plan.

REFERENCES

- Agenbroad, L. D. et. al., 1981. 1980 Excavations in White Mesa, San Juan County, Utah.
- Aki, K., 1979. Characterization of Barriers on an Earthquake Fault, *Journal of Geophysical Research*, v. 84, pp. 6140-6148.
- Algermissen, S. T. and Perkins, D. M., 1976. A Probabilistic Estimate of Maximum Acceleration on Rock in the Contiguous United States, U. S. Geological Survey Open-File Report, No. 76-416.
- Behle, W. H. and M. L. Perry, 1975. *Utah Birds*, Utah Museum of Natural History, University of Utah, Salt Lake City.
- Brill, K. G. and Nuttli, O. W., 1983. Seismicity of the Colorado Lineament, *Geology*, v. 11, pp. 20-24.
- Case, J. E. and Joesting, H. R., 1972. Regional Geophysical Investigations in the Central Plateau, U. S. Geological Survey Professional Paper 736.
- Casjens, L. A. et. al., 1980. Archeological Excavations on White Mesa, San Juan County, Utah, 1979; Volumes I through IV; June, 1980.
- Cater, F. W., 1970. Geology of the Salt Anticline Region in Southwestern Colorado, U. S. Geological Survey, Professional Paper 637.
- Cline, J. F., F. G. Burton, d. A. Cataldo, W. E. Shiens, and K. A. Gano. 1982. Long-term biobarriers to plant and animal intrusions of uranium mill tailings. Rep. PNL-4340. Pacific Northwest Lab. Richland, WA.
- Cook, K. L. and Smith, R. B., 1967. Seismicity in Utah, 1850 Through June 1965, *Bull. Seism. Soc. Am.*, v. 57, pp. 689-718.
- Craig, L. C., Holmes, C.N., Cadigan, R.A., Freeman, V.L., Mullens, T.E., and Weir, G.W., 1955. Stratigraphy of the Morrison and Related Formations, Colorado Plateau Region, a Preliminary Report, U. S. Geological Survey Bulletin 1009-E, pp. 125-168.
- Dames and Moore, 1978a. Site Selection and Design Study - Tailing Retention and Mill Facilities, White Mesa Uranium Project, January 17, 1978.

Dames and Moore, 1978b. Environmental Report, White Mesa Uranium Project, San Juan County, Utah, January 20, 1978, revised May 15, 1978.

Denison Mines (USA) Corp. Semi-Annual Effluent Reports (January through June, 2008), (June through December, 2008) and (January through June, 2009), for the White Mesa Mill.

Denison Mines (USA) Corp, February 28, 2007. White Mesa Uranium Mill License Renewal Application State of Utah Radioactive Materials License No. UT1900479.

Denison Mines (USA) Corp, February 28, 2007. White Mesa Uranium Mill Environmental Report In Support of the License Renewal Application State of Utah Radioactive Materials License No. UT1900479.

Denison Mines USA Corp. (Denison), 2008. Stormwater Best Management Practices Plan, White Mesa Mill, Blanding Utah, Revision 1.3, June 12.

Denison Mines USA Corp. (Denison), 2009a. Reclamation Plan, White Mesa Mill, Blanding Utah, Revision 4.0, November.

Denison Mines USA Corp. (Denison), 2009b. Sampling Plan for Seeps and Springs in the Vicinity of the White Mesa Uranium Mill, Revision 0, March 17.

Denison Mines USA Corp. (Denison), 2011a. Spill Prevention, Control, and Countermeasures Plan for Chemicals and Petroleum Products, White Mesa Mill.

Denison Mines (USA) Corp. (Denison), 2011b. White Mesa Mill – Standard Operating Procedures, Book #11, Environmental Protection Manual. January.

Eardly, A. J., 1958. Physiography of Southeastern Utah in Intermountain Association Petroleum Geologists Guidebook, 9th Annual Field Conference, Geology of the Paradox Basin, pp. 10-15.

GEO-SLOPE International Ltd, 2007. Slope/W, Version 7.17, Calgary, Alberta.

Geosyntec Consultants (Geosyntec), 2007a. Analysis of Slimes Drain (Cell 4A). May 11.

Geosyntec Consultants (Geosyntec), 2007b. Analysis of Slimes Drain (Cell 4B). August 30.

Grose, L. T., 1972. Tectonics, in Geologic Atlas of the Rocky Mountain Region Rocky Mountain Association Geologists, Denver, Colorado, pp. 35-44.

Hadsell, F. A., 1968. History of Earthquakes in Colorado, in Hollister, J. S. and Weimer, R. J., eds., Geophysical and Geological Studies of the Relationships Between the Denver

- Earthquakes and the Rocky Mountain Arsenal Well, Colorado School Mines Quarterly, v. 63, No. 1, pp. 57-72.
- Harbaugh, A.W., Banta, E.R., Hill, M.C., and McDonald, M.G., 2000. MODFLOW-2000, the U.S. Geological Survey modular ground-water model -- User guide to modularization concepts and the Ground-Water Flow Process: U.S. Geological Survey Open-File Report 00-92, 121 p.
- Haynes, D.D., Vogel, J.D., and Wyant, D.G., 1972, "Geology, Structure and Uranium Deposits of the Cortez Quadrangle, Colorado and Utah." U.S. Geological Survey, Miscellaneous Investigation Series, Map, I-629, May.
- Hermann, R. B., Dewey, J. W., and Park, S. F., 1980. The Dulce, New Mexico, Earthquake of January 23, 1966, Seismological Society of America Bulletin, v. 70, No. 6, pp. 2171-2183.
- Hintze, et al. 2000. Digital Geologic Map of Utah. Utah Geological Survey.
- Hite, R. J., 1975. An Unusual Northeast-trending Fracture Zone and its Relation to Basement Wrench Faulting in Northern Paradox Basin, Utah and Colorado, Four Corners Geological Society 8th Field Conference Guidebook, Durango, Colorado, pp. 217-223.
- Holechek, J.L., R.D. Pieper, and C.H. Herbel. 1998. Range Management Principles and Practices. Prentice Hall, Upper Saddle River, NJ.
- Huff, L. D., and F. G. Lesure, 1965. Geology and Uranium Deposits of Montezuma Canyon Area, San Juan County, Utah, U. S. Geological Survey Bulletin 1190, 102 p.
- Hydro Geo Chem, Inc. (HGC), 2007. Draft Letter to Steven Landau, Denison Mines (USA) Corporation, Denver, Colorado, December 19, 2007.
- Hydro Geo Chem, Inc. (HGC), August 27, 2009a. Site Hydrogeology and Estimation of Groundwater Travel Times in the Perched Zone, White Mesa Uranium Mill Site Near Blanding, Utah.
- Hydro Geo Chem, Inc. (HGC) 2009b. Letter Report to Mr. David Frydenlund, Esq. Denison Mines (USA) Corporation, November 3.
- Hydro Geo Chem, Inc. (HGC) 2010a. Installation and Testing of Perched Monitoring Wells MW-33, MW-34, and MW-35. White Mesa Uranium Mill Near Blanding, Utah.

- Hydro Geo Chem, Inc. (HGC), 2010b. Hydrogeology of the Perched Groundwater Zone and Associated Seeps and Springs Near the White Mesa Uranium Mill Site. November 12.
- INTERA, Inc., 2007. Revised Background Groundwater Quality Report: Existing Wells For Denison Mines (USA) Corp.'s White Mesa Mill Site, San Juan County, Utah. October.
- INTERA, Inc., 2007. Revised Addendum: -- Evaluation of Available Pre-Operational and Regional Background Data, Background Groundwater Quality Report: Existing Wells For Denison Mines (USA) Corp.'s White Mesa Mill Site, San Juan County, Utah. November 16.
- INTERA, Inc., 2008. Revised Addendum: -- Background Groundwater Quality Report: New Wells For Denison Mines (USA) Corp.'s White Mesa Mill Site, San Juan County, Utah. April 30.
- Johnson, H. S., Jr., and W. Thordarson, 1966. Uranium Deposits of the Moab, Monticello, White Canyon, and Monument Valley Districts, Utah and Arizona, U. S. Geological Survey Bulletin 1222-H, 53 p.
- Johnson, T.L., 2002. "Design of Erosion Protection for Long-Term Stabilization." U.S. Nuclear Regulatory Commission (NRC), *NUREG-1623*. September.
- Kelley, V. C., 1955. Regional Tectonics of the Colorado Plateau and Relationship to the Origin and Distribution of Uranium, New Mexico University Publication Geology No. 5, 120 p.
- Kelley, V. C., 1956.
- Kirby, 2008. Geologic and Hydrologic Characterization of the Dakota-Burro Canyon Aquifer Near Blanding, San Juan County, Utah. Utah Geological Survey Special Study 123.
- Kirkham, R. M. and W. P. Rogers, 1981. Earthquake Potential in Colorado, A Preliminary Evaluation, Colorado Geological Survey, Bulletin 43.
- Knight-Piesold LLC, 1998. Evaluation of Potential for Tailings Cell Discharge – White Mesa Mill. November 23
- Lindsay, L. M. W., 1978. Archeological Test Excavations on White Mesa, San Juan County, Southeastern Utah.
- McDonald, M.G., and A.W. Harbaugh, 1988. A Modular Three-Dimensional Finite-Difference Ground-Water Flow Model: U.S. Geological Survey Techniques of Water-Resources Investigations, book 6, chap. A1, 586 p.

- McVehil-Monnett Associates, Inc., 2010. Semi-Annual Monitoring Report July 1 – July 1, 2010, White Mesa Mill Meteorological Station. August 19.
- MWH Americas, Inc. (MWH), 2007. Denison Mines (USA) Corp. Infiltration and Contaminant Transport Modeling Report, White Mesa Mill Site, Blanding, Utah. Report prepared for Denison Mines. November.
- MWH Americas, Inc. (MWH), 2010. Denison Mines (USA) Corp. Revised Infiltration and Contaminant Transport Modeling Report, White Mesa Mill Site, Blanding, Utah. Report prepared for Denison Mines. March.
- MWH Americas, Inc. (MWH), 2011a. Preliminary Mill Decommissioning Plan. September.
- MWH Americas, Inc. (MWH), 2011b. Denison Mines (USA) Corp. Draft Updated Tailings Cover Design Report. September.
- National Oceanic and Atmospheric Administration (NOAA), 1977. Probable Maximum Precipitation Estimates, Colorado River and Great Basin Drainages. Hydrometeorological Report (HMR) No. 49.
- National Council on Radiation Protection and Measurements (NCRP), 1987. Exposure of the Population in the United States and Canada from Natural Background Radiation. Report No. 94.
- Nielson, A. S., 1979. Additional Archeological Test Excavations and Inventory on White Mesa, San Juan County, Southeastern Utah.
- NUREG 1620, 2003. Standard Review Plan for the Review of a Reclamation Plan for Mill Tailings Sites Under title II of the Uranium Mill Tailings Radiation Control Act of 1978. Revision 1.
- NUREG/CR-3533, February 1984. Radon Attenuation Handbook for Uranium Mill Tailings Cover Design.
- NUREG/CR-4520, April 1986. Predictive Geochemical Modeling of Contaminant Concentrations in Laboratory Columns and in Plumes Migrating from Uranium Mill Tailings Waste Impoundments.
- NUREG/CR-4620, June, 1986. Methodologies for Evaluating Long-Term Stabilization Designs of Uranium Mill Tailings Impoundments, J. D. Nelson, S. R. Abt., et. al.
- Shoemaker, E. M., 1954. Structural Features of Southeastern Utah and Adjacent Parts of Colorado, New Mexico, and Arizona. Utah Geological Society Guidebook to the Geology of Utah, No. 9, pp. 48-69.

- Shoemaker, E.M., 1956, "Structural Features of the Colorado Plateau and Their Relation to Uranium Deposits." U.S. Geological Survey Professional Paper 300, p. 155-168.
- Shuman, R. and F. W. Whicker, 1986. Intrusion of reclaimed uranium mill tailings by prairie dogs and ground squirrels. *J. Environmental Quality* 15:21-24.
- Simunek, J., M. Sejna, H. Saito, M. Sakai, and M. Th. van Genuchten, 2009. The HYDRUS-1D Software Package for Simulating the Movement of Water, Heat, and Multiple Solutes in Variably Saturated Media, Version 4.08, HYDRUS Software Series 3, Department of Environmental Sciences, University of California – Riverside, Riverside, CA. pp. 240.
- Smith, R. B., 1978. Seismicity, Crustal Structure, and Intraplate Tectonics of the Western Cordillera, in *Cenozoic Tectonics and Regional Geophysics of the Western Cordillera*. Smith, R. B. and Eaton, G. P., eds, Memoir 152, Geological Society of America, pp. 111-144.
- Streng, D.L. and T.J. Bander. 1981. MILDOS – A Computer Program for Calculating Environmental Radiation Dose from Uranium Recovery Operations. NUREG/CR-2011, PNL-3767, April.
- Stokes, W. L., 1967. A Survey of Southeastern Utah Uranium Districts, Utah Geological Society Guidebook to the Geology of Utah, No. 21, pp. 1-11.
- Telco Environmental, 2011. National Emission Standards for Hazardous Air Pollutants Radon Flux Measurement Program, White Mesa Mill Site.
- Tetra Tech, Inc. (formerly MFG, Inc.). 2006. White Mesa Uranium Facility, Cell 4 Seismic Study, Blanding, Utah. November 27.
- Tetra Tech, Inc., 2010. White Mesa uranium Facility. Seismic Study Update for a Proposed Cell, Blanding, Utah. February 3.
- Thompson, K. C., 1967. Structural Features of Southeastern Utah and Their Relations to Uranium Deposits, Utah Geological Society Guidebook to the Geology of Utah, No. 21, pp. 23-31.
- Titan Environmental Corporation, 1994a. Hydrogeologic Evaluation of White Mesa Uranium Mill, July 1994.
- Titan Environmental Corporation, 1994b. Points of Compliance, White Mesa Uranium Mill, September 1994.

- Titan Environmental Corporation, 1996. Tailings Cover Design, White Mesa Mill, October 1996.
- Umetco, 1987. Umetco Minerals Corporation SUA-1358: Docket No. 40-8681, License Condition 48, White Mesa Mill, Utah, Letter From R. K. Jones to U. S. Nuclear Regulatory Commission dated November 30, 1987.
- Umetco Minerals Corporation, 1992, "Ground Water Study, White Mesa Mill, Blanding, Utah," License SUA 1358, Docket No. 40-8681.
- Umetco Minerals Corporation and Peel Environmental Services, 1993. Groundwater Study, White Mesa Facilities, Blanding, Utah.
- University of Utah, Department of Geophysics (T. Grant Hurst and D. Kip Solomon), May 2008. Summary of work completed, data results, interpretations and recommendations for the July 2007 Sampling Event at the Denison Mines, USA, White Mesa Uranium Mill Near Blanding Utah.
- UNSCEAR, 2000. Sources and Effects of Ionising Radiation, Report to the General Assembly, with Scientific Annexes, Volume 1 Sources, United Nations, New York. United Nations Scientific Committee on the Effects of Atomic Radiation.
- U.S. Department of Energy, 1988. Effect of Freezing and Thawing on UMTRA Covers, Albuquerque, New Mexico, October.
- U.S. Department of Energy, 1989. Technical Approach Document, Revision II, UMTRA-DOE/AL 050425.0002, Uranium Mill Tailings Remedial Action Project, Albuquerque, New Mexico.
- U.S. Department of Energy, 1993, "Environmental Assessment of Remedial Action at the Slick Rock Uranium Mill Tailings Sites, Slick Rock, Colorado." UMTRA Project Office, Albuquerque, New Mexico, February.
- U.S. Environmental Protection Agency (EPA), 1994. The Hydrologic Evaluation of Landfill Performance (HELP) Model, Version 3, EPA/600/R-94/168b, September.
- U. S. Nuclear Regulatory Commission, 1979. *A Final Environmental Statement Related to Operation of White Mesa Uranium Project, Energy Fuels Nuclear, Inc.*, NUREG-0556. May.
- U. S. Nuclear Regulatory Commission (NRC), 1989. Regulatory Guide 3.64 (Task WM-503-4) Calculation of Radon Flux Attenuation by Earthen Uranium Mill Tailings Covers, March.

- U.S. Nuclear Regulatory Commission, 1994. Background as a Residual Radioactivity Criterion for Decommissioning.
- U.S. Nuclear Regulatory Commission (NRC), 1990. "Final Staff Technical Position, Design of Erosion Protective Covers for Stabilization of Uranium Mill Tailings Sites," August.
- U.S. Nuclear Regulatory Commission, Division of Fuel Cycle Safety and Safeguards, Office of Nuclear Material Safety and Safeguards, 2000. Environmental Assessment For the Reclamation Plan for the White Mesa Mill.
- U.S. Nuclear Regulatory Commission, Division of Fuel Cycle Safety and Safeguards, Office of Nuclear Material Safety and Safeguards, August 22, 2002. Environmental Assessment For International Uranium (USA) Corporation's Uranium Mill Site White Mesa, San Juan County, Utah, In Consideration Of An Amendment To Source Material License SUA-1358 For The Receipt And Processing Of The Maywood Alternate Feed.
- U.S. Nuclear Regulatory Commission (NRC), 2002. Regulatory Guide 8.31, Information Relevant to Ensuring that Occupational Radiation Exposures at Uranium Recovery Facilities will be As Low As is Reasonable Achievable, Revision 1, May.
- U.S. Nuclear Regulatory Commission (NRC), 2003. Standard Review Plan for the Review of a Reclamation Plan for Mill Tailings Sites under Title II of the Uranium Mill Tailings Radiation Control Act of 1978. NUREG-1620, Revision 1, June.
- U.S. Nuclear Regulatory Commission, 2007. Regulatory Guide 4.15. Quality Assurance for Radiological Monitoring Programs (Inception Through Normal Operations to License Termination), Effluent Streams and the Environment, Rev. 2.
- Utah Department of Environmental Quality, Division of Radiation Control, 2004. Statement of Basis for a Uranium Milling Facility at White Mesa, South of Blanding, Utah, Owned and Operated by International Uranium (USA) Corporation. December 1.
- Utah Department of Environmental Quality, Utah Division of Radiation Control (DRC). 2008. Email correspondence between David Rupp and Greg Corcoran regarding items noted during drain construction inspection, Cell 4A. June 25 – July 2.
- Utah Department of Environmental Quality, Division of Radiation Control (DRC), 2010. Denison Mines (USA) Corporation Reclamation Plan, Revision 4.0, November 2009; Interrogatories – Round 1. September.
- Utah Department of Environmental Quality, Division of Radiation Control (DRC), 2011. Denison Mines (USA) Corporation Reclamation Plan, Revision 4.0, November 2009; Interrogatories – Round 1A. April.

- von Hake, C. A., 1977. Earthquake History of Utah, Earthquake Information Bulletin 9, pp. 48-51.
- Warner, L. A., 1978. The Colorado Lineament, A Middle Precambrian Wrench Fault System, Geological Society of America Bulletin, v. 89, pp. 161-171.
- Witkind, I. J., 1964. Geology of the Abajo Mountains Area, San Juan County, Utah, U. S. Geological Survey, Professional Paper 453.
- Wong, I. G., 1981. Seismological Evaluation of the Colorado Lineament in the Intermountain Region (abs.), Earthquake Notes, v. 53, pp. 33-34.
- Wong, I. G., 1984. Seismicity of the Paradox Basin and the Colorado Plateau Interior, ONWI-492, Prepared for the Office of Nuclear Waste Isolation, Battelle Memorial Institute.
- Youd, T., Idriss, I., Andrus, R., Arango, I., Castro, G., Christian, J., Dobry, R., Liam Finn, W., Harder, L., Hynes, M., Ishihara, K., Koester, J., Liao, S., Marcuson, W., Martin, G., Mitchell, J., Moriwaki, Y., Power, M., Robertson, P., Seed, R., Stokoe, K., 2001. Liquefaction Resistance of Soils: Summary report from the 1996 NCEER and 1998 NCEER/NSF Workshops of Evaluation of Liquefaction Resistance of Soils, Journal of Geotechnical and Geoenvironmental Engineering, October.
- Yuan, Y. C., J. H. C. Wang, and A. Zielen, 1998, "MILDOS-AREA: An Enhanced Version of MILDOS for Large-Area Sources," ANL/ES-161.
- Zoback, M. D. and Zoback, M. L., 1980. State of Stress in the Conterminous United States, Journal of Geophysical Research, v. 85, pp. 6113-6156.